



SHEET 2 OF 3

BECHTEL PROJECT NO.: 25409				MACTEC PROJECT NO.: 6468-07-1950				COUNTY: Miami-Dade		GEOLOGIST: J. Liles				
SITE DESCRIPTION: Turkey Point COL				DRILL MACHINE: CME-550 (Miller)				DRILLER: R. White/ J. Dugger/ C. White				GROUND WATER (ft)		
BORING NO.: B-702				DRILL METHOD: Mud Rotary/ Core				SAMPLE METHODS: SPT/Core				0 HR. NA		
GROUND ELEV.: -1.2 ft (NAVD88)				NORTHING: 397,018 US ft (NAD83/90)				EASTING: 875,746 US ft (NAD83/90)				24 HR. NA		
TOTAL DEPTH: 202.5 ft		BORING DIAMETER: 4" to 25.0', 3" to 202.5'				CASING DEPTH: 4" to 25.0', 3" to 122.9'				HAMMER (ID):140 lb. Auto (M06)				
DATE STARTED: 2/26/08		COMPLETED: 3/6/08				CORE SIZE: HQ3				BITS USED: 2 7/8" Roller Cone				
ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT						SAMP NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
		0.5ft	0.5ft	0.5ft	0	20	40	60	80	100				
-76.0					Continued from previous page									
-80.1	78.9													73.9ft: hard, few vugs LIMESTONE, boundstone, white (2.5Y8/1), hard, extremely indurated, fossiliferous, some vugs, strong HCl reaction (Lower Fort Thompson Formation) (continued) 78.9ft: moderately hard, trace vugs
-85.1	83.9													83.9ft: hard
-90.1	88.9													88.9ft: moderately hard, little vugs
-95.1	93.9													93.9ft: moderately indurated
-100.1	98.9													98.9ft: indurated, some vugs, little shell molds and casts
-105.1	103.9													
-110.1	108.9													
-115.1	113.9													113.9ft: white (5Y8/1), trace vugs, shell molds and casts
-120.1	118.9													118.9ft: white (5Y8/1), trace vugs, shell molds and casts
-120.4	119.2	1	2	1										119.2ft: Switch sampling method to SPT
-125.4	124.2	2	2	2										119.2ft: loose, trace shells, limestone fragments, trace silt
-132.3	131.1	1	4	5										131.1ft: POORLY GRADED SAND with silt (SP-SM), light gray (5Y7/1), very loose, wet, fine grained sand, few fines, trace limestone fragments, strong HCl reaction
-137.3	136.1	5	7	4										136.1ft: Silty SAND (SM), greenish gray (10YR6/1), loose, wet, fine grained sand, few fines, strong HCl reaction
-142.2	141.0	6	5	7										136.1ft: medium dense, few limestone fragments, trace shell fragments
-147.2	146.0	5	5	9										

TURKEY POINT COL BORE TURKEY POINT COL GDT 5/30/08



BECHTEL PROJECT NO.: 25409					MACTEC PROJECT NO.: 6468-07-1950					COUNTY: Miami-Dade			GEOLOGIST: J. Liles				
SITE DESCRIPTION: Turkey Point COL					DRILL MACHINE: CME-550 (Miller)					DRILLER: R. White/ J. Dugger/ C. White					GROUND WATER (ft)		
BORING NO.: B-702					DRILL METHOD: Mud Rotary/ Core					SAMPLE METHODS: SPT/Core					0 HR. NA		
GROUND ELEV.: -1.2 ft (NAVD88)					NORTHING: 397,018 US ft (NAD83/90)					EASTING: 875,746 US ft (NAD83/90)					24 HR. NA		
TOTAL DEPTH: 202.5 ft			BORING DIAMETER: 4" to 25.0', 3" to 202.5'					CASING DEPTH: 4" to 25.0', 3" to 122.9'					HAMMER (ID): 140 lb. Auto (M06)				
DATE STARTED: 2/26/08			COMPLETED: 3/6/08			CORE SIZE: HQ3			BITS USED: 2 7/8" Roller Cone								
ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT						SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
		0.5ft	0.5ft	0.5ft	0	20	40	60	80	100							
-150.8					Continued from previous page												
-152.3	151.1	4	7	11							702-18			Silty SAND (SM), greenish gray (10YR6/1), loose, wet, fine grained sand, few fines, strong HCl reaction (continued) 151.1ft: greenish gray (10Y5/1), little fines			
-157.3	156.1	3	3	5							702-19			156.1ft: loose			
-167.3	166.1	2	4	7							702-20			166.1ft: medium dense			
-177.4	176.2	1	1	1							702-21			177.4	SILT with sand (ML), greenish gray (10Y5/1), very loose, wet, fine to medium grained sand, strong HCl reaction		
-190.4	189.2	1	1	4							702-22			189.2	189.2ft: loose, trace clay		
-197.4	196.2	1	1	1							702-23			197.4	Clayey SAND (SC), greenish gray (10Y5/1), very loose, wet, fine grained sand, some fines, strong HCl reaction		
-202.2	201.0	5	7	10							702-24			201.2	SILT with sand (ML), greenish gray (10Y5/1), very loose, wet, fine grained sand, strong HCl reaction		
														203.7	LEAN CLAY with sand (CL), greenish gray (10Y5/1), very stiff, wet, little fine grained sand, strong HCl reaction Boring Terminated at Elevation -203.7 ft		



SHEET 1 OF 2

BECHTEL PROJECT NO.: 25409				MACTEC PROJECT NO.: 6468-07-1950				COUNTY: Miami-Dade		GEOLOGIST: J. Liles		
SITE DESCRIPTION: Turkey Point COL				DRILL MACHINE: CME-550 (Miller)				DRILLER: R. White/ J. Dugger/ C. White			GROUND WATER (ft) 0 HR. NA 24 HR. NA	
BORING NO.: B-702				DRILL METHOD: Mud Rotary/ Core				SAMPLE METHODS: SPT/Core				
GROUND ELEV.: -1.2 ft (NAVD88)				NORTHING: 397,018 US ft (NAD83/90)				EASTING: 875,746 US ft (NAD83/90)				
TOTAL DEPTH: 202.5 ft				CASING DEPTH: 4" to 25.0', 3" to 122.9'						HAMMER (ID): 140 lb. Auto (M06)		
DATE STARTED: 2/26/08		COMPLETED: 3/6/08		CORE SIZE: HQ3		CORE BARREL TYPE: Triple Tube Wireline (Split inner liners)						
ELEV. (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		L O G	DESCRIPTION AND REMARKS		
				REC (ft) %	RQD (ft) %		REC (ft) %	RQD (ft) %				
										Begin Coring @ 35.9 ft		
-37.1	35.9	3.0	2:18	(3.0)	(2.8)	RUN-1	(11.5)	(10.1)		LIMESTONE, boundstone, white (2.5Y8/1), hard, extremely indurated, strong HCl reaction, coralline, few vugs (continued)		
-40.1	38.9		2:29	100%	93%		100%	88%				
		5.0	2:12	(5.0)	(4.2)	RUN-2				38.9ft: trace shell fragments, fossiliferous		
			2:25	100%	84%					42.0ft: loss of circulation		
-45.1	43.9		2:03							43.9ft: light gray (10YR7/1) to 47.4ft		
		5.0	1:51									
			2:22									
		5.0	2:32	(4.3)	(3.5)	RUN-3						
			2:16	86%	70%							
			1:28									
-50.1	48.9		1:50				(53.4)	(37.7)		LIMESTONE, boundstone, white (2.5Y8/1), hard, extremely indurated, fossiliferous, some vugs, strong HCl reaction (Lower Fort Thompson Formation)		
		5.0	0:55				79%	56%				
			1:49	(5.0)	(4.6)	RUN-4						
			1:35	100%	92%							
			1:29									
-55.1	53.9		1:36									
		5.0	2:05									
			0:00	(2.6)	(1.3)	RUN-5				53.9ft: medium hard to moderately hard, moderately indurated to indurated, trace vugs		
			0:32	52%	26%					54.0 to 55.0ft: soft zone		
-60.1	58.9		1:08									
		5.0	3:35									
			1:34									
			1:19	(5.0)	(3.5)	RUN-6				58.9ft: moderately hard, moderately indurated, little vugs		
			1:00	100%	70%							
			1:20									
-65.1	63.9		1:07									
		5.0	1:44									
			2:10	(2.0)	(1.6)	RUN-7				63.9ft: light gray (5Y7/1), hard, indurated, few vugs		
			1:20	40%	32%					65.0 to 69.0ft: soft zone		
			0:25									
-70.1	68.9		0:20									
		5.0	0:30									
			1:07	(4.7)	(4.0)	RUN-8				68.9ft: white (2.5Y8/1), moderately hard, some vugs		
			2:18	94%	80%							
-75.1	73.9		3:08			702-CS-01						
		5.0	2:03									
			2:15			702-CS-02						
			2:18	(4.2)	(3.5)	RUN-9				73.9ft: hard, few vugs		
			1:44	84%	70%							
-80.1	78.9		2:18									
		5.0	1:23									
			1:00									
			0:57	(4.0)	(1.7)	RUN-10				78.9ft: moderately hard, trace vugs		
			0:43	80%	34%							
-85.1	83.9		0:40									
		5.0	0:45									
			0:40									
			0:30	(4.5)	(3.3)	RUN-11				83.9ft: hard		
			0:31	90%	66%							
-90.1	88.9		1:30									
		5.0	1:25			702-CS-03						
			1:38									
			0:51	(4.6)	(3.0)	RUN-12				88.9ft: moderately hard, little vugs		
			0:55	92%	60%							
-95.1	93.9		1:04									
		5.0	0:48									
			0:39									
			0:33	(1.5)	(0.4)	RUN-13				93.9ft: moderately indurated		
			0:12	30%	8%							
-100.1	98.9		0:13									
		5.0	0:14									
			0:47									
			0:23	(4.4)	(3.9)	RUN-14				98.9ft: indurated, some vugs, little shell molds and casts		
			0:33	88%	78%							
-105.1	103.9		0:35									
		5.0	0:28			702-CS-04						
			0:38									
			0:23	(4.8)	(3.3)	RUN-15						
			0:28	96%	66%							
-110.1	108.9		0:19									
		5.0	0:28									
			0:22									
			0:18	(4.4)	(3.2)	RUN-16						
			0:19									

TURKEY POINT COL CORE TURKEY POINT GPJ TURKEY POINT COL GDI 5 30/08




SHEET 2 OF 2


BECHTEL PROJECT NO.: 25409	MACTEC PROJECT NO.: 6468-07-1950	COUNTY: Miami-Dade	GEOLOGIST: J. Liles
SITE DESCRIPTION: Turkey Point COL	DRILL MACHINE: CME-550 (Miller)	DRILLER: R. White/ J. Dugger/ C. White	GROUND WATER (ft)
BORING NO.: B-702	DRILL METHOD: Mud Rotary/ Core	SAMPLE METHODS: SPT/Core	0 HR. NA
GROUND ELEV.: -1.2 ft (NAVD88)	NORTHING: 397,018 US ft (NAD83/90)	EASTING: 875,746 US ft (NAD83/90)	24 HR. NA
TOTAL DEPTH: 202.5 ft	CASING DEPTH: 4" to 25.0', 3" to 122.9'	HAMMER (ID): 140 lb. Auto (M06)	
DATE STARTED: 2/26/08	COMPLETED: 3/6/08	CORE SIZE: HQ3	CORE BARREL TYPE: Triple Tube Wireline (Split inner liners)

ELEV. (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		L O G	DESCRIPTION AND REMARKS
				REC (ft) %	RQD (ft) %		REC (ft) %	RQD (ft) %		
										Continued from previous page
-115.1	113.9		0:19 0:28 1:08	88%	64%					LIMESTONE, boundstone, white (2.5Y8/1), hard, extremely indurated, fossiliferous, some vugs, strong HCl reaction (Lower Fort Thompson Formation) (continued)
		5.0	1:00 0:23 0:39 0:16 0:12	(0.9) 18%	(0.0) 0%	RUN-17	(0.3) 7%	(NA)		113.9ft: white (5Y8/1), trace vugs, shell molds and casts
-120.1	118.9									POORLY GRADED GRAVEL with silt and gravel (SP-SM), light gray (5Y7/1), wet, fine to coarse grained sand, fine to coarse limestone gravel fragments, strong HCl reaction (Tamiami Formation)
-120.4	119.2	0.3	0:20/0.3	(0.3) 100%	(0.0) 0%	RUN-18				119.2
										Coring Terminated at Elevation -120.4


TURKEY POINT COL CORE TURKEY POINT GPJ TURKEY POINT COL GDT 5/30/08




B-702 - Box 1




B-702 - Box 2




B-702 - Box 3



B-702 - Box 4



B-702 – Box 5



B-702 – Box 6



GEOTECHNICAL BORING LOG

Prepared By 2276 Date 8-19-08

Checked By 502 Date 8/19/08

SHEET 1 OF 3

BECHTEL PROJECT NO.: 25409					MACTEC PROJECT NO.: 6468-07-1950					COUNTY: Miami-Dade			GEOLOGIST: J. Liles				
SITE DESCRIPTION: Turkey Point COL					DRILL MACHINE: CME-550 (Miller)					DRILLER: R. White/ J. Dugger					GROUND WATER (ft)		
BORING NO.: B-703					DRILL METHOD: Mud Rotary/ Core					SAMPLE METHODS: SPT/Core					0 HR. NA		
GROUND ELEV.: -1.3 ft (NAVD88)					NORTHING: 397,018 US ft (NAD83/90)					EASTING: 875,846 US ft (NAD83/90)					24 HR. NA		
TOTAL DEPTH: 150.0 ft			BORING DIAMETER: 4" to 27.9', 3" to 150.0'					CASING DEPTH: 4" to 27.9', 3" to 115.0'					HAMMER (ID):140 lb. Auto (M06)				
DATE STARTED: 2/22/08			COMPLETED: 2/25/08			CORE SIZE: HQ3			BITS USED: 2 7/8" Roller Cone								
ELEV.	DEPTH	BLOW COUNT			BLOWS PER FOOT					SAMP.	LOG	SOIL AND ROCK DESCRIPTION					
(ft)	(ft)	0.5ft	0.5ft	0.5ft	0	20	40	60	80	100			NO.				
-1.3					Ground Surface												
-1.3	0.0	WOH	WOH	WOH							703-1	-1.3					
-3.8	2.5										703-2A&B						
		WOH	6	17								-4.6					
-6.5	5.2										703-3	2.5ft: soft					
		2	7	8								LIMESTONE, boundstone, white (2.5Y8/1), soft, wet, friable to moderately indurated, strong HCl reaction (Miami Formation)					
-9.1	7.8										703-4	5.2ft: very soft, oolitic					
		2	3	5													
-11.2	9.9										703-5	9.9ft: white (5Y8/1)					
		1	4	5													
-13.6	12.3										703-6						
		1	3	5													
-16.3	15.0										703-7	15.0ft: hard					
		20	22	50/0.2							RUN-1	16.2ft: Switch sampling method to coring					
-17.5	16.2											16.2ft: white (5Y8/1), soft, friable to moderately indurated, strong HCl reaction, locally interconnected vugs, oolitic					
											RUN-2	18.8ft: trace shell fragments					
-20.1	18.8																
											RUN-3						
-25.1	23.8											-26.3					
												25.0					
-30.1	28.8										RUN-4	LIMESTONE, boundstone, white (5Y8/1), moderately hard, indurated, coralline, little vugs (Upper Fort Thompson Formation)					
												28.8ft: white (2.5Y8/1), hard, recrystallized calcite, fossiliferous					
-34.1	32.8										RUN-5	31.0ft: loss of circulation					
-39.1	37.8										RUN-6	37.8ft: white (2.5Y8/1) to 39.0ft, then bluish gray (5PB6/1) to 42.8ft					
-44.1	42.8										RUN-7	-44.1					
												42.8					
-49.1	47.8										RUN-8	LIMESTONE, boundstone, white (2.5Y8/1), hard, indurated, few vugs, fossiliferous, trace shell molds and casts (Lower Fort Thompson Formation)					
-54.1	52.8										RUN-9	52.8ft: little vugs					
-59.1	57.8										RUN-10						
-64.1	62.8										RUN-11						
-69.1	67.8										RUN-12	67.8ft: white (10YR8/1), few vugs					
-74.1	72.8										RUN-13						

TURKEY POINT COL BORE TURKEY POINT.GPJ TURKEY POINT COL.GPJ 8-18-08



SHEET 2 OF 3

BECHTEL PROJECT NO.: 25409					MACTEC PROJECT NO.: 6468-07-1950					COUNTY: Miami-Dade			GEOLOGIST: J. Liles				
SITE DESCRIPTION: Turkey Point COL					DRILL MACHINE: CME-550 (Miller)					DRILLER: R. White/ J. Dugger					GROUND WATER (ft)		
BORING NO.: B-703					DRILL METHOD: Mud Rotary/ Core					SAMPLE METHODS: SPT/Core					0 HR. NA		
GROUND ELEV.: -1.3 ft (NAVD88)					NORTHING: 397,018 US ft (NAD83/90)					EASTING: 875,846 US ft (NAD83/90)					24 HR. NA		
TOTAL DEPTH: 150.0 ft			BORING DIAMETER: 4" to 27.9', 3" to 150.0'					CASING DEPTH: 4" to 27.9', 3" to 115.0'					HAMMER (ID):140 lb. Auto (M06)				
DATE STARTED: 2/22/08			COMPLETED: 2/25/08			CORE SIZE: HQ3			BITS USED: 2 7/8" Roller Cone								
ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT						SAMP. NO.	LOG MOI	LOG	SOIL AND ROCK DESCRIPTION			
		0.5ft	0.5ft	0.5ft	0	20	40	60	80	100							
-76.1					Continued from previous page												
-79.1	77.8										RUN-14			LIMESTONE, boundstone, white (2.5Y8/1), hard, indurated, few vugs, fossiliferous, trace shell molds and casts (Lower Fort Thompson Formation) (continued)			
-84.1	82.8										RUN-15						
-89.1	87.8										RUN-16			87.8ft: moderately hard			
-94.1	92.8										RUN-17			92.8ft: little vugs, little shell molds and casts			
-99.1	97.8										RUN-18			97.8ft: hard			
-104.1	102.8										RUN-19			102.8ft: few shell molds and casts			
-109.1	107.8										RUN-20			107.8ft: POORLY GRADED SAND with silt (SP-SM), light gray (5Y7/1), loose, wet, fine grained sand, few carbonate nodules, strong HCl reaction (Tamiami Formation)			
-115.0	113.7													113.7ft: Switch sampling method to SPT			
-119.9	118.6	3	4	2							703-8			118.6ft: white (5Y8/1), very loose, fine to medium grained sand			
		WOH	WOH	WOH							703-9			123.3ft: Silty SAND (SM), light olive gray (5Y6/2), loose, wet, fine to medium grained sand, strong HCl reaction			
-125.1	123.8	3	3	3							703-10			127.0ft: POORLY GRADED SAND with silt (SP-SM), greenish gray (10Y5/1), medium dense, wet, fine grained sand, strong HCl reaction			
-129.9	128.6	2	4	7							703-11			133.5ft: Silty SAND (SM), greenish gray (10Y5/1), loose, wet, fine to coarse grained sand, fine gravel, trace shell fragments, strong HCl reaction			
-134.8	133.5	4	5	4							703-12			138.6ft: medium dense			
-139.9	138.6	5	10	10							703-13			143.5ft: Silty, Clayey SAND (SC-SM), greenish gray (10Y5/1), medium dense, wet, fine grained sand, strong HCl reaction			
-144.8	143.5	5	6	10							703-14						
-149.8	148.5	4	5	9							703-15						

TURKEY POINT COL BORE TURKEY POINT COL GDT 8/18/08



SHEET 3 OF 3

BECHTEL PROJECT NO.: 25409		MACTEC PROJECT NO.: 6468-07-1950		COUNTY: Miami-Dade		GEOLOGIST: J. Liles							
SITE DESCRIPTION: Turkey Point COL		DRILL MACHINE: CME-550 (Miller)		DRILLER: R. White/ J. Dugger		GROUND WATER (ft)							
BORING NO.: B-703		DRILL METHOD: Mud Rotary/ Core		SAMPLE METHODS: SPT/Core		0 HR. NA							
GROUND ELEV.: -1.3 ft (NAVD88)		NORTHING: 397,018 US ft (NAD83/90)		EASTING: 875,846 US ft (NAD83/90)		24 HR. NA							
TOTAL DEPTH: 150.0 ft		BORING DIAMETER: 4" to 27.9', 3" to 150.0'		CASING DEPTH: 4" to 27.9', 3" to 115.0'		HAMMER (ID): 140 lb. Auto (M06)							
DATE STARTED: 2/22/08		COMPLETED: 2/25/08		CORE SIZE: HQ3		BITS USED: 2 7/8" Roller Cone							
ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
		0.5ft	0.5ft	0.5ft	0	20	40	60	80				100
-150.9					Continued from previous page								
													Silty SAND (SM), greenish gray (10Y5/1), medium dense, wet, fine to coarse grained sand, strong HCl reaction (continued) Boring Terminated at Elevation -151.3 ft

TURKEY POINT COL BORE TURKEY POINT.GPJ TURKEY POINT COL.GDT 8/18/08



SHEET 1 OF 2

BECHTEL PROJECT NO.: 25409		MACTEC PROJECT NO.: 6468-07-1950		COUNTY: Miami-Dade	GEOLOGIST: J. Liles	
SITE DESCRIPTION: Turkey Point COL		DRILL MACHINE: CME-550 (Miller)		DRILLER: R. White/ J. Dugger		GROUND WATER (ft) 0 HR. NA 24 HR. NA
BORING NO.: B-703		DRILL METHOD: Mud Rotary/ Core		SAMPLE METHODS: SPT/Core		
GROUND ELEV.: -1.3 ft (NAVD88)		NORTHING: 397,018 US ft (NAD83/90)		EASTING: 875,846 US ft (NAD83/90)		
TOTAL DEPTH: 150.0 ft		CASING DEPTH: 4" to 27.9', 3" to 115.0'				HAMMER (ID): 140 lb. Auto (M06)
DATE STARTED: 2/22/08	COMPLETED: 2/25/08	CORE SIZE: HQ3	CORE BARREL TYPE: Triple Tube Wireline (Split inner liners)			

ELEV. (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC (ft) %		SAMP. NO.	STRATA REC (ft) %		L O G	DESCRIPTION AND REMARKS
										Begin Coring @ 16.2 ft
-17.5	16.2	2.6	4:00	(2.5)	(1.8)	RUN-1	(3.9)	(1.8)		LIMESTONE, boundstone, white (2.5Y8/1), soft, wet, friable to moderately indurated, strong HCl reaction (Miami Formation) (continued)
-20.1	18.8		2:00	96%	69%		44%	20%		
		5.0	1:30/0.6	(1.4)	(0.0)	RUN-2				16.2ft: white (5Y8/1), soft, friable to moderately indurated, strong HCl reaction, locally interconnected vugs, oolitic
			1:00	28%	0%					18.8ft: trace shell fragments
-25.1	23.8		0:30							
		5.0	0:30	(3.0)	(2.4)	RUN-3				
			0:30	60%	48%		(16.5)	(15.1)		26.3
			1:00				93%	85%		LIMESTONE, boundstone, white (5Y8/1), moderately hard, indurated, coralline, little vugs (Upper Fort Thompson Formation)
-30.1	28.8		1:30							
		4.0	2:30	(3.5)	(2.8)	RUN-4				28.8ft: white (2.5Y8/1), hard, recrystallized calcite, fossiliferous
			2:30	88%	70%					31.0ft: loss of circulation
-34.1	32.8		1:30							
		5.0	1:40	(5.0)	(5.0)	RUN-5				
			2:58	100%	100%					
			2:34							
-39.1	37.8		3:30							
			4:23							
		5.0	3:33	(5.0)	(4.9)	RUN-6				37.8ft: white (2.5Y8/1) to 39.0ft, then bluish gray (5PB6/1) to 42.8ft
			3:27	100%	98%					
			3:41							
-44.1	42.8		3:05							
			4:03							
		5.0	3:16	(5.0)	(5.0)	RUN-7	(55.9)	(46.8)		
			4:03	100%	100%		87%	73%		LIMESTONE, boundstone, white (2.5Y8/1), hard, indurated, few vugs, fossiliferous, trace shell molds and casts (Lower Fort Thompson Formation)
-49.1	47.8		4:22							
		5.0	2:30	(3.8)	(3.4)	RUN-8				
			3:52	76%	68%					
			1:31							
-54.1	52.8		2:11							
			2:23							
		5.0	1:46	(5.0)	(4.1)	RUN-9				52.8ft: little vugs
			2:48	100%	82%					
			2:15							
-59.1	57.8		3:08							
			3:09							
		5.0	3:28	(3.9)	(3.3)	RUN-10				
			2:35	78%	66%					
			2:13							
-64.1	62.8		4:19							
			3:00							
		5.0	1:25	(4.3)	(3.3)	RUN-11				
			1:11	86%	66%					
			2:26							
-69.1	67.8		1:31							
			3:23							
		5.0	2:54	(5.0)	(4.9)	RUN-12				67.8ft: white (10YR8/1), few vugs
			3:31	100%	98%					
			3:08							
-74.1	72.8		4:28							
			2:32							
		5.0	3:11	(4.7)	(4.2)	RUN-13				
			2:30	94%	84%					
			1:48							
-79.1	77.8		2:03							
			1:15							
		5.0	0:31	(4.3)	(3.0)	RUN-14				
			1:50	86%	60%					
			3:57							
-84.1	82.8		3:49							
			7:07							
		5.0	2:13	(4.7)	(4.1)	RUN-15				
			1:00	94%	82%					
			0:54							
-89.1	87.8		0:52							
			0:38							
		5.0	0:21	(2.3)	(0.0)	RUN-16				87.8ft: moderately hard
			0:14	46%	0%					
			0:49							

TURKEY POINT COL CORE TURKEY POINT GPJ TURKEY POINT COL GDT 8/18/08