




OW-2169 L FALLING HEAD HEAD TEST

PROJECT INFORMATION

Company: EXELON
 Client: BECHTEL
 Project: 6468-07-1777
 Location: VICTORIA SITE
 Test Well: OW-2169 L
 Test Date: 1/17/07

AQUIFER DATA

Saturated Thickness: 10. ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2169 L)

Initial Displacement: 3.465 ft
 Total Well Penetration Depth: 100. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 58.7 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft


SOLUTION

Aquifer Model: Confined

Solution Method: Bouwer-Rice

$K = 1.068$ ft/day

$y_0 = 3.008$ ft



OW-2169 L FALLING HEAD HEAD TEST

PROJECT INFORMATION

Company: EXELON
 Client: BECHTEL
 Project: 6468-07-1777
 Location: VICTORIA SITE
 Test Well: OW-2169 L
 Test Date: 1/17/07

AQUIFER DATA

Saturated Thickness: 10. ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2169 L)

Initial Displacement: 3.465 ft
 Total Well Penetration Depth: 100. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 58.7 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft


SOLUTION

Aquifer Model: Confined

Solution Method: Butler

$K = 1.325$ ft/day.

$L_e = 1000.$ ft



OW-2169 L RISING HEAD TEST

PROJECT INFORMATION

Company: EXELON
 Client: BECHTEL
 Project: 6468-07-1777
 Location: VICTORIA SITE
 Test Well: OW-2169 L
 Test Date: 1/17/07

AQUIFER DATA

Saturated Thickness: 10. ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2169 L)

Initial Displacement: 4.174 ft
 Total Well Penetration Depth: 100. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 58.7 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft


SOLUTION

Aquifer Model: Confined

Solution Method: Bouwer-Rice

$K = 36.16$ ft/day

$y_0 = 4.345$ ft



OW-2169 L RISING HEAD HEAD TEST

PROJECT INFORMATION

Company: EXELON
 Client: BECHTEL
 Project: 6468-07-1777
 Location: VICTORIA SITE
 Test Well: OW-2169 L
 Test Date: 1/17/07

AQUIFER DATA


Saturated Thickness: 10. ft Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (OW-2169 L)

Initial Displacement: 4.174 ft Static Water Column Height: 58.7 ft
 Total Well Penetration Depth: 100. ft Screen Length: 10. ft
 Casing Radius: 0.083 ft Well Radius: 0.083 ft


SOLUTION

Aquifer Model: Confined Solution Method: Butler
 K = 36.52 ft/day Le = 27.29 ft

Checked by: CHB Date: 3/14/08

SLUG TEST REPORT

Project Name: Exelon COL	Project Number: 6489-07-1777	Page 1 of 1	OW-2181U
Client: Bechtel	Contractor: MACTEC		
Location: Victoria	MACTEC Rep: J. Moore CHB 3/13/08	Date: 1-21-08 2-5-08	CHB 3/13/08
UNITS			
Length	Feet		
Time	Minutes		
Well Data	38:00 CHB 3/13/08		
Static Water Level	38.24 feet		
Total Well Depth	53.02 feet		
Static Water Column Height (H)	15.02 feet		
Observed Initial Displacement (H ₀)	Background	Falling Head	Rising Head
	NA	~4'	~4' or ~6'
Saturated Thickness (b)	feet		
Conductivity Anisotropy (Kv/Kh)	Assume 1 to 1		
Depth to Top of Well Screen (d)	40 feet		
Length of Well Screen (L)	10 feet		
Radius of Well Casing (rc)	0.083 feet		
Radius of Screen (rw)	0.083 feet		
Radius of Probe (req)			
Radius of Boring (rsk) Skin Effect	0.083 feet		
Probe Serial Number	103678 106721 CHB 3/13/08		
Slug Data	Slug #1		
Length	5.5 feet		
Weight			
Diameter	1.625 inches		
Slug Test File	Background	Falling	Rising
File Name	OW-2181U BACKGROUND	OW-2181U FALLING HEAD	OW-2181U RISING HEAD
Start Time	11:35:47	11:55:29	12:05:28
End Time	11:50:47	12:00:30	12:10:12
Notes	Hard Bottom Rising head test might have two erroneous displacement numbers @ 6' at start, most likely need to delete them, but curve looks good.		
Rev 0			



OW-2181 U FALLING HEAD HEAD TEST

PROJECT INFORMATION

Company: EXELON
 Client: BECHTEL
 Project: 6468-07-1777
 Location: VICTORIA SITE
 Test Well: OW-2181 U
 Test Date: 2/5/07

AQUIFER DATA


Saturated Thickness: 10. ft Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (OW-2181 U)

Initial Displacement: 4.089 ft Static Water Column Height: 15.02 ft
 Total Well Penetration Depth: 50. ft Screen Length: 10. ft
 Casing Radius: 0.083 ft Well Radius: 0.083 ft

SOLUTION

Aquifer Model: Confined Solution Method: Bouwer-Rice
 K = 4.077 ft/day y0 = 1.925 ft



OW-2181 U FALLING HEAD TEST

PROJECT INFORMATION

Company: EXELON
 Client: BECHTEL
 Project: 6468-07-1777
 Location: VICTORIA SITE
 Test Well: OW-2181 U
 Test Date: 2/5/07

AQUIFER DATA

Saturated Thickness: 10. ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2181 U)

Initial Displacement: 4.089 ft

Static Water Column Height: 15.02 ft

Total Well Penetration Depth: 50. ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.083 ft


SOLUTION

Aquifer Model: Confined

Solution Method: Butler

$K = 13.53$ ft/day

$L_e = 0.1$ ft



OW-2181 U RISING HEAD TEST

PROJECT INFORMATION

Company: EXELON
 Client: BECHTEL
 Project: 6468-07-1777
 Location: VICTORIA SITE
 Test Well: OW-2181 U
 Test Date: 2/5/07

AQUIFER DATA

Saturated Thickness: 10. ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2181 U)

Initial Displacement: 3.373 ft
 Total Well Penetration Depth: 50. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 15.02 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft


SOLUTION

Aquifer Model: Confined

Solution Method: Bouwer-Rice

$K = 8.95$ ft/day

$y_0 = 2.73$ ft



OW-2181 U RISING HEAD HEAD TEST

PROJECT INFORMATION

Company: EXELON
 Client: BECHTEL
 Project: 6468-07-1777
 Location: VICTORIA SITE
 Test Well: OW-2181 U
 Test Date: 2/5/07

AQUIFER DATA

Saturated Thickness: 10. ft

Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (OW-2181 U)

Initial Displacement: 3.373 ft
 Total Well Penetration Depth: 50. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 15.02 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft

SOLUTION

Aquifer Model: Confined
 K = 12.82 ft/day


Solution Method: Butler
 Le = 0.1 ft

SLUG TEST REPORT

Project Name: Exelon COL		Project Number: 6489-07-1777		Page 1 of 1		OW-2181 L	
Client: Bechtel		Contractor: MACTEC					
Location: Victoria		MACTEC Rep: <u>L.M. BISSON</u> <u>B. TAYLOR</u>			Date: <u>1/17/08</u>		
UNITS							
Length		Feet					
Time		Minutes					
Well Data							
Static Water Level		<u>45.37</u> feet					
Total Well Depth		<u>99.20</u> feet					
Static Water Column Height (H)		<u>53.83</u> feet					
		Background		Falling Head		Rising Head	
Observed Initial Displacement (H ₀)		NA		<u>~ 4.70'</u>		<u>~ 4.6</u>	
Saturated Thickness (b)		feet					
Conductivity Anisotropy (Kv/Kh)		Assume 1 to 1					
Depth to Top of Well Screen (d)		<u>90 feet</u>					
Length of Well Screen (L)		<u>10</u> feet					
Radius of Well Casing (rc)		0.083 feet					
Radius of Screen (rw)		0.083 feet					
Radius of Probe (req)							
Radius of Boring (rsk) Skin Effect		0.083 feet					
Probe Serial Number		<u>103048</u>					
Slug Data							
		<u>SINGLE SLUG # 2</u>					
Length		<u>5' FEET</u>					
weight							
Diameter		<u>1.625 INCHES</u>					
Slug Test File		Background		Falling		Rising	
File Name		<u>OW-2181 L BACKGROUND</u>		<u>OW-2181 L FALLING HEAD</u>		<u>OW-2181 L RISING HEAD</u>	
Start Time		<u>12:28:24 PM</u>		<u>5:21:20 PM 1/17</u>		<u>11:04:17 AM</u>	
End Time		<u>5:17:24 PM</u>		<u>11:05:08 AM 1/18</u>		<u>8:39:05 AM 11/19</u>	
Notes							
Rev 0							

Prepared by: WSR Date: 3-17-08

Checked by: WBL Date: 3-17-08



OW-2181 L FALLING HEAD HEAD TEST (LATE TIME)

PROJECT INFORMATION

Company: EXELON
Client: BECHTEL
Project: 6468-07-1777
Location: VICTORIA SITE
Test Well: OW-2181 L
Test Date: 1/17/08

AQUIFER DATA

Saturated Thickness: 5.2 ft

Anisotropy Ratio (K_z/K_r): 1

WELL DATA (OW-2181 L)

Initial Displacement: 5.2 ft
Total Well Penetration Depth: 100 ft
Casing Radius: 0.083 ft

Static Water Column Height: 53.83 ft
Screen Length: 10 ft
Well Radius: 0.083 ft

SOLUTION


Aquifer Model: Confined

Solution Method: Bouwer-Rice

$K = 0.005787$ ft/day
Volume 4, Rev. 0 - 7/10/08

Page 510 of 861
 $y_0 = 3.055$ ft

DCN# EXE805



OW-2181 L FALLING HEAD HEAD TEST

PROJECT INFORMATION

Company: EXELON
 Client: BECHTEL
 Project: 6468-07-1777
 Location: VICTORIA SITE
 Test Well: OW-2181 L
 Test Date: 1/17/08

AQUIFER DATA

Saturated Thickness: 5.2 ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2181 L)

Initial Displacement: 4.715 ft
 Total Well Penetration Depth: 100. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 53.83 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft


SOLUTION

Aquifer Model: Confined

Solution Method: Butler

$K = 0.03435$ ft/day

$Le = 0.1134$ ft



OW-2181 L RISING HEAD HEAD TEST

PROJECT INFORMATION

Company: EXELON
 Client: BECHTEL
 Project: 6468-07-1777
 Location: VICTORIA SITE
 Test Well: OW-2181 L
 Test Date: 1/17/08

AQUIFER DATA

Saturated Thickness: 5.2 ft

Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (OW-2181 L)


Initial Displacement: 4.562 ft
 Total Well Penetration Depth: 100. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 53.83 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft

SOLUTION


Aquifer Model: Confined
 K = 0.01298 ft/day

Solution Method: Bouwer-Rice
 y0 = 3.206 ft

OW-2181 L RISING HEAD TESTPROJECT INFORMATION


Company: EXELON
Client: BECHTEL
Project: 6468-07-1777
Location: VICTORIA SITE
Test Well: OW-2181 L
Test Date: 1/17/08

AQUIFER DATASaturated Thickness: 5.2 ftAnisotropy Ratio (K_z/K_r): 1.WELL DATA (OW-2181 L)Initial Displacement: 4.562 ftStatic Water Column Height: 53.83 ftTotal Well Penetration Depth: 100. ftScreen Length: 10. ftCasing Radius: 0.083 ftWell Radius: 0.083 ftSOLUTIONAquifer Model: ConfinedSolution Method: Butler $K = 0.03435$ ft/day $Le = 0.1004$ ft

Checked by: CHB Date: 3/14/08

SLUG TEST REPORT

Project Name: Exelon COL		Project Number: 6469-07-1777		Page 1 of 1	OW-2185 U
Client: Bechtel		Contractor: MACTEC			
Location: Victoria		MACTEC Rep: <u>A.M. BIRSON</u> <u>B. TAYLOR</u>		Date: <u>1/17/08</u>	
UNITS					
Length		Feet			
Time		Minutes			
Well Data					
Static Water Level		<u>41.70</u> feet			
Total Well Depth		<u>78.24</u> feet			
Static Water Column Height (H)		<u>36.54</u> feet			
		Background	Falling Head	Rising Head	
Observed Initial Displacement (H ₀)		NA	<u>~ 5.3'</u>	<u>~ 5.3'</u>	
Saturated Thickness (b)		feet			
Conductivity Anisotropy (Kv/Kh)		Assume 1 to 1			
Depth to Top of Well Screen (d)		<u>65 feet</u>			
Length of Well Screen (L)		<u>10 feet</u>			
Radius of Well Casing (rc)		0.083 feet			
Radius of Screen (rw)		0.083 feet			
Radius of Probe (req)					
Radius of Boring (rsk) Skin Effect		0.083 feet			
Probe Serial Number		<u>117812</u>			
Slug Data		<u># 2</u>			
Length		<u>5 FEET</u>			
Weight					
Diameter		<u>1.625</u>			
Slug Test File		Background	Falling	Rising	
File Name		<u>OW-2185 U BACKGROUND</u>	<u>OW-2185 U FALLING HEAD</u>	<u>OW-2185 U RISING HEAD</u>	
Start Time		<u>4:09:34</u>	<u>4:41:31 PM</u>	<u>4:45:51 PM</u>	
End Time		<u>4:09:39</u>	<u>4:44:01 PM</u>	<u>4:50:04 PM</u>	
Notes		<u>→ 10:00:04 AM</u> <u>→ 4:38:53 PM</u>			
Rev 0					



OW-2185U FALLING HEAD

PROJECT INFORMATION

Company: MACTEC
 Client: Bechtel Power Corp.
 Project: 6468-07-1777.210
 Location: Victoria, Texas
 Test Well: OW-2185U
 Test Date: 1-17-08

AQUIFER DATA


Saturated Thickness: 4.5 ft Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2185U)

Initial Displacement: 5.333 ft Static Water Column Height: 36.54 ft
 Total Well Penetration Depth: 75. ft Screen Length: 10. ft
 Casing Radius: 0.083 ft Well Radius: 0.083 ft

SOLUTION

Aquifer Model: Confined Solution Method: Bouwer-Rice
 $K = 9.919$ ft/day $y_0 = 3.229$ ft



OW-2185U FALLING HEAD

PROJECT INFORMATION

Company: MACTEC
 Client: Bechtel Power Corp.
 Project: 6468-07-1777.210
 Location: Victoria, Texas
 Test Well: OW-2185U
 Test Date: 1-17-08

AQUIFER DATA

Saturated Thickness: 4.5 ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2185U)

Initial Displacement: 5.333 ft
 Total Well Penetration Depth: 75. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 36.54 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft


SOLUTION

Aquifer Model: Confined

Solution Method: Butler

$K = 15.15$ ft/day

$L_e = 0.1$ ft



OW-2185U RISING HEAD

PROJECT INFORMATION

Company: MACTEC
 Client: Bechtel Power Corp.
 Project: 6468-07-1777.210
 Location: Victoria, Texas
 Test Well: OW-2185U
 Test Date: 1-17-08

AQUIFER DATA

Saturated Thickness: 4.5 ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2185U)

Initial Displacement: 6.255 ft
 Total Well Penetration Depth: 75. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 36.54 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft


SOLUTION

Aquifer Model: Confined

Solution Method: Bouwer-Rice

$K =$ 10.79 ft/day

$y_0 =$ 3.071 ft

OW-2185U RISING HEADPROJECT INFORMATION

Company: MACTEC
Client: Bechtel Power Corp.
Project: 6468-07-1777.210
Location: Victoria, Texas
Test Well: OW-2185U
Test Date: 1-17-08


AQUIFER DATASaturated Thickness: 4.5 ftAnisotropy Ratio (Kz/Kr): 1.WELL DATA (OW-2185U)Initial Displacement: 6.255 ftStatic Water Column Height: 36.54 ftTotal Well Penetration Depth: 75. ftScreen Length: 10. ftCasing Radius: 0.083 ftWell Radius: 0.083 ftSOLUTIONAquifer Model: ConfinedSolution Method: ButlerK = 13.86 ft/dayLe = 0.1 ft

Checked by: CHS Date: 3/14/08



SLUG TEST REPORT

Project Name: Exelon COL		Project Number: 6489-07-1777		Page 1 of 1	OW-2185L
Client: Bechtel		Contractor: MACTEC			
Location: Victoria		MACTEC Rep: <u>J.M. HISSON</u> <u>B. TAYLOR</u>		Date: <u>1/17/08</u>	
UNITS					
Length		Feet			
Time		Minutes			
Well Data					
Static Water Level		<u>45.52</u> feet			
Total Well Depth		<u>102.96</u> feet			
Static Water Column Height (H)		<u>57.44</u> feet			
Observed Initial Displacement (H ₀)	Background	Falling Head	Rising Head		
	NA	<u>N 4 FEET</u>	<u>N 4 FEET</u>		
Saturated Thickness (b)		feet			
Conductivity Anisotropy (Kv/Kh)		Assume 1 to 1			
Depth to Top of Well Screen (d)		<u>90 feet</u>			
Length of Well Screen (L)		<u>10 feet</u>			
Radius of Well Casing (rc)		0.083 feet			
Radius of Screen (rw)		0.083 feet			
Radius of Probe (req)					
Radius of Boring (rsk) Skin Effect		0.083 feet			
Probe Serial Number					
Slug Data		<u>SINGLE SLUG # 2</u>			
Length		<u>5 FEET</u>			
Weight					
Diameter		<u>1.625 INCHES</u>			
Slug Test File		Background	Falling	Rising	
File Name		<u>OW-2185L BACKGROUND</u>	<u>OW-2185L FALLING HEAD</u>	<u>OW-2185L RISING HEAD</u>	
Start Time		<u>12:09:39 AM</u>	<u>4:27:11 PM</u>	<u>4:34:04</u>	
End Time		<u>4:09:39 PM</u>	<u>4:37:12 PM</u>	<u>4:37:13</u>	
Notes					
Rev 0					

OW-2185L FALLING HEADPROJECT INFORMATION


Company: MACTEC
Client: Bechtel Power Corp.
Project: 6468-07-1777.210
Location: Victoria, Texas
Test Well: OW-2185L
Test Date: 1-17-08

AQUIFER DATASaturated Thickness: 10. ftAnisotropy Ratio (K_z/K_r): 1.WELL DATA (OW-2185L)

Initial Displacement: 4.39 ft
Total Well Penetration Depth: 100. ft
Casing Radius: 0.083 ft

Static Water Column Height: 57.44 ft
Screen Length: 10. ft
Well Radius: 0.083 ft

SOLUTIONAquifer Model: ConfinedSolution Method: Bouwer-Rice $K = \underline{6.171 \text{ ft/day}}$ $y_0 = \underline{1.875 \text{ ft}}$

OW-2185L FALLING HEADPROJECT INFORMATION

Company: MACTEC
Client: Bechtel Power Corp.
Project: 6468-07-1777.210
Location: Victoria, Texas
Test Well: OW-2185L
Test Date: 1-17-08

AQUIFER DATASaturated Thickness: 10. ftAnisotropy Ratio (K_z/K_r): 1.WELL DATA (OW-2185L)


Initial Displacement: 4.39 ft
Total Well Penetration Depth: 100. ft
Casing Radius: 0.083 ft

Static Water Column Height: 57.44 ft
Screen Length: 10. ft
Well Radius: 0.083 ft

SOLUTION

Aquifer Model: Confined
 $K = 8.095$ ft/day

Solution Method: Butler
 $Le = 0.1$ ft

OW-2185L RISING HEADPROJECT INFORMATION


Company: MACTEC
Client: Bechtel Power Corp.
Project: 6468-07-1777.210
Location: Victoria, Texas
Test Well: OW-2185L
Test Date: 1-17-08

AQUIFER DATASaturated Thickness: 10. ftAnisotropy Ratio (K_z/K_r): 1.WELL DATA (OW-2185L)

Initial Displacement: 8.373 ft
Total Well Penetration Depth: 100. ft
Casing Radius: 0.083 ft

Static Water Column Height: 57.44 ft
Screen Length: 10. ft
Well Radius: 0.083 ft

SOLUTIONAquifer Model: ConfinedSolution Method: Bouwer-Rice $K =$ 19.4 ft/day $y_0 =$ 2.936 ft

OW-2185L RISING HEADPROJECT INFORMATION

Company: MACTEC
Client: Bechtel Power Corp.
Project: 6468-07-1777.210
Location: Victoria, Texas
Test Well: OW-2185L
Test Date: 1-17-08

AQUIFER DATA

Saturated Thickness: 10. ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2185L)

Initial Displacement: 8.373 ft

Static Water Column Height: 57.44 ft

Total Well Penetration Depth: 100. ft

Screen Length: 10. ft

Casing Radius: 0.083 ft

Well Radius: 0.083 ft

SOLUTION

Aquifer Model: Confined

Solution Method: Butler

$K = 27.27$ ft/day


$L_e = 0.1$ ft

Checked by: CHB Date: 3/14/08



SLUG TEST REPORT

Project Name: Exelon COL		Project Number: 6469-07-1777		Page 1 of 1		OW-2253U	
Client: Bechtel		Contractor: MACTEC					
Location: Victoria		MACTEC Rep: L.M. JISSON B. TAYLOR		Date: 1/15/08			
UNITS							
Length		Feet					
Time		Minutes					
Well Data							
Static Water Level:		34.10 feet					
Total Well Depth:		68.25 feet					
Static Water Column Height (H)		34.15 feet					
		Background		Falling Head		Rising Head	
Observed Initial Displacement (H ₀)		NA		N 4.2 FEET		N 8.0 FEET	
Saturated Thickness (b)		feet					
Conductivity Anisotropy (K _v /K _h)		Assume 1 to 1					
Depth to Top of Well Screen (d)		55 feet					
Length of Well Screen (L)		10 feet					
Radius of Well Casing (rc)		0.083 feet					
Radius of Screen (rw)		0.083 feet					
Radius of Probe (rp)							
Radius of Boring (rb) Skin Effect		0.083 feet					
Probe Serial Number:		112335					
Slug Data:		SLUG # 2					
Length		5.0 FEET					
Weight							
Diameter		1.625 INCHES					
Slug Test File		Background		Falling		Rising	
File Name		OW-2253U		OW-2253U FALLING HEAD		OW-2253U RISING HEAD	
Start Time				4:27:23 PM		4:35:59 PM	
End Time				4:33:40 PM		4:47:52 PM	
Notes							
Rev 0							



OW-2253 U FALLING HEAD

PROJECT INFORMATION

Company: MACTEC
 Client: Bechtel Power Corp.
 Project: 6468-07-1777.210
 Location: Victoria, Texas
 Test Well: OW-2253 U
 Test Date: 1-15-08

AQUIFER DATA


Saturated Thickness: 8.5 ft Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2253 U)

Initial Displacement: 4.234 ft Static Water Column Height: 34.15 ft
 Total Well Penetration Depth: 65. ft Screen Length: 10. ft
 Casing Radius: 0.083 ft Well Radius: 0.083 ft

SOLUTION

Aquifer Model: Confined Solution Method: Bouwer-Rice
 $K = 10.8 \text{ ft/day}$ $y_0 = 3.575 \text{ ft}$



OW-2253 U FALLING HEAD

PROJECT INFORMATION

Company: MACTEC
 Client: Bechtel Power Corp.
 Project: 6468-07-1777.210
 Location: Victoria, Texas
 Test Well: OW-2253 U
 Test Date: 1-15-08

AQUIFER DATA


Saturated Thickness: 8.5 ft Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2253 U)

Initial Displacement: 4.234 ft Static Water Column Height: 34.15 ft
 Total Well Penetration Depth: 65. ft Screen Length: 10. ft
 Casing Radius: 0.083 ft Well Radius: 0.083 ft

SOLUTION

Aquifer Model: Confined Solution Method: Butler
 $K = 11.58$ ft/day $L_e = 0.1$ ft

OW-2253U RISING HEADPROJECT INFORMATION


Company: MACTEC
Client: Bechtel Power Corp.
Project: 6468-07-1777.210
Location: Victoria, Texas
Test Well: OW-2253 U
Test Date: 1-15-08

AQUIFER DATASaturated Thickness: 8.5 ftAnisotropy Ratio (K_z/K_r): 1.WELL DATA (OW-2253U)

Initial Displacement: 8.171 ft
Total Well Penetration Depth: 65. ft
Casing Radius: 0.083 ft

Static Water Column Height: 34.1 ft
Screen Length: 10. ft
Well Radius: 0.083 ft

SOLUTIONAquifer Model: ConfinedSolution Method: Bouwer-Rice $K =$ 12.48 ft/day $y_0 =$ 4.136 ft



OW-2253U RISING HEAD

PROJECT INFORMATION

Company: MACTEC
 Client: Bechtel Power Corp.
 Project: 6468-07-1777.210
 Location: Victoria, Texas
 Test Well: OW-2253 U
 Test Date: 1-15-08

AQUIFER DATA

Saturated Thickness: 8.5 ft Anisotropy Ratio (K_z/K_r): 1.


WELL DATA (OW-2253U)

Initial Displacement: 8.171 ft Static Water Column Height: 34.1 ft
 Total Well Penetration Depth: 65. ft Screen Length: 10. ft
 Casing Radius: 0.083 ft Well Radius: 0.083 ft

SOLUTION


Aquifer Model: Confined Solution Method: Butler
 $K = 15.36 \text{ ft/day}$ $L_e = 10. \text{ ft}$

Checked by: CHB Date: 3/14/08



SLUG TEST REPORT

Project Name: Exelon COL		Project Number: 6469-07-1777		Page 1 of 1		OW-2253 L	
Client: Bechtel		Contractor: MACTEC					
Location: Victoria		MACTEC Rep: <u>d.m. Bisson</u> <u>B. TAYLOR</u>				Date: <u>1/15/08</u>	
UNITS							
Length:		Feet					
Time:		Minutes					
Well Data							
Static Water Level:		<u>49.36</u> feet					
Total Well Depth:		<u>148.35</u> feet					
Static Water Column Height (H):		<u>98.99</u> feet					
Observed Initial Displacement (H ₀)		Background		Falling Head		Rising Head	
		NA		<u>N 4 FEET</u>		<u>N 8 FEET</u>	
Saturated Thickness (b)		feet					
Conductivity Anisotropy (K _v /K _h)		Assume 1 to 1					
Depth to Top of Well Screen (d)		<u>135</u> feet					
Length of Well Screen (L)		<u>10</u> feet					
Radius of Well Casing (rc)		0.083 feet					
Radius of Screen (rw)		0.083 feet					
Radius of Probe (req)							
Radius of Boring (rb) Skin Effect		0.083 feet					
Probe Serial Number		<u>109172</u>					
Slug Data							
Length:		<u>DOUBLE SLUG</u> <u>5.5' x 5.5'</u>					
Weight:		<u>17.5 lbs.</u>					
Diameter:		<u>1.625"</u>					
Slug Test File		Background		Falling		Rising	
File Name <u>OW-2253 L</u>		<u>OW-2253 L</u>		<u>OW-2253 L FALLING HEAD</u>		<u>OW-2253 L RISING HEAD</u>	
Start Time		<u>4:45:26</u>		<u>5:16:49 PM</u>		<u>5:12:52 PM</u>	
End Time		<u>4:53:36</u>		<u>5:17:50 PM</u>		<u>5:13:29 PM</u>	
Notes:		<u>- RAN 3 FALLING HEAD AND 1 RISING HEAD TESTS</u> <u>DUE TO QUICK RECOVERY</u> <u>WJ</u> <u>3-15-08</u>					
Rev: 0							



OW-2253L FALLING HEAD 1

PROJECT INFORMATION

Company: MACTEC
 Client: Bechtel Power Corp.
 Project: 6468-07-1777.210
 Location: Victoria, Texas
 Test Well: OW-2253 L
 Test Date: 1-15-08

AQUIFER DATA

Saturated Thickness: 10. ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2253 L)


Initial Displacement: 7.394 ft
 Total Well Penetration Depth: 145. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 98.99 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft

SOLUTION

Aquifer Model: Confined
 $K = 101.4 \text{ ft/day}$

Solution Method: Bouwer-Rice
 $y_0 = 7.555 \text{ ft}$



OW-2253L FALLING HEAD 1

PROJECT INFORMATION

Company: MACTEC
 Client: Bechtel Power Corp.
 Project: 6468-07-1777.210
 Location: Victoria, Texas
 Test Well: OW-2253 L
 Test Date: 1-15-08

AQUIFER DATA


Saturated Thickness: 10. ft Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (OW-2253 L)

Initial Displacement: 7.394 ft Static Water Column Height: 98.99 ft
 Total Well Penetration Depth: 145. ft Screen Length: 10. ft
 Casing Radius: 0.083 ft Well Radius: 0.083 ft


SOLUTION

Aquifer Model: Confined Solution Method: Butler
 K = 105.2 ft/day Le = 44.53 ft

OW-2253L FALLING HEAD BPROJECT INFORMATION


Company: MACTEC
Client: Bechtel Power Corp.
Project: 6468-07-1777.210
Location: Victoria, Texas
Test Well: OW-2253 L
Test Date: 1-15-08

AQUIFER DATASaturated Thickness: 10. ftAnisotropy Ratio (K_z/K_r): 1.WELL DATA (OW-2253L)Initial Displacement: 14.32 ftStatic Water Column Height: 49.36 ftTotal Well Penetration Depth: 145. ftScreen Length: 10. ftCasing Radius: 0.083 ftWell Radius: 0.083 ftSOLUTIONAquifer Model: ConfinedSolution Method: Bouwer-Rice $K = 99.76$ ft/day $y_0 = 12.71$ ft

OW-2253L FALLING HEAD BPROJECT INFORMATION

Company: MACTEC
Client: Bechtel Power Corp.
Project: 6468-07-1777.210
Location: Victoria, Texas
Test Well: OW-2253 L
Test Date: 1-15-08

AQUIFER DATASaturated Thickness: 10. ftAnisotropy Ratio (Kz/Kr): 1.WELL DATA (OW-2253L)Initial Displacement: 14.32 ftStatic Water Column Height: 49.36 ftTotal Well Penetration Depth: 145. ftScreen Length: 10. ftCasing Radius: 0.083 ftWell Radius: 0.083 ftSOLUTIONAquifer Model: ConfinedSolution Method: ButlerK = 115.2 ft/dayLe = 0.1 ft

OW-2253L FALLING HEAD 2PROJECT INFORMATION


Company: MACTEC
Client: Bechtel Power Corp.
Project: 6468-07-1777.210
Location: Victoria, Texas
Test Well: OW-2253 L
Test Date: 1-15-08

AQUIFER DATASaturated Thickness: 10. ftAnisotropy Ratio (K_z/K_r): 1.WELL DATA (OW-2253L)

Initial Displacement: 9.166 ft
Total Well Penetration Depth: 145. ft
Casing Radius: 0.083 ft

Static Water Column Height: 49.36 ft
Screen Length: 10. ft
Well Radius: 0.083 ft

SOLUTIONAquifer Model: ConfinedSolution Method: Bouwer-Rice $K = 137.6$ ft/day $y_0 = 9.815$ ft

OW-2253L FALLING HEAD 2PROJECT INFORMATION


Company: MACTEC
Client: Bechtel Power Corp.
Project: 6468-07-1777.210
Location: Victoria, Texas
Test Well: OW-2253 L
Test Date: 1-15-08

AQUIFER DATASaturated Thickness: 10. ftAnisotropy Ratio (K_z/K_r): 1.WELL DATA (OW-2253L)

Initial Displacement: 9.166 ft
Total Well Penetration Depth: 145. ft
Casing Radius: 0.083 ft

Static Water Column Height: 49.36 ft
Screen Length: 10. ft
Well Radius: 0.083 ft

SOLUTIONAquifer Model: ConfinedSolution Method: Butler $K =$ 147.8 ft/day $L_e =$ 10. ft

OW-2253L RISING HEADPROJECT INFORMATION

Company: MACTEC
Client: Bechtel Power Corp.
Project: 6468-07-1777.210
Location: Victoria, Texas
Test Well: OW-2253 L
Test Date: 1-15-08

AQUIFER DATASaturated Thickness: 10. ftAnisotropy Ratio (K_z/K_r): 1.WELL DATA (OW-2253L)


Initial Displacement: 7.948 ft
Total Well Penetration Depth: 145. ft
Casing Radius: 0.083 ft

Static Water Column Height: 98.99 ft
Screen Length: 10. ft
Well Radius: 0.083 ft

SOLUTION

Aquifer Model: Confined
 $K =$ 77.25 ft/day

Solution Method: Bouwer-Rice
 $y_0 =$ 6.915 ft



OW-2253L RISING HEAD

PROJECT INFORMATION

Company: MACTEC
 Client: Bechtel Power Corp.
 Project: 6468-07-1777.210
 Location: Victoria, Texas
 Test Well: OW-2253 L
 Test Date: 1-15-08

AQUIFER DATA

Saturated Thickness: 10. ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2253L)

Initial Displacement: 7.948 ft
 Total Well Penetration Depth: 145. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 98.99 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft

SOLUTION


Aquifer Model: Confined

Solution Method: Butler

$K = 87.9$ ft/day


$L_e = 43.65$ ft

Checked by: CHB Date: 3/14/08



SLUG TEST REPORT

Project Name: Exelon COL		Project Number: 8469-07-1777		Page: 1 of 1		OW-22690	
Client: Bechtel		Contractor: MACTEC		1/15/08			
Location: Victoria		MACTEC Rep: <u>LM. Brisson</u> <u>B. TAYLOR</u>		Date: <u>1/16/08</u>			
UNITS							
Length		Feet					
Time		Minutes					
Well Data							
Static Water Level		<u>46.62</u> feet					
Total Well Depth		<u>93.35</u> feet					
Static Water Column Height (H)		<u>46.63</u> feet					
Observed Initial Displacement (H ₀)		Background		Falling Head		Rising Head	
		NA		<u>6.0'</u>			
Saturated Thickness (b)		feet					
Conductivity Anisotropy (K _v /K _h)		Assume 1 to 1					
Depth to Top of Well Screen (d)		<u>80</u> feet					
Length of Well Screen (L)		<u>10</u> feet					
Radius of Well Casing (rc)		0.083 feet					
Radius of Screen (rw)		0.083 feet					
Radius of Probe (req)							
Radius of Boring (rsk) Skin Effect		0.083 feet					
Probe Serial Number		<u>117812</u>					
Slug Data		<u>SLUG # 2</u>					
Length		<u>5.0 FEET</u>					
Weight							
Diameter		<u>1.625 INCH</u>					
Slug Test File		Background		Falling		Rising	
File Name		<u>OW-22846</u>		<u>OW-22846</u>		<u>OW-22690</u>	
Start Time		<u>1-15-08 3:44.34</u>		<u>12:02:17</u>		<u>12:34.06</u>	
End Time		<u>1-16-08 11:50.34</u>		<u>12:10:42</u>		<u>12:31:36</u>	
Notes		<u>2 FALLING HEAD:</u> <u>Falling Head "B" rope caught up.</u> <u>Transposed Label on Computer File: OW-22846 Start time</u> <u>1-15-08 3:44.34</u>					
Rev.0							



OW-2269 U FALLING HEAD

PROJECT INFORMATION

Company: MACTEC
 Client: Bechtel Power Corp.
 Project: 6468-07-1777.210
 Location: Victoria, Texas
 Test Well: OW-2269 U
 Test Date: 1-16-08

AQUIFER DATA

Saturated Thickness: 9.6 ft

Anisotropy Ratio (K_z/K_r): 1.

WELL DATA (OW-2269 U)

Initial Displacement: 5.985 ft
 Total Well Penetration Depth: 90. ft
 Casing Radius: 0.083 ft

Static Water Column Height: 46.63 ft
 Screen Length: 10. ft
 Well Radius: 0.083 ft

SOLUTION

Aquifer Model: Confined

Solution Method: Bouwer-Rice

$K = 0.7932$ ft/day

$y_0 = 3.294$ ft