



SHEET 2 OF 3

BECHTEL PROJECT NO.: 25409				MACTEC PROJECT NO.: 6468-07-1950				COUNTY: Miami-Dade		GEOLOGIST: J. Liles				
SITE DESCRIPTION: Turkey Point COL				DRILL MACHINE: CME-550 (Miller)				DRILLER: R. White/ J. Dugger/ C. White				GROUND WATER (ft)		
BORING NO.: B-702				DRILL METHOD: Mud Rotary/ Core				SAMPLE METHODS: SPT/Core				0 HR. NA		
GROUND ELEV.: -1.2 ft (NAVD88)				NORTHING: 397,018 US ft (NAD83/90)				EASTING: 875,746 US ft (NAD83/90)				24 HR. NA		
TOTAL DEPTH: 202.5 ft		BORING DIAMETER: 4" to 25.0', 3" to 202.5'				CASING DEPTH: 4" to 25.0', 3" to 122.9'				HAMMER (ID):140 lb. Auto (M06)				
DATE STARTED: 2/26/08		COMPLETED: 3/6/08		CORE SIZE: HQ3				BITS USED: 2 7/8" Roller Cone						
ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT						SAMP NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
		0.5ft	0.5ft	0.5ft	0	20	40	60	80	100				
-76.0					Continued from previous page									
-80.1	78.9													73.9ft: hard, few vugs LIMESTONE, boundstone, white (2.5Y8/1), hard, extremely indurated, fossiliferous, some vugs, strong HCl reaction (Lower Fort Thompson Formation) (continued) 78.9ft: moderately hard, trace vugs
-85.1	83.9													83.9ft: hard
-90.1	88.9													88.9ft: moderately hard, little vugs
-95.1	93.9													93.9ft: moderately indurated
-100.1	98.9													98.9ft: indurated, some vugs, little shell molds and casts
-105.1	103.9													
-110.1	108.9													
-115.1	113.9													113.9ft: white (5Y8/1), trace vugs, shell molds and casts
-120.1	118.9													118.9ft: white (5Y8/1), trace vugs, shell molds and casts
-120.4	119.2	1	2	1										119.2ft: Switch sampling method to SPT
-125.4	124.2	2	2	2										119.2ft: loose, trace shells, limestone fragments, trace silt
-132.3	131.1	1	4	5										131.1ft: POORLY GRADED SAND with silt (SP-SM), light gray (5Y7/1), very loose, wet, fine grained sand, few fines, trace limestone fragments, strong HCl reaction
-137.3	136.1	5	7	4										136.1ft: Silty SAND (SM), greenish gray (10YR6/1), loose, wet, fine grained sand, few fines, strong HCl reaction
-142.2	141.0	6	5	7										136.1ft: medium dense, few limestone fragments, trace shell fragments
-147.2	146.0	5	5	9										

TURKEY POINT COL BORE TURKEY POINT COL GDT 5/30/08



BECHTEL PROJECT NO.: 25409					MACTEC PROJECT NO.: 6468-07-1950					COUNTY: Miami-Dade					GEOLOGIST: J. Liles				
SITE DESCRIPTION: Turkey Point COL					DRILL MACHINE: CME-550 (Miller)					DRILLER: R. White/ J. Dugger/ C. White					GROUND WATER (ft)				
BORING NO.: B-702					DRILL METHOD: Mud Rotary/ Core					SAMPLE METHODS: SPT/Core					0 HR. NA				
GROUND ELEV.: -1.2 ft (NAVD88)					NORTHING: 397,018 US ft (NAD83/90)					EASTING: 875,746 US ft (NAD83/90)					24 HR. NA				
TOTAL DEPTH: 202.5 ft					BORING DIAMETER: 4" to 25.0', 3" to 202.5'					CASING DEPTH: 4" to 25.0', 3" to 122.9'					HAMMER (ID): 140 lb. Auto (M06)				
DATE STARTED: 2/26/08					COMPLETED: 3/6/08					CORE SIZE: HQ3					BITS USED: 2 7/8" Roller Cone				
ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	▼ MOI	L O G	SOIL AND ROCK DESCRIPTION						
		0.5ft	0.5ft	0.5ft	0	20	40	60	80	100									
-150.8					Continued from previous page														
-152.3	151.1	4	7	11		18					702-18		Silty SAND (SM), greenish gray (10YR6/1), loose, wet, fine grained sand, few fines, strong HCl reaction (continued) 151.1ft: greenish gray (10Y5/1), little fines						
-157.3	156.1	3	3	5		8					702-19		156.1ft: loose						
-167.3	166.1	2	4	7		11					702-20		166.1ft: medium dense						
-177.4	176.2	1	1	1		2					702-21		177.4ft: SILT with sand (ML), greenish gray (10Y5/1), very loose, wet, fine to medium grained sand, strong HCl reaction						
-190.4	189.2	1	1	4		5					702-22		189.2ft: loose, trace clay						
-197.4	196.2	1	1	1		2					702-23		197.4ft: Clayey SAND (SC), greenish gray (10Y5/1), very loose, wet, fine grained sand, some fines, strong HCl reaction						
-202.2	201.0	5	7	10		17					702-24		201.2ft: SILT with sand (ML), greenish gray (10Y5/1), very loose, wet, fine grained sand, strong HCl reaction 203.7ft: LEAN CLAY with sand (CL), greenish gray (10Y5/1), very stiff, wet, little fine grained sand, strong HCl reaction Boring Terminated at Elevation -203.7 ft						



SHEET 1 OF 2

BECHTEL PROJECT NO.: 25409				MACTEC PROJECT NO.: 6468-07-1950				COUNTY: Miami-Dade		GEOLOGIST: J. Liles			
SITE DESCRIPTION: Turkey Point COL				DRILL MACHINE: CME-550 (Miller)				DRILLER: R. White/ J. Dugger/ C. White			GROUND WATER (ft) 0 HR. NA 24 HR. NA		
BORING NO.: B-702				DRILL METHOD: Mud Rotary/ Core				SAMPLE METHODS: SPT/Core					
GROUND ELEV.: -1.2 ft (NAVD88)				NORTHING: 397,018 US ft (NAD83/90)				EASTING: 875,746 US ft (NAD83/90)		HAMMER (ID): 140 lb. Auto (M06)			
TOTAL DEPTH: 202.5 ft				CASING DEPTH: 4" to 25.0', 3" to 122.9'									
DATE STARTED: 2/26/08		COMPLETED: 3/6/08		CORE SIZE: HQ3		CORE BARREL TYPE: Triple Tube Wireline (Split inner liners)							
ELEV. (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		L O G	DESCRIPTION AND REMARKS			
				REC (ft) %	RQD (ft) %		REC (ft) %	RQD (ft) %					
										Begin Coring @ 35.9 ft			
-37.1	35.9	3.0	2:18	(3.0)	(2.8)	RUN-1	(11.5)	(10.1)		LIMESTONE, boundstone, white (2.5Y8/1), hard, extremely indurated, strong HCl reaction, coralline, few vugs (continued)			
-40.1	38.9		2:29	100%	93%		100%	88%					
		5.0	2:12	(5.0)	(4.2)	RUN-2				38.9ft: trace shell fragments, fossiliferous			
			2:25	100%	84%								
			2:03										
			1:51										
-45.1	43.9		2:22							42.0ft: loss of circulation			
		5.0	2:32	(4.3)	(3.5)	RUN-3				43.9ft: light gray (10YR7/1) to 47.4ft			
			2:16	86%	70%								
			1:28										
			1:50										
-50.1	48.9		0:55				(53.4)	(37.7)		LIMESTONE, boundstone, white (2.5Y8/1), hard, extremely indurated, fossiliferous, some vugs, strong HCl reaction (Lower Fort Thompson Formation)			
		5.0	1:49	(5.0)	(4.6)	RUN-4	79%	56%					
			1:35	100%	92%								
			1:29										
			1:36										
-55.1	53.9		2:05										
		5.0	0:00	(2.6)	(1.3)	RUN-5				53.9ft: medium hard to moderately hard, moderately indurated to indurated, trace vugs			
			0:32	52%	26%					54.0 to 55.0ft: soft zone			
			1:08										
-60.1	58.9		3:35										
			1:34										
		5.0	1:19	(5.0)	(3.5)	RUN-6				58.9ft: moderately hard, moderately indurated, little vugs			
			1:00	100%	70%								
			1:20										
			1:07										
-65.1	63.9		1:44										
		5.0	2:10	(2.0)	(1.6)	RUN-7				63.9ft: light gray (5Y7/1), hard, indurated, few vugs			
			1:20	40%	32%					65.0 to 69.0ft: soft zone			
			0:25										
			0:20										
-70.1	68.9		0:30										
		5.0	1:07	(4.7)	(4.0)	RUN-8				68.9ft: white (2.5Y8/1), moderately hard, some vugs			
			2:18	94%	80%								
			3:08			702-CS-01							
			2:03			702-CS-02							
-75.1	73.9		2:15										
		5.0	2:18	(4.2)	(3.5)	RUN-9				73.9ft: hard, few vugs			
			1:44	84%	70%								
			2:18										
-80.1	78.9		1:23										
			1:00										
		5.0	0:57	(4.0)	(1.7)	RUN-10				78.9ft: moderately hard, trace vugs			
			0:43	80%	34%								
			0:40										
			0:45										
-85.1	83.9		0:40										
		5.0	0:30	(4.5)	(3.3)	RUN-11				83.9ft: hard			
			0:31	90%	66%								
			1:30										
			1:25			702-CS-03							
-90.1	88.9		1:38										
		5.0	0:51	(4.6)	(3.0)	RUN-12				88.9ft: moderately hard, little vugs			
			0:55	92%	60%								
			1:04										
			0:48										
-95.1	93.9		0:39										
		5.0	0:33	(1.5)	(0.4)	RUN-13				93.9ft: moderately indurated			
			0:12	30%	8%								
			0:13										
			0:14										
-100.1	98.9		0:47										
		5.0	0:23	(4.4)	(3.9)	RUN-14				98.9ft: indurated, some vugs, little shell molds and casts			
			0:33	88%	78%								
			0:35										
			0:28			702-CS-04							
-105.1	103.9		0:38										
		5.0	0:23	(4.8)	(3.3)	RUN-15							
			0:28	96%	66%								
			0:19										
			0:28										
-110.1	108.9		0:22										
		5.0	0:18	(4.4)	(3.2)	RUN-16							
			0:18										

TURKEY POINT COL CORE TURKEY POINT GPJ TURKEY POINT COL GDI 5 30/08




SHEET 2 OF 2


BECHTEL PROJECT NO.: 25409	MACTEC PROJECT NO.: 6468-07-1950	COUNTY: Miami-Dade	GEOLOGIST: J. Liles
SITE DESCRIPTION: Turkey Point COL	DRILL MACHINE: CME-550 (Miller)	DRILLER: R. White/ J. Dugger/ C. White	GROUND WATER (ft)
BORING NO.: B-702	DRILL METHOD: Mud Rotary/ Core	SAMPLE METHODS: SPT/Core	0 HR. NA
GROUND ELEV.: -1.2 ft (NAVD88)	NORTHING: 397,018 US ft (NAD83/90)	EASTING: 875,746 US ft (NAD83/90)	24 HR. NA
TOTAL DEPTH: 202.5 ft	CASING DEPTH: 4" to 25.0', 3" to 122.9'	HAMMER (ID): 140 lb. Auto (M06)	
DATE STARTED: 2/26/08	COMPLETED: 3/6/08	CORE SIZE: HQ3	CORE BARREL TYPE: Triple Tube Wireline (Split inner liners)

ELEV. (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		L O G	DESCRIPTION AND REMARKS
				REC (ft) %	RQD (ft) %		REC (ft) %	RQD (ft) %		
										Continued from previous page
-115.1	113.9		0:19 0:28 1:08	88%	64%					LIMESTONE, boundstone, white (2.5Y8/1), hard, extremely indurated, fossiliferous, some vugs, strong HCl reaction (Lower Fort Thompson Formation) (continued)
		5.0	1:00 0:23 0:39 0:16 0:12	(0.9) 18%	(0.0) 0%	RUN-17	(0.3) 7%	(NA)		113.9ft: white (5Y8/1), trace vugs, shell molds and casts
-120.1	118.9									POORLY GRADED GRAVEL with silt and gravel (SP-SM), light gray (5Y7/1), wet, fine to coarse grained sand, fine to coarse limestone gravel fragments, strong HCl reaction (Tamiami Formation)
-120.4	119.2	0.3	0:20/0.3	(0.3) 100%	(0.0) 0%	RUN-18				119.2
										Coring Terminated at Elevation -120.4


TURKEY POINT COL CORE TURKEY POINT GPJ TURKEY POINT COL GDT 5/30/08




B-702 - Box 1




B-702 - Box 2




B-702 - Box 3



B-702 - Box 4



B-702 – Box 5



B-702 – Box 6



GEOTECHNICAL BORING LOG

Prepared By 2276 Date 8-19-08Checked By 502 Date 8/19/08

SHEET 1 OF 3

BECHTEL PROJECT NO.: 25409		MACTEC PROJECT NO.: 6468-07-1950		COUNTY: Miami-Dade		GEOLOGIST: J. Liles							
SITE DESCRIPTION: Turkey Point COL		DRILL MACHINE: CME-550 (Miller)		DRILLER: R. White/ J. Dugger		GROUND WATER (ft)							
BORING NO.: B-703		DRILL METHOD: Mud Rotary/ Core		SAMPLE METHODS: SPT/Core		0 HR. NA							
GROUND ELEV.: -1.3 ft (NAVD88)		NORTHING: 397,018 US ft (NAD83/90)		EASTING: 875,846 US ft (NAD83/90)		24 HR. NA							
TOTAL DEPTH: 150.0 ft		BORING DIAMETER: 4" to 27.9', 3" to 150.0'		CASING DEPTH: 4" to 27.9', 3" to 115.0'		HAMMER (ID): 140 lb. Auto (M06)							
DATE STARTED: 2/22/08		COMPLETED: 2/25/08		CORE SIZE: HQ3		BITS USED: 2 7/8" Roller Cone							
ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
		0.5ft	0.5ft	0.5ft	0	20	40	60	80	100			
-1.3					Ground Surface								
-1.3	0.0	WOH	WOH	WOH	WOH						703-1		-1.3
-3.8	2.5										703-2A&B		0.0
		WOH	6	17									-4.6
-6.5	5.2										703-3		3.3
-9.1	7.8	2	7	8							703-4		
-11.2	9.9										703-5		
-13.6	12.3	1	4	5							703-6		
											703-7		
-16.3	15.0	1	3	5							RUN-1		
-17.5	16.2	20	22	50/0.2							RUN-2		
-20.1	18.8										RUN-3		
-25.1	23.8										RUN-4		
-30.1	28.8										RUN-5		
-34.1	32.8										RUN-6		
-39.1	37.8										RUN-7		
-44.1	42.8										RUN-8		
-49.1	47.8										RUN-9		
-54.1	52.8										RUN-10		
-59.1	57.8										RUN-11		
-64.1	62.8										RUN-12		
-69.1	67.8										RUN-13		
-74.1	72.8												

TURKEY POINT COL BORE TURKEY POINT.GPJ TURKEY POINT COL.GPJ 8-18-08



SHEET 2 OF 3

BECHTEL PROJECT NO.: 25409				MACTEC PROJECT NO.: 6468-07-1950				COUNTY: Miami-Dade				GEOLOGIST: J. Liles			
SITE DESCRIPTION: Turkey Point COL				DRILL MACHINE: CME-550 (Miller)				DRILLER: R. White/ J. Dugger				GROUND WATER (ft)			
BORING NO.: B-703				DRILL METHOD: Mud Rotary/ Core				SAMPLE METHODS: SPT/Core				0 HR. NA			
GROUND ELEV.: -1.3 ft (NAVD88)				NORTHING: 397,018 US ft (NAD83/90)				EASTING: 875,846 US ft (NAD83/90)				24 HR. NA			
TOTAL DEPTH: 150.0 ft				BORING DIAMETER: 4" to 27.9', 3" to 150.0'				CASING DEPTH: 4" to 27.9', 3" to 115.0'				HAMMER (ID):140 lb. Auto (M06)			
DATE STARTED: 2/22/08				COMPLETED: 2/25/08				CORE SIZE: HQ3				BITS USED: 2 7/8" Roller Cone			
ELEV. (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT						SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
		0.5ft	0.5ft	0.5ft	0	20	40	60	80	100					
-76.1					Continued from previous page										
-79.1	77.8										RUN-14			LIMESTONE, boundstone, white (2.5Y8/1), hard, indurated, few vugs, fossiliferous, trace shell molds and casts (Lower Fort Thompson Formation) (continued)	
-84.1	82.8										RUN-15				
-89.1	87.8										RUN-16			87.8ft: moderately hard	
-94.1	92.8										RUN-17			92.8ft: little vugs, little shell molds and casts	
-99.1	97.8										RUN-18			97.8ft: hard	
-104.1	102.8										RUN-19			102.8ft: few shell molds and casts	
-109.1	107.8										RUN-20			107.8ft: POORLY GRADED SAND with silt (SP-SM), light gray (5Y7/1), loose, wet, fine grained sand, few carbonate nodules, strong HCl reaction (Tamiami Formation)	
-115.0	113.7	3	4	2							703-8			113.7ft: Switch sampling method to SPT	
-119.9	118.6	WOH	WOH	WOH							703-9			118.6ft: white (5Y8/1), very loose, fine to medium grained sand	
-125.1	123.8	3	3	3							703-10			123.8ft: Silty SAND (SM), light olive gray (5Y6/2), loose, wet, fine to medium grained sand, strong HCl reaction	
-129.9	128.6	2	4	7							703-11			127.0ft: POORLY GRADED SAND with silt (SP-SM), greenish gray (10Y5/1), medium dense, wet, fine grained sand, strong HCl reaction	
-134.8	133.5	4	5	4							703-12			133.5ft: Silty SAND (SM), greenish gray (10Y5/1), loose, wet, fine to coarse grained sand, fine gravel, trace shell fragments, strong HCl reaction	
-139.9	138.6	5	10	10							703-13			138.6ft: medium dense	
-144.8	143.5	5	6	10							703-14			143.5ft: Silty, Clayey SAND (SC-SM), greenish gray (10Y5/1), medium dense, wet, fine grained sand, strong HCl reaction	
-149.8	148.5	4	5	9							703-15			148.5ft:	

TURKEY POINT COL BORE TURKEY POINT COL GDT 8/18/08

BECHTEL PROJECT NO.: 25409						MACTEC PROJECT NO.: 6468-07-1950						COUNTY: Miami-Dade				GEOLOGIST: J. Liles					
SITE DESCRIPTION: Turkey Point COL						DRILL MACHINE: CME-550 (Miller)						DRILLER: R. White/ J. Dugger						GROUND WATER (ft)			
BORING NO.: B-703						DRILL METHOD: Mud Rotary/ Core						SAMPLE METHODS: SPT/Core						0 HR. NA			
GROUND ELEV.: -1.3 ft (NAVD88)						NORTHING: 397,018 US ft (NAD83/90)						EASTING: 875,846 US ft (NAD83/90)						24 HR. NA			
TOTAL DEPTH: 150.0 ft						BORING DIAMETER: 4" to 27.9', 3" to 150.0'						CASING DEPTH: 4" to 27.9', 3" to 115.0'						HAMMER (ID):140 lb. Auto (M06)			
DATE STARTED: 2/22/08						COMPLETED: 2/25/08						CORE SIZE: HQ3						BITS USED: 2 7/8" Roller Cone			
ELEV.	DEPTH	BLOW COUNT			BLOWS PER FOOT						SAMP.	▼ MOI	L O G	SOIL AND ROCK DESCRIPTION							
(ft)	(ft)	0.5ft	0.5ft	0.5ft	0	20	40	60	80	100	NO.										
-150.9					Continued from previous page																
														Silty SAND (SM), greenish gray (10Y5/1). medium dense, wet, fine to coarse grained sand, strong HCl reaction (<i>continued</i>) Boring Terminated at Elevation -151.3 ft							

TURKEY POINT COL BORE TURKEY POINT GPJ TURKEY POINT COL GDT 8'18'08



SHEET 1 OF 2

BECHTEL PROJECT NO.: 25409		MACTEC PROJECT NO.: 6468-07-1950		COUNTY: Miami-Dade	GEOLOGIST: J. Liles	
SITE DESCRIPTION: Turkey Point COL		DRILL MACHINE: CME-550 (Miller)		DRILLER: R. White/ J. Dugger		GROUND WATER (ft) 0 HR. NA 24 HR. NA
BORING NO.: B-703		DRILL METHOD: Mud Rotary/ Core		SAMPLE METHODS: SPT/Core		
GROUND ELEV.: -1.3 ft (NAVD88)		NORTHING: 397,018 US ft (NAD83/90)		EASTING: 875,846 US ft (NAD83/90)		
TOTAL DEPTH: 150.0 ft		CASING DEPTH: 4" to 27.9', 3" to 115.0'				HAMMER (ID): 140 lb. Auto (M06)
DATE STARTED: 2/22/08	COMPLETED: 2/25/08	CORE SIZE: HQ3	CORE BARREL TYPE: Triple Tube Wireline (Split inner liners)			

ELEV. (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		L O G	DESCRIPTION AND REMARKS
				REC. (ft) %	RQD (ft) %		REC. (ft) %	RQD (ft) %		
										Begin Coring @ 16.2 ft
-17.5	16.2	2.6	4:00	(2.5)	(1.8)	RUN-1	(3.9)	(1.8)		LIMESTONE, boundstone, white (2.5Y8/1), soft, wet, friable to moderately indurated, strong HCl reaction (Miami Formation) (<i>continued</i>)
-20.1	18.8		2:00	96%	69%		44%	20%		
		5.0	1:30/0.6	(1.4)	(0.0)	RUN-2				16.2ft: white (5Y8/1), soft, friable to moderately indurated, strong HCl reaction, locally interconnected vugs, oolitic
			1:00	28%	0%					18.8ft: trace shell fragments
-25.1	23.8		0:30							
		5.0	0:30	(3.0)	(2.4)	RUN-3				
			0:30	60%	48%					
-30.1	28.8		1:00				(16.5)	(15.1)		LIMESTONE, boundstone, white (5Y8/1), moderately hard, indurated, coralline, little vugs (Upper Fort Thompson Formation)
		4.0	1:30	(3.5)	(2.8)	RUN-4				
			2:30	88%	70%					28.8ft: white (2.5Y8/1), hard, recrystallized calcite, fossiliferous
-34.1	32.8		2:30							31.0ft: loss of circulation
		5.0	1:30	(5.0)	(5.0)	RUN-5				
			2:58	100%	100%					
-39.1	37.8		2:34							
		5.0	3:30	(5.0)	(4.9)	RUN-6				
			4:23	100%	98%					37.8ft: white (2.5Y8/1) to 39.0ft, then bluish gray (5PB6/1) to 42.8ft
-44.1	42.8		3:33	(5.0)	(5.0)	RUN-7	(55.9)	(46.8)		
		5.0	4:03	100%	100%		87%	73%		LIMESTONE, boundstone, white (2.5Y8/1), hard, indurated, few vugs, fossiliferous, trace shell molds and casts (Lower Fort Thompson Formation)
-49.1	47.8		4:22							
		5.0	2:30	(3.8)	(3.4)	RUN-8				
			3:52	76%	68%					
-54.1	52.8		1:31							
		5.0	2:11	(5.0)	(4.1)	RUN-9				
			2:23	100%	82%					52.8ft: little vugs
		5.0	1:46							
-59.1	57.8		2:48							
		5.0	2:15	(3.9)	(3.3)	RUN-10				
			3:08	78%	66%					
-64.1	62.8		3:09							
		5.0	3:28	(4.3)	(3.3)	RUN-11				
			2:35	86%	66%					
-69.1	67.8		2:13							
		5.0	4:19	(5.0)	(4.9)	RUN-12				
			3:00	100%	98%					67.8ft: white (10YR8/1), few vugs
-74.1	72.8		1:25							
		5.0	1:11	(4.7)	(4.2)	RUN-13				
			2:26	94%	84%					
-79.1	77.8		1:31							
		5.0	3:23	(4.3)	(3.0)	RUN-14				
			2:54	86%	60%					
-84.1	82.8		3:31							
		5.0	3:08	(4.7)	(4.1)	RUN-15				
			4:02	94%	82%					
-89.1	87.8		4:28							
		5.0	2:32	(2.3)	(0.0)	RUN-16				
			3:11	46%	0%					87.8ft: moderately hard
		5.0	0:31							
			1:50							
			3:57							
			3:49							
			7:07							
			2:13							
			1:00							
			0:54							
			0:52							
			0:38							
			0:21							
			0:14							
			0:49							

TURKEY POINT COL CORE TURKEY POINT GPJ TURKEY POINT COL GDT 8/18/08