


APPENDIX A DRAINAGE CALCULATIONS



WCS\FINAL\03047.04\DEC 2004 ANOD R041217_FLOODPLAIN RPT.DOC

REVISION 3 17 DECEMBER 2004

PAGE 1 OF 1

DRAINAGE CALCULATIONS

500 YEAR STORM CALCULATIONS

REF: DEPTH-DURATION FREQUENCY OF PRECIPITATION FOR TEXAS, W.H. ASQUITH, WATER RESOURCES INVESTIGATIONS REPORT 98-4044, U.S. GEOLOGICAL SURVEY, 1998 (98-4044)

GENERALIZED LOGISTIC DISTRIBUTION

$$Xd(F) = \xi + \alpha / \kappa \{1 - [(1 - F)/F]^{\kappa}\}$$
 EQ 10, 98-4044

WHERE: Xd(F)= PRECIPITATION DEPTH FOR A GIVEN

FREQUENCY

 $\xi, \alpha, and \kappa = \text{LOCATION}, SCALE AND SHAPE}$

PARAMETERS FOR THE GLO DIST.

F= ANNUAL NONEXCEEDANCE PROBABILITY

FOR 500 YEAR STORM


 $\xi = 1.93$ FIGURE 18, 98-4044

 $\alpha = 0.55$ FIGURE 32, 98-4044

 $\kappa = -0.22$ FIGURE 46, 98-4044

F= 0 998

Xd(F)= 924**INCHES**



Synthetic Rainfall Distributions and Rainfall Data Sources

The highest peak discharges from small watersheds in the United States are usually caused by intense, brief rainfalls that may occur as distinct events or as part of a longer storm. These intense rainstorms do not usually extended over a large area and intensities vary greatly. One common practice in rainfall-runoff analysis is to develop a synthetic rainfall distribution to use in lieu of actual storm events. This distribution includes maximum rainfall intensities for the selected design frequency arranged in a sequence that is critical for producing peak runoff.


Synthetic rainfall distributions

The length of the most intense rainfall period contributing to the peak runoff rate is related to the time of concentration (T_c) for the watershed. In a hydrograph created with NRCS procedures, the duration of rainfall that directly contributes to the peak is about 170 percent of the T_c . For example, the most intense 8.5-minute rainfall period would contribute to the peak discharge for a watershed with a T_c of 5 minutes. The most intense 8.5-hour period would contribute to the peak for a watershed with a 5-hour T_c .

Different rainfall distributions can be developed for each of these watersheds to emphasize the critical rainfall duration for the peak discharges. However, to avoid the use of a different set of rainfall intensities for each drainage area size, a set of synthetic rainfall distributions having "nested" rainfall intensities was developed. The set "maximizes" the rainfall intensities by incorporating selected short duration intensities within those needed for longer durations at the same probability level.


For the size of the drainage areas for which NRCS usually provides assistance, a storm period of 24 hours was chosen the synthetic rainfall distributions. The 24-hour storm, while longer than that needed to determine peaks for these drainage areas, is appropriate for determining runoff volumes. Therefore, a single storm duration and associated synthetic rainfall distribution can be used to represent not only the peak discharges but also the runoff volumes for a range of drainage area sizes.

Figure B-1 SCS 24-hour rainfall distributions



The intensity of rainfall varies considerably during a storm as well as geographic regions. To represent various regions of the United States, NRCS developed four synthetic 24-hour rainfall distributions (I, IA, II, and III) from available National Weather Service (NWS) duration-frequency data (Hershfield 1061; Frederick et al., 1977) or local storm data. Type IA is the least intense and type II the most intense short duration rainfall. The four distributions are shown in figure B-1, and figure B-2 shows their approximate geographic boundaries.

Types I and IA represent the Pacific maritime climate with wet winters and dry summers. Type III represents Gulf of Mexico and Atlantic coastal areas where tropical storms bring large 24-hour rainfall amounts. Type II represents the rest of the country. For more precise distribution boundaries in a state having more than one type, contact the NRCS State Conservation Engineer.



Rainfall data sources

This section lists the most current 24-hour rainfall data published by the National Weather Service (NWS) for various parts of the country. Because NWS Technical Paper 40 (TP-40) is out of print, the 24-hour rainfall maps for areas east of the 105th meridian are included here as figures B-3 through B-8. For the area generally west of the 105th meridian, TP-40 has been superseded by NOAA Atlas 2, the Precipitation-Frequency Atlas of the Western United States, published by the National Ocean and Atmospheric Administration.

East of 105th meridian

Hershfield, D.M. 1961. Rainfall frequency atlas of the United States for durations from 30 minutes to 24 hours and return periods from 1 to 100 years. U.S. Dept. Commerce, Weather Bur. Tech. Pap. No. 40. Washington, DC. 155 p.

West of 105th meridian

Miller, J.F., R.H. Frederick, and R.J. Tracey. 1973. Precipitation-frequency atlas of the Western United States. Vol. I Montana; Vol. II, Wyoming; Vol III, Colorado; Vol. IV, New Mexico; Vol V, Idaho; Vol. VI, Utah; Vol. VII, Nevada; Vol. VIII, Arizona; Vol. IX, Washington; Vol. X, Oregon; Vol. XI, California. U.S. Dept. of

Commerce, National Weather Service, NOAA Atlas 2. Silver Spring, MD.

Alaska

Miller, John F. 1963. Probable maximum precipitation and rainfall-frequency data for Alaska for areas to 400 square miles, durations to 24 hours and return periods from 1 to 100 years. U.S. Dept. of Commerce, Weather Bur. Tech. Pap. No. 47. Washington, DC. 69 p.

Hawaii

Weather Bureau. 1962. Rainfall-frequency atlas of the Hawaiian Islands for areas to 200 square miles, durations to 24 hours and return periods from 1 to 100 years. U.S. Dept. Commerce, Weather Bur. Tech. Pap. No. 43. Washington, DC. 60 p.

Puerto Rico and Virgin Islands

Weather Bureau. 1961. Generalized estimates of probable maximum precipitation and rainfall-frequency data for Puerto Rico and Virgin Islands for areas to 400 square miles, durations to 24 hours, and return periods from 1 to 100 years. U.S. Dept. Commerce, Weather Bur. Tech. Pap. No. 42. Washington, DC. 94 P.

Figure B-3 2-year, 24-hr rainfall





Figure B-4 5-year, 24-hour rainfall







Figure B-6 25-year, 24-hour rainfall








Figure B-8 100-year, 24-hour rainfall



100-YEAR 24-HOUR RAINFALL (INCHES)



WCS

FHH DRAINAGE CALCULATIONS

Dec-04

PAGE 1 OF 1

500 YEAR STORM CALCULATIONS

REF: DEPTH-DURATION FREQUENCY OF PRECIPITATION FOR TEXAS, W.H. ASQUITH, WATER RESOURCES INVESTIGATIONS REPORT 98-4044, U.S. GEOLOGICAL SURVEY, 1998 (98-4044)

GENERALIZED LOGISTIC DISTRIBUTION

$$Xd(F) = \xi + \alpha / \kappa \{1 - [(1 - F)/F]^{\wedge} \kappa\}$$
 EQ. 10, 98-4044

WHERE: Xd(F)= PRECIPITATION DEPTH FOR A GIVEN

FREQUENCY

 $\xi, \alpha, and \kappa = LOCATION, SCALE AND SHAPE$

PARAMETERS FOR THE GLO DIST.

F= ANNUAL NONEXCEEDANCE PROBABILITY

FOR 500 YEAR STORM

 $\xi = 1.93$ FIGURE 18, 98-4044

 $\alpha = 0.55$ FIGURE 32, 98-4044

 $\kappa = -0.20$ FIGURE 46, 98-4044

F= 0.998

Xd(F)= 8.71 INCHES






Figure 18. Location (ξ) parameter of generalized logistic (GLO) distribution for 24-hour precipitation duration in Texas.

36 Depth-Duration Frequency of Precipitation for Texas




Figure 32. Scale (α) parameter of generalized logistic (GLO) distribution for 24-hour precipitation duration in Texas.

50 Depth-Duration Frequency of Precipitation for Texas




Figure 46. Shape (κ) parameter of generalized logistic (GLO) distribution for 24-hour precipitation duration in Texas.

64 Depth-Duration Frequency of Precipitation for Texas

PMP CALCULATIONS

REF: HYDROMETEOROLOGICAL REPORT NO. 51, PROBABLE MAXIMUM PRECIPITATION ESTIMATES, UNITED STATES EAST OF THE 105TH MERIDIAN, NATIONAL WEATHER SERVICE, 1978 (HMR 51)

NOAA HYDROMETEOROLOGICAL REPORT NO. 52, APPLICATION OF PROBABLE MAXIMUM PRECIPITATION ESTIMATES - UNITED STATES EAST OF THE 105TH MERIDIAN, NATIONAL WEATHER SERVICE, 1982 (HMR 52)

AREA-DEPTH-DURATION FROM HMR 51

AREA	DURATION (HR)				
	6	12	24	48	72
SQ.MI.					
10	25.0	30.5	35.0	39.0	40.5
25	23.2	28.1	32.5	36.6	38.2
50	21.9	26.1	30.3	34.5	36.2
100	20.1	24.0	28.1	32.2	34.0
175	18.8	22.3	26.3	30.2	32.3
300	17.1	20.4	24.4	28.2	30.2
450	15.7	19.0	22.9	26.9	28.8
700	14.2	17.4	21.1	25.0	27.0
1000	13.0	16.1	19.6	23.5	25.0

FROM CURVE

AREA	18 - HR
SQ.MI.	DURATION
10	33.0
25	30.6
50	28.5
100	26.4
175	24.7
300	22.8
450	21.3
700	19.6
1000	18.1

FIRST THREE SIX HOURS

wcs

AREA	1	2	. 3
SQ.MI.			
10	25.0	5.5	2.5
25	23.2	4.9	2.5
50	21.9	4.2	2.4
100	20.1	3.9	2.4
175	18.8	3.5	2.4
300	17.1	3.3	2.4
450	15.7	3.3	2.3
700	14.2	3.2	2.2
1000	13.0	3.1	2.0

FROM GRAPH

AREA	1	2	. 3
SQ.MI.			
10	24.99	5.50	2.53
25	23.50	4.62	2.51
50	21.90	4.20	2.48
100	20.10	3.86	2.44
175	18.60	3.63	2.40
300	17.00	3.42	2.35
450	15.70	3.30	2.29
700	14.20	3.18	2.20
1000	13.00	3.08	2.02

6-HR INC.	PRECIP.	DELTA PRECIF
	(IN.)	(IN.)
1	24.99	24.99
2	30.49	5.50
3	33.02	2.53
4	35.00	1.98
5	36.00	1.00
6	37.00	1.00
7	38.00	1.00
8	39.00	1.00
9	39.50	0.50
10	40.00	0.50
11	40.30	0.30
12	40.50	0.20


FHH **DRAINAGE CALCULATIONS**

Dec-04 PAGE 3 OF 3

TEMPORAL DISTRIBUTION

INTERVAL	SEQUENCE A	SEQUENCE B
(HR)		
0 to 6	0.20	0.30
6 to 12	0.30	0.50
12 to 18	0.50	1.00
18 to 24	0.50	1.00
24 to 30	1.00	24.99
30 to 36	1.00	5. 50
36 to 42	1.00	2.53
42 to 48	2.53	1.98
48 to 54	24.99	1.00
54 to 60	5.50	1.00
60 to 66	1.98	0.50
66 to 72	1.00	0.20

74H 12/04







Z.

HAESTAD METHODS 37 Brookside Road Waterbury, CT 06708 USA Phone: +1-203-755-1666 • Fax: +1-203-597-1488 Internet: www.haestad.com & www.civilprojects.com

Project 12/04 Project # Engineer








APPENDIX B

HEC-HMS MODEL FOR THE CALCULATION OF THE 100-YEAR PEAK DISCHARGES



REVISION 3 17 DECEMBER 2004 PLAYA ELEVATION, STORAGE, OUTFLOW

ELEVATION AND STORAGE

WCS

ELEV.	AREA	DELTA E	AVERAGE AREA	STORAGE VOLUME	C	CUMULATIVE STORAGE
MSL	SQ. FT.	FT.	SQ FT.	CU. FT.	CU. FT.	ACFT
3478	402878	2	517775	0	0	0
3480	632672	2	811324.5	1035550	1035550	24
3482	989977	2	2375467	1622649	2658199	61
3484	3760957	2	6247779.5	4750934	7409133	170
3486	8734602	2	10261979	12495559	19904692	457
3488	11789356			20523958	40428650	928

OUTFLOW

WEIR EQUATION

 $Q= C*L*H^3/2$

WHERE:

Q= FLOW, CFS

C= WEIR COEFFICIENT


L= HORIZONTAL LENGTH, FT

H= HEAD ON WEIR, FT


ASSUME TOP OF PLAYA IS ELEVATION 3486 LENGTH OF 3486 CONTOUR IS 241 FT.


HEAD FT	Cw	Q CU FT./SEC
0.5	3.58	305
1.0	3.58	863
1.5	3,58	1585
2.0	3.56	2427


NOTE: Cw IS FROM WATER-RESOURCES ENGINEERING, LINSLEY AND FRANZINI





Meteorologic Model Input







































































HMS * Summary of Results

Project : WCS


Run Name : R1/22/04

 Start of Run
 : 01Dec00 0000
 Basin Model
 : 100YrAM1/22/04

 End of Run
 : 02Dec00 0000
 Met. Model
 : Met100 Year

 Execution Time
 : 29Jan04 1349
 Control Specs
 : Control 1

Hydrologic	Discharge	Time of	Volume	Drainage	
Element	Peak	Peak	(ac	Area	
	(cfs)		ft)	(sq mi)	•
Subbasin-4	297.60	01 Dec 00 1235	49.246	0.490	
Reach-2	297.60	01 Dec 00 1250	48.953	0.490	
Subbasin-2	440.24	01 Dec 00 1305	105.39	1.063	
playa	0.0	30 Nov 00 2400	0.0	1.063	
Reach-1	0.0	30 Nov 00 2400	0.0	1.063	
Subbasin-1A	256.61	01 Dec 00 1328	73.808	0.691	
Reach-1A	256.61	01 Dec 00 1345	73.298	0.691	
Subbasin-1B	174.42	01 Dec 00 1241	31.477	0.314	
Junction-1A	324.86	01 Dec 00 1332	104.77	1.005	
Reach-1B	324.86	01 Dec 00 1335	104.65	1.005	
Subbasin-3	86.653	01 Dec 00 1241	15.638	0.156	
Junction-1	364.05	01 Dec 00 1326	120.28	2.224	
Reach-3	364.05	01 Dec 00 1343	119.45	2.224	
<pre>qubbasin-5A</pre>	118.86	01 Dec 00 1234	19.306	0.192	
nction-2	686.69	01 Dec 00 1255	187.71	2.906	
Reach-4	686.69	01 Dec 00 1316	186.08	2.906	
Subbasin-5B	128.06	01 Dec 00 1251	26.440	0.265	
Junction-3	790.00	01 Dec 00 1314	212.52	3.171	
Reach-5	790.00	01 Dec 00 1328	211.28	3.171	
Subbasin-6	54.403	01 Dec 00 1225	7.4715	0.074	
Junction-4	803.31	01 Dec 00 1328	218.75	3.245	
Reach-6	803.31	01 Dec 00 1328	218.75	3.245	
Subbasin-7	43.582	01 Dec 00 1304	10.316	0.104	
Junction-5	841.14	01 Dec 00 1327	229.07	3.349	



or Claip	44.0		
		te same	
ាមិននាក់ហើយនៅប្រែក នៅថា	0; eMI/22/04		
	a 1986 per esta a sent	1 3842561	Para de la companya dela companya dela companya dela companya de la companya dela companya de la
A Spiciosini Vennes (SCS Durve Number.	nitial Abstraction (in)	Manuferviousness (XII)
vi vije iz	62		0.0
ia Elektrika	60	-	0.0
eriskese	60		0.0
(Distant)	60 .		0.0
န်းရှိခဲ့ _{ကြုပ်} (နှုပ်) နှ	60		0.0
หรือสหาสาสัง	60		0.0
urbasja (B	60		0.0
ublications and a second	60		0.0

