

Appendix 3A Dynamic Structural Analysis of the NuScale Power Module**3A.1 Seismic Analysis**

The dynamic analysis of the NuScale Power Module (NPM) uses a complete system model to represent the dynamic coupling of the reactor pressure vessel (RPV), containment vessel (CNV), reactor internals and core support, reactor core, surrounding pool water, and structures, systems, and components (SSC) supported by the NPM. The dynamic analysis of the complete NPM system is performed using time history dynamic analysis methods and a three dimensional (3-D) ANSYS (Section 3.9.1.2) finite element model. The NPM system model includes acoustic elements to represent the effects of fluid-structure interaction (FSI) due to pool water found between the CNV and pool floor and walls.

To account for possible dynamic coupling of the NPMs and the reactor building (RXB) system, a model of each of the NPMs is included in the RXB system model as described in Section 3.7.2.

The Reactor Building (RXB) system model, with representation of the NPMs, is analyzed for soil-structure interaction (SSI) in the frequency domain using computer code SASSI2010 (Section 3.7.5.3). Results from the RXB seismic system analysis include in-structure time histories at each NPM support location and the pool walls and floor surrounding the NPM. In-structure response spectra (ISRS) are also calculated. Results are shown in Section 3.7.2.

The detailed dynamic analysis of the NPM subsystem is performed using a 3D NPM system model using ANSYS. The NPM dynamic analysis provides in-structure time histories and in-structure response spectra for qualification of equipment supported on the NPM and time histories at core support locations for seismic qualification of fuel assemblies.

The seismic analysis of the NPM is provided in technical report TR-0916-51502, "NuScale Power Module Seismic Analysis."

3A.2 Blowdown Analysis

The blowdown analysis addresses events caused by the failure or actuation of piping and valves, including high-energy line breaks inside the CNV. These short term transient events result in system internal pressure waves and asymmetric cavity pressurization waves external to the pipe break or valve outlet.

Short term transient events require special treatment due to their rapidly changing thermal hydraulic conditions and resulting dynamic mechanical loads. In addition to the rapid nature of these transients, fluid-structure interactions are influential and are therefore also considered.

The blowdown analysis of the NPM is provided in technical report TR-1016-51669, "NuScale Power Module Short-Term Transient Analysis."

Appendix 3B Design Reports and Critical Section Details

This appendix summarizes the structural design and analysis of the Reactor Building (RXB) and Control Building (CRB). Section 3.8.4 and Section 3.8.5 describe these structures, their foundations, and the primary loads and load combinations. This appendix describes how those loads are combined and how the design is checked for adequacy. In addition, a selection of structural elements are described in detail. These elements are critical sections in that they represent parts of the structure that: (1) perform a safety-critical function, (2) are subjected to large stress demands, (3) are considered difficult to design or construct, or (4) are considered to be representative of the structural design. Within the safety related structures, the only true critical sections are those associated with the bays that contain the NuScale Power Modules (NPMs). The walls and slab at the NPM bays satisfy the first three criteria. To present a representative overview of the buildings, an additional 10 sections in the RXB and 7 in the CRB are provided as critical sections.

Section 3B.1 discusses the design methodology used for both buildings. Section 3B.2 provides the design report and critical section details for the RXB, and Section 3B.3 provides that information for the CRB.

The following critical sections are presented for the RXB:

Walls

- Wall at grid line 1 - West outer perimeter wall at foundation level
- Wall at grid line 3 - Interior weir wall and upper stiffener
- Wall at grid line 4 - Interior wall of RXB with two different thicknesses
- Wall at grid line 6 - Pool wall and upper stiffener wall
- Wall at grid line E - South exterior wall extending upward from foundation level

Slabs

- Basemat foundation
- Slab at EL. 100'-0" - Slab at grade
- Slab at EL. 181'-0" - Slab at roof

Pilasters

- Pilasters at grid line A

Beams

- Beam at EL. 75'-0"

Buttresses

- Buttress at EL. 126'-0"

NPM Bay

- West wing wall

- Pool wall
- NPM support skirt
- NPM lug restraint

The following critical sections are presented for the CRB:

Walls

- Wall at grid line 3 - Interior structural wall
- Wall at grid line 4 - East exterior structural wall
- Wall at grid line A - North exterior structural wall

Slabs

- Basemat foundation
- Slab at EL. 100'-0" - Slab at grade

Pilasters

- Pilasters at grid line 1

T-Beams

- T-Beam at EL. 120'-0"

Table 3B-55 and Table 3B-56 outline the critical sections and details for the RXB and CRB.

Section 1.2 contains architectural drawings of the RXB and CRB. Figure 1.2-10 through Figure 1.2-20 are for the RXB and Figure 1.2-21 through Figure 1.2-27 are for the CRB.

Table 3B-66 through Table 3B-94 provide section properties, reinforcement schedules, out-of-plane moment, and in-plane and out-of-plane shear capacities for critical sections in the RXB and CRB.

The concrete design process is organized by defining each wall, slab, pilaster, buttress and T-beam into several small zones on the structure and assigning identification names to these regions. The zone definitions are labeled according to the naming conventions below:

Wall Zone Definition Name: "A";"B";"C-D";"E-F"

where,

"A" = Building name

"B" = Grid line ID designation

"C-D" = Wall zone grid line ID range in the horizontal direction

"E-F" = Wall zone elevation range

For example a zone labeled as "RXB;1;E-D;100-120" is a RXB wall zone on grid line 1, between grid lines E and D, and located between elevations 100' and 120'.

Slab Zone Definition Name: "A";"B";"C-D";"E-F"

where,

"A" = Building name

"B" = TOC elevation designation

"C-D" = Slab zone grid line ID range in the E-W direction

"E-F" = Slab zone grid line ID range in the N-S direction

For example, a zone labeled as "RXB;100;1-2;A-B" is an RXB slab zone at the 100' elevation between grid lines 1 and 2, and between grid lines A and B.

Pilaster Zone Definition Name: "A";"B";"CD";"E-F"

where,

"A" = Building name

"B" = Pilaster abbreviation

"C" = the wall grid line ID where the pilaster is located

"D" = the grid line that represents the centerline of where the pilaster is located

"E-F" = Elevation IDs that represent where the pilaster is between in the vertical direction

For example, a zone labeled as "RXB;PI;A2;75 - 100" is a RXB pilaster on wall grid line A, on grid centerline 2, between elevations 75' 100'.

T-Beam Zone Definition Name: "A";"B";"C";"D-E";"F-G"

where,

"A" = Building name

"B" = T-beam abbreviation

"C" = Elevation designation

"D-E" = Slab zone grid line range in the E-W direction

"F-G" = Slab zone grid line range in the N-S direction

For example, a zone labeled as "RXB;TB;100;1-2;A-B" is a RXB T-beam at Elevation 100', between grid lines 1 and 2, and between grid lines A and B. If multiple zones lie between two grid lines, the numbering of (1), (2), or (3) is added to the end of the definition name.

Buttress Zone Definition Name: "A";"B";"C";"D";"E-F"

where,

"A" = Building name

"B" = Buttress abbreviation

"C" = the wall grid line ID where the buttress is located

"D" = Elevation designation

"E-F" = Grid line IDs that represent the buttress range in the horizontal direction

For example, a zone labeled as "RXB;B;A;145.5;1-2" is a RXB buttress on wall grid line A, at elevation 145'-6", between grid lines 1 and 2.

In addition to the zone names, figures are included in Section 3B.2 and Section 3B.3 that visually place the section within the building.

3B.1 Methodology

SAP2000 (Reference 3B-1) and SASSI2010 (Reference 3B-2) are used to develop the static and dynamic loads as described in Section 3.7 and 3.8. The methodology and equations from ACI-349 (Reference 3B-3) are used to develop the forces and moments used for the design of the RXB and CRB, unless otherwise noted. The predominant governing load combination is Combination 10 from Table 3.8.4-1 (ACI 349 Load Equation 9-6). The demand forces and moments have been increased by 5 percent to account for the effect of accidental torsion as described in Section 3.7.2.11. The strength reduction factors used for the reinforced concrete design are provided in Table 3B-54.

3B.1.1 Wall and Slab Design Methodology

The standard global and local axis orientation is shown below.

- Global X- Axis - east-west direction
- Global Y- Axis - north-south direction
- Global Z- Axis - vertical direction
- Local "x" axis - always horizontal
- Local "y" axis - parallel to global y for slab or parallel to global z for wall
- Local "z" axis - perpendicular to the x and y axes by the right-hand rule

The total area of the longitudinal reinforcing steel provided in an element is the sum of the steel required for (i) membrane tension, (ii) in-plane shear, and (iii) out-of-plane

moment. The maximum compression in an element is a combination of flexural compression (out-of-plane moment) and membrane compression. A simplified approach is used for addressing combined effects of flexural and membrane compression. For the simplified method, the sectional area, defined by $(b = 12") \cdot (a)$, provides for flexural compression. The net sectional area, defined by $(b = 12") \cdot (h - a)$, is available for carrying membrane compression. The maximum membrane compressive stress is calculated to be $(S_{xx} \text{ or } S_{yy})/[12(h - a)]$. The Whitney stress block defines parameters "a" and "h" as shown in Figure 3B-1. The maximum membrane compressive stress is less than the allowable compressive strength for membrane compression.

3B.1.1.1 Averaging Demand Forces and Moments

The finite element models often show highly localized forces and moments that are not representative of the average demand forces and moments over the wall and slab sections. Therefore, the design zones with demand/capacity (D/C) ratio exceedances over a single finite element are averaged with adjacent elements to show a more realistic value. When necessary for averaging purposes of finite element analysis generated element forces and moments, the length of the failure plane considered is taken approximately 4 times the thickness of the element.

An acceptable section cut length varies for different element forces, based on ACI code design provisions as well as the various applied forces. Critical section lengths vary depending upon the applied loadings, however element forces can be averaged over the critical section length, considering the fact that the forces or moments are redistributed to adjacent areas once the higher-stressed region reaches its strength limit.

For the in-plane shear stress check used to demonstrate acceptable wall and slab thickness, average demand shear stresses over the full available section length of wall or slab cross-sections are used. The cross-sectional areas used for the stress check also include the presence of pilasters and T-beams.

3B.1.1.2 Wall and Slab Design Forces and Moments

For each element in the analysis models, static forces and moments are obtained from SAP2000 analysis for non-seismic loads. The direction of the loads result in either compression (negative) or tension (positive) membrane forces due to the static forces and moments being monotonic. The forces and moments for SAP2000 analysis are listed below and are shown in Figure 3B-2 and Figure 3B-3.

- F11, F22 Membrane forces
- F12 In-plane shear
- M11, M22 Out-of-plane moment
- M12 Torsional moment
- V13, V23 Out-of-plane shear

Similarly, for each element in the analysis models, dynamic forces and moments are obtained from SASSI2010 soil-structure interaction analysis for seismic loads. The

dynamic forces and moments are reversible (not monotonic) and therefore consider the direction that is most adverse in a load combination. The SASSI2010 x- and y-components of membrane tension or compression, out-of-plane moment, and out-of-plane shear are enveloped in order to ensure compliance with the local axes of SAP2000. The forces and moments from SASSI2010 are listed below and shown in Figure 3B-4.

- S_{xx}, S_{yy} Membrane forces
- S_{xy} In-plane shear
- M_{xx}, M_{yy} Out-of-plane moment
- M_{xy} Torsional moment
- V_{xz}, V_{yz} Out-of-plane shear

3B.1.1.3 Wall and Slab Design Approach

The design check approach uses load combinations that involve both static and dynamic load cases from SAP2000 and SASSI2010 to get combined element forces and moments. The shell element forces and moments from the two analyses are shown in Table 3B-1. Additional terms used in this analysis combined are shown below:

- S_{xx} Membrane tension/compression in local x direction
- S_{yy} Membrane tension/compression in local y direction
- S_{xy} In-plane shear acting along both faces
- $(M_{xx} + M_{xy})$ Out-of-plane moment about local y-axis
- $(M_{yy} + M_{xy})$ Out-of-plane moment about local x-axis
- V_{xz} Out-of-plane shear in local z direction on local x face
- V_{yz} Out-of-plane shear in local z direction on local y face

The terms in-plane and out-of plane are abbreviated as IP and OOP in tables and figures. The following paragraphs describe the design check approach for a structural wall. The approach is equally applicable for slabs.

The design forces and moments that produce tensile, shear and flexural stress are resisted by the reinforcing steel and stirrups in the following manner:

- 1) The main reinforcing steel is provided at the face of the wall (such as 1 layer #9 @ 12" centers = 2.00 in²) and considered for the resistance of membrane tension forces (S_{xx} or S_{yy}), out-of-plane moments ($(M_{xx} + M_{xy})$ or $(M_{yy} + M_{xy})$), and in-plane shear (S_{xy}).
- 2) The out-of-plane shear forces on the section are resisted by the strength of concrete and, if required, the addition of stirrups (such as 1 leg #6 stirrups @ 12" centers).

- 3) The design forces and moments that produce compressive stress, namely membrane compression and flexural compression, are resisted by the strength of concrete.

Design for Horizontal Reinforcement (Local X)

The area of horizontal reinforcing steel due to membrane tension, in-plane shear and out-of-plane moment are calculated as follows. In the calculation of the required in-plane shear steel required, V_{conc} is the in-plane shear resisted by concrete and is calculated using a shear wall coefficient of 2.

Area of steel required due to membrane tension:

$$A_{s1x} = \frac{S_{xx}}{\phi_m f_y} \quad \text{Eq. 3B-1}$$

Area of steel required due to in-plane shear:

$$A_{s2x} = \frac{S_{xy} - V_{conc}}{\phi_v f_y} \quad \text{Eq. 3B-2}$$

Area of steel required due to out-of-plane moment:

$$A_{s3x} = \frac{M_{xx} + M_{xy}}{\phi_m j d f_y} \quad \text{Eq. 3B-3}$$

where,

V_{conc} is the factored capacity of concrete,

jd is the lever arm, the distance between the resultant compressive force and the resultant tensile force (in), and

j is a dimensionless ratio used to define the lever arm, jd . It varies depending on the moment acting on the wall section.

The sum of membrane tension, in-plane shear, and out-of-plane moment steel areas must be less than that provided by the chosen horizontal reinforcement.

Area of total horizontal reinforcing steel:

$$A_{S \text{ Horiz}} = A_{s1x} + A_{s2x} + A_{s3x} \quad \text{Eq. 3B-4}$$

D/C ratio:

$$D/C_{\text{HorizReinf}} = \frac{A_{S \text{ Horiz}}}{A_{S \text{ Provided H}}} \quad \text{Eq. 3B-5}$$

Total horizontal reinforcing steel provided ($A_{S \text{ Provided H}}$) is divided equally on each face.

Horizontal membrane compressive stress:

$$f_{xx} = \frac{S_{xx}}{b(h-a)} \quad \text{Eq. 3B-6}$$

Membrane compression strength:

$$\sigma_{\text{all}} = \frac{0.8\phi_c[0.85f'_c(A_g - A_s) + f_y A_s]}{A_g} \quad \text{Eq. 3B-7}$$

The horizontal membrane compressive stress must be less than the membrane compressive strength.

Membrane compression D/C ratio:

$$D/C_{\text{Horiz Comp}} = \frac{f_{xx}}{\sigma_{\text{all}}} \quad \text{Eq. 3B-8}$$

Design for Vertical Reinforcement (Local Y)

The area of vertical reinforcing steel due to membrane tension, in-plane shear, and out-of-plane moment are calculated as follows. In the calculation of in-plane shear steel required, V_{conc} is the in-plane shear resisted by concrete and is calculated using a shear wall coefficient of 2.

Area of steel required due to membrane tension:

$$A_{s1y} = \frac{S_{yy}}{\phi_m f_y} \quad \text{Eq. 3B-9}$$

Area of steel required due to in-plane shear:

$$A_{s2y} = \frac{S_{xy} - V_{\text{conc}}}{\phi_v f_y} \quad \text{Eq. 3B-10}$$

Area of steel required due to out-of-plane moment:

$$A_{s3y} = \frac{M_{yy} + M_{xy}}{\phi_m j d f_y} \quad \text{Eq. 3B-11}$$

where,

V_{conc} is the factored capacity of concrete,

jd is the lever arm, the distance between the resultant compressive force and the resultant tensile force (in), and

j is a dimensionless ratio used to define the lever arm, jd . It varies depending on the moment acting on the wall section.

The sum of membrane tension, in-plane shear, and out-of-plane moment steel areas must be less than that provided by the chosen vertical reinforcement shown below:

Total vertical reinforcing steel:

$$A_{S\text{ Vert}} = A_{s1y} + A_{s2y} + A_{s3y} \quad \text{Eq. 3B-12}$$

D/C ratio:

$$D/C_{\text{Vert Reinf}} = \frac{A_{S\text{ Vert}}}{A_{S\text{ Provided V}}} \quad \text{Eq. 3B-13}$$

Total vertical reinforcing steel provided ($A_{S\text{ Provided V}}$) is divided equally on each face.

Vertical membrane compressive stress:

$$f_{yy} = \frac{S_{yy}}{b(h-a)} \quad \text{Eq. 3B-14}$$

Membrane compression strength:

$$\sigma_{all} = \frac{0.8\phi_c[0.85f'_c(A_g - A_s) + f_y A_s]}{A_g} \quad \text{Eq. 3B-15}$$

Membrane compression D/C ratio:

$$D/C_{\text{Vert Comp}} = \frac{f_{yy}}{\sigma_{all}} \quad \text{Eq. 3B-16}$$

Shear Friction in the X Plane

The design check for shear friction is based on a coefficient of friction of $\mu=1$. The XZ plane shear friction area of steel is the sum of the in-plane shear and out-of-plane moment. The in-plane shear S_{xy} must be less than the nominal shear friction capacity.

XZ plane shear friction:

$$A_{vfx} = A_{S \text{ Provided } V} - A_{s1x} \quad \text{Eq. 3B-17}$$

Nominal shear friction capacity:

$$\phi_v V_{nx} = \min (\phi_v A_{vfx} f_y \mu, \phi_v f_c A_c, \phi_v 800 A_c) \quad \text{Eq. 3B-18}$$

Shear friction check:

$$S_{xy} < \phi_v V_{nx} \quad \text{Eq. 3B-19}$$

Shear Friction in the Y Plane

The design check for shear friction is based on a coefficient of friction of $\mu=1$. The YZ plane shear friction area of steel is the sum of the in-plane shear and out-of-plane moment. The in-plane shear S_{xy} must be less than the nominal shear friction capacity.

YZ plane shear friction:

$$A_{vfy} = A_{S \text{ Provided } H} - A_{s1y} \quad \text{Eq. 3B-20}$$

Nominal shear friction capacity:

$$\phi_v V_{ny} = \min (\phi_v A_{vfy} f_y \mu, \phi_v f_c A_c, \phi_v 800 A_c) \quad \text{Eq. 3B-21}$$

Shear friction check:

$$S_{xy} < \phi_v V_{ny} \quad \text{Eq. 3B-22}$$

In-Plane Shear Check

The area of reinforcing steel required for the in-plane shear stress (S_{xy}) is always added to the total steel area for the horizontal and vertical reinforcement. The added in-plane shear areas are A_{S2x} and A_{S2y} .

However, another design check for the in-plane shear forces, which is independent of the amount of the reinforcing steel but dependent upon having sufficient

thickness of the concrete section, can be performed. The maximum in-plane shear capacity is the maximum allowable shear on a given section based on the dimensional properties and concrete compressive strength. For the nominal in-plane shear strength, the coefficient defining the relative contribution to nominal wall shear strength is a conservative value of 2 when calculating the nominal in-plane shear strength.

Maximum in-plane shear capacity:

$$\phi_v V_n = \phi_v 8A_{cv} \sqrt{f'_c} \quad \text{Eq. 3B-23}$$

Nominal in-plane shear strength:

$$\phi_v V_n = \phi_v A_{cv} (\alpha_c \sqrt{f'_c} + \rho_t f_y) \quad \text{Eq. 3B-24}$$

In-plane shear check:

$$S_{xy} < \phi_v V_n \quad \text{Eq. 3B-25}$$

The averaging for in-plane shear can be done on the entire span of the wall.

Out-of-Plane Shear in XZ Plane

Out-of-plane shear capacity is based on a shear strength reduction factor of $\phi_v = 0.75$. The shear capacity is adjusted when the section is subjected to membrane compression or tension.

See Figure 3B-2 through Figure 3B-5 for SAP2000/SASSI2010 sign convention of positive forces and moments.

Capacity of concrete for elements
subjected to axial compression (S_{xx} is positive):

$$\phi V_{C,XZ} = 2\phi_v \left(1 + \frac{S_{xx}}{2000A_g} \right) \sqrt{f'_c} b_w d \quad \text{Eq. 3B-26}$$

Capacity of concrete for elements
subjected to axial tension (S_{xx} is negative):

$$\phi V_{C,XZ} = 2\phi_v \left(1 + \frac{S_{xx}}{500A_g} \right) \sqrt{f'_c} b_w d \quad \text{Eq. 3B-27}$$

Out-of-plane shear D/C ratio:

$$D/C_{XZ} = \frac{V_{XZ}}{\phi V_{C,XZ} + \phi V_S} \quad \text{Eq. 3B-28}$$

Out-of-Plane Shear in YZ Plane

Out-of-plane shear capacity is based on a shear strength reduction factor of $\phi_v = 0.75$. The shear capacity is adjusted when the section is subjected to membrane compression or tension.

Capacity of concrete for elements subjected to axial compression (S_{yy} is positive):

$$\phi V_{C,YZ} = 2\phi \left(1 + \frac{S_{yy}}{2000A_g} \right) \sqrt{f'_c} b_w d \quad \text{Eq. 3B-29}$$

Capacity of concrete for elements subjected to axial tension (S_{yy} is negative):

$$\phi V_{C,YZ} = 2\phi \left(1 + \frac{S_{yy}}{500A_g} \right) \sqrt{f'_c} b_w d \quad \text{Eq. 3B-30}$$

Out-of-plane shear D/C ratio:

$$D/C_{YZ} = \frac{V_{YZ}}{\phi V_{C,YZ} + \phi V_S} \quad \text{Eq. 3B-31}$$

Headed bars were introduced in ACI 318-08 (Reference 3B-9), followed by ACI 349-13. Section 11.11.3 of ACI 318-08 allows the use of shear reinforcement for slabs and footings in the form of bars, as in the vertical legs of stirrups. Section 11.11.5 of ACI 318-08 permits headed shear stud reinforcement. Compared with a leg of a stirrup having bends at the ends, a stud head exhibits smaller slip, resulting in smaller shear crack widths. This improved performance results in larger limits for shear strength and spacing between peripheral lines of headed shear stud reinforcement. Therefore, the design may use headed bars for shear reinforcement in slabs and walls, as needed, to eliminate congestion due to high bar density.

3B.1.1.4 Basemat Foundation Design Force and Moments

The design check considers bounding demand forces and moments for the basemat.

The demand forces and moments of the design check consist of:

- Out-of-plane moment, in kip-ft per unit length in feet: maximum out-of-plane moment in either of the two perpendicular directions in-plane
- Out-of-plane shear force, in kips per unit length in feet: maximum out-of-plane shear force from either of the planes XZ or YZ
- In-plane shear force, in kips per unit length in feet: maximum in-plane shear force
- Axial force along x- or y-direction in kips per unit length in feet: maximum axial tension along the x- or y-axis

The SASSI2010 program calculates the dynamic stresses due to a seismic excitation at the centroid of a solid element. These stresses are post-processed to obtain the forces and bending moments in the basemat foundation. The dynamic forces and moments in a solid element are combined with the corresponding static forces and moments calculated with SAP2000. For a solid element, the SAP2000 program calculates only the nodal forces at all eight nodes of the solid element. Therefore, these nodal forces also require post-processing to convert to forces and moments.

3B.1.2 T-Beam, Buttress and Pilaster Methodology

These frame elements increase the stiffness of the walls or slabs which helps to mitigate the effects of out-of-plane seismic loads. The design check determines the D/C ratios for strong axis bending, strong axis shear, axial compression, and axial tension by using the combined forces and moments due to seismic and non-seismic loads.

3B.1.2.1 T-Beam, Buttress and Pilaster Design Forces and Moments

The SAP2000 analysis for non-seismic loads provides the static forces and moments for the frame elements in the analysis models. The direction of the loads are specific resulting in either compression (negative) or tension (positive) forces due to the static forces being monotonic. Figure 3B-5 defines the frame element forces and moments for SAP2000 shown below.

- P Axial force
- V2 Shear force in the 1-2 plane
- V3 Shear force in the 1-3 plane
- T Axial torque (about the 1-axis)
- M2 Bending moment in the 1-3 plane (about the 2-axis)
- M3 Bending moment in the 1-2 plane (about the 3-axis)

The SASSI2010 soil-structure interaction analysis for seismic loads provides the dynamic forces and moments for frame elements in the analysis models. The dynamic forces and moments consider the direction that is most adverse in a load combination due to the fact that they are reversible (not monotonic). Figure 3B-6 defines the forces and moments extracted from SASSI2010 listed below.

- P1 Axial force
- P2 Shear force in the 1-2 plane
- P3 Shear force in the 1-3 plane
- M1 Axial torque (about the 1-axis)
- M2 Bending moment in the 1-3 plane (about the 2-axis)
- M3 Bending moment in the 1-2 plane (about the 3-axis)

The combined resultant force or moment obtained from the combination of these loads uses the SAP2000 naming convention.

3B.1.2.2 T-Beam, Buttress and Pilaster Design Approach

The frame design check approach uses load combinations of both static and dynamic load cases to get combined element forces and moments. The frame element forces and moments are shown in Table 3B-1. The SAP2000 terminology is used.

The design of reinforced concrete T-beam and pilaster sections uses the following methodology for frame elements.

Design for Strong Axis Bending

The strong axis bending of the frame element governs the design. Iterations of the moment determine the required amount of strong axis bending rebar. The design of the frame element uses the equation for the nominal moment capacity shown below. The total combined static and dynamic moment must be less than the factored nominal moment capacity.

Nominal moment capacity:

$$\phi M_{n3} = \phi_m A_s f_y \left(d_{A2} - \frac{a}{2} \right) \quad \text{Eq. 3B-32}$$

Strong axis bending D/C ratio:

$$D/C_3 = \frac{M3}{\phi M_{n3}} \quad \text{Eq. 3B-33}$$

Design for Strong Axis Shear

The strong axis shear capacity uses a shear strength reduction factor of $\phi_v=0.75$.

The shear capacity is adjusted when the section is subjected to membrane compression or tension.

Capacity of concrete for elements
subjected to axial compression (P is positive):

$$\phi V_{C,2} = 2\phi_v \left(1 + \frac{P}{2000A_g} \right) \sqrt{f'_c} b_w d \quad \text{Eq. 3B-34}$$

Capacity of concrete for elements
subjected to axial tension (P is negative):

$$\phi V_{C,2} = 2\phi_v \left(1 + \frac{P}{500A_g} \right) \sqrt{f'_c} b_w d \quad \text{Eq. 3B-35}$$

The strong axis shear demand must be less than the combined capacity of concrete and stirrups.

Out-of-plane shear D/C ratio:

$$D/C_2 = \frac{V_2}{\phi V_{C,2} + \phi V_s} \quad \text{Eq. 3B-36}$$

Design for Compression or Tension (Axial Force)

With the exception for the dynamic axial force, the design SAP2000 axial force is known to be in tension or compression. The dynamic axial load is both added and subtracted from the static axial load to create a minimum and maximum value. Compression is not checked if both the minimum and maximum values are positive and tension is not checked if both values are negative.

Axial compression capacity:

$$\phi P_C = \phi_c 0.8 f'_c A_g \quad \text{Eq. 3B-37}$$

Compression D/C ratio:

$$D/C_C = \frac{P}{\phi P_C} \quad \text{Eq. 3B-38}$$

Axial tension capacity:

$$\phi P_T = \phi_m f_y A_s \quad \text{Eq. 3B-39}$$

Tension D/C ratio:

$$D/C_T = \frac{P}{\phi P_T} \quad \text{Eq. 3B-40}$$

3B.1.3 Thermal and Pressurization Analysis and Design Methodology

The strains for static, dynamic, and hydrodynamic pressure loads are calculated from the resulting stresses in the reinforcing steel. The strains for the reinforcing steel using T_0 loads for load combination 10 and $T_a + P_a$ loads for load combination 13 of Table 3.8.4-1 are obtained from the ANSYS analysis described in Section 3.8.4.4.1. The total strain in the reinforcing steel is obtained by summing the two strains. The following steps are used to evaluate the final strain obtained for each load case:

Step 1: If the total strain in the reinforcing steel is less than $1.2\varepsilon_y$, the section is considered acceptable based on the 4th bullet in Section 1.3 of ACI 349.1R-07 (Reference 3B-8), which states the following about the reinforcing steel strain with thermal gradient, $1.2\varepsilon_y$: "Such an exceedance is inconsequential, and will not reduce the capacity of the concrete section for mechanical loads." If the strain in the concrete is less than 0.003 in/in, the section is considered acceptable since this value is the limiting strain set by Section 10.2.3 of ACI-349-06.

Step 2: If the total strain in the steel exceeds $1.2\varepsilon_y$ for any element in Step 1, the average strains from adjoining elements are calculated, since the finite element models often show highly localized forces and moments and the average presents a more realistic value. For computation of average strain, an effective length of approximately 4 times the thickness of the structural component is considered. However, for the walls with liner plates such as pool walls, elements that correspond to larger lengths of the walls can be used for average strain determination. It is rationalized that the concrete walls confined within the liner plates provide enhanced integrity of the concrete walls to withstand the applied forces as an integrated entity that will enable consideration of larger wall lengths. If the average strain is less than $1.2\varepsilon_y$, the section is considered acceptable.

Step 3: For sections that did not pass Step 2, the reinforcing steel in the region is further reviewed to determine if there is additional steel from the intersecting members that are underutilized.

3B.2 Reactor Building

3B.2.1 Design Report

Structural Description and Geometry

The RXB is a Seismic Category I concrete structure. For a detailed description of the RXB, see Section 3.8.4.1.1. The RXB geometry and floor layout are shown in Figure 1.2-11 through Figure 1.2-20.

Structural Material Requirements

The RXB design is based on the following material properties:

- Concrete
 - Compressive Strength - 5 ksi (7 ksi for exterior walls of the RXB above grade)
 - Modulus of Elasticity - 4,031 ksi
 - Shear Modulus - 1,722 ksi
 - Poisson's Ratio - 0.17
- Reinforcement
 - Yield Stress - 60 ksi (ASTM A615 Grade 60 or ASTM A706 Grade 60)
 - Tensile Strength - 90 ksi (A615 Grade 60), 80 ksi (A706 Grade 60)
 - Elongation - See ASTMs A615 and A706
- Structural Steel
 - Grade - ASTM A992 (W shapes), ASTM A500 Grade B (Tube Steel), ASTM A36 (plates)
 - Ultimate Tensile Strength - 65 ksi A992, 58 ksi A500 Grade B and A36
 - Yield Stress - 50 ksi A992, 46 ksi A500 Grade B, 36 ksi A36
- Foundation Media

For a description of the soils considered in the design of the RXB, see Section 3.7.1.3.1.

Structural Loads

The structural loads for the RXB are discussed in detail in Sections 3.7.1 and 3.8.4 for seismic and non-seismic loads, respectively.

Structural Analysis and Design

- Design Computations of Critical Elements

The design methodology of RXB related Critical Elements is discussed in Section 3B.1. Specific RXB Critical Elements analyzed are discussed in Section 3B.2.

- Stability Calculations

Stability of the RXB is addressed in Section 3.8.5.4.1, Section 3.8.5.5, and Section 3.8.5.6.1.

Summary of Results

See Section 3B.2.2 through Section 3B.2.7. The D/C ratios presented represent the bounding design values.

Conclusions

The D/C ratios presented are all less than 1.0. Therefore, the Critical Elements satisfy the design criteria for the investigated loading.

3B.2.2 Design Approach -Walls

The combined SAP2000 and SASSI2010 design forces and moments are used in the element-based design check. The design check determines the D/C ratios for the horizontal and vertical wall reinforcement including the various shear failure modes based on the combined demand forces and moments.

An iterative design check approach is used to determine the appropriate uniform reinforcement pattern for a given structural wall section based on the maximum combined design forces and moments. A representative wall shell element within the design check zone is selected to demonstrate the element-based design check that is repeated for all shell elements within the wall.

This design approach is used for each structural wall. A summary of the D/C ratios for each wall is presented using specified uniform reinforcement. If all elements pass, then the wall section is considered acceptable. The general design goal is to achieve D/C ratios below 0.8. Demand/Capacity ratios higher than 0.8 but less than 1.0 are also acceptable, however case by case justifications are provided.

When individual elements exceed design requirements, the region is evaluated. Often, more accurate design moments and forces are obtained by averaging the results of several elements. If this approach is inappropriate for the location (or does not produce acceptable results) additional reinforcing is added to increase section capacity.

The summary tables of D/C ratios at each gridline shows the maximum D/C ratios within each design check zone. If necessary, a separate check of averaging for walls that contain elements exceeding the in-plane shear limit, or contain elements that exceed shear friction limits is performed to ensure the D/C ratios are acceptable.

In-plane shear for the adequacy of concrete wall thickness is checked for all elements in the RXB. Several individual elements in the wall at grid line 3 encountered In-plane shear exceedances. Where individual elements in the wall exceed in-plane shear limits, the elements are averaged as shown in Table 3B-51. The cross-section was checked based on calculating the average in plane shear over the entire wall section, and is acceptable. Note that the example in Table 3B-51 is a different element than shown in Table 3B-4 through Table 3B-6.

Shear friction is also checked for all elements in the RXB. Some individual elements in the wall at grid line 3 encountered shear friction exceedances. An example of averaging over additional elements is shown in Table 3B-52. The example in Table 3B-52 is a different element than shown in Table 3B-4 through Table 3B-6.

3B.2.2.1 Wall at Grid Line 1

The wall at grid line 1 is an exterior structural wall on the west side of the RXB. This wall is 5 feet thick. The SAP2000 analysis model elevation view is shown in Figure 3B-7, along with the shell element labels.

This wall uses 5000 psi concrete below grade and 7000 psi concrete above grade.

Reinforcement drawings and section details are presented in Figure 3B-8 and Figure 3B-9.

A summary table of the element-based design check results for the wall at grid line 1 is presented in Table 3B-2. This summary table shows the maximum D/C ratios within each design check zone. All design check zones have no D/C exceedances. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-2a and Table 3B-2b. Based on the above results and evaluations, the wall is acceptable.

3B.2.2.2 Wall at Grid Line 3

The wall at grid line 3 consists of a 5 foot thick weir wall for the pool and a 4 foot thick upper stiffener located near the roof level. The SAP2000 analysis model elevation view is shown in Figure 3B-10, along with the shell element labels.

Reinforcement drawings and section details are presented in Figure 3B-11 through Figure 3B-13.

A summary table of the element-based design check results for the wall at grid line 3 is presented in Table 3B-3. This summary table shows the maximum D/C ratios within each design check zone and highlights those design check zones that exceed a D/C ratio of 0.8. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-3a and Table 3B-3b. Table 3B-4, Table 3B-5, and Table 3B-6 show the element averaging for the horizontal reinforcement, the horizontal membrane compression stress, and the vertical reinforcement, respectively. Table 3B-7 provides a summary of D/C ratios after averaging the affected elements. The method of averaging of the demand membrane forces, in-plane shear and out-of-plane moments (used for determination of D/C ratios in terms of reinforcing steel), and out-of-plane shears (used for determination of D/C ratios for shear) over a length of nominally 4 times the thickness of the wall is described in Section 3B.1.1.1. As shown in Table 3B-7, with this further distribution of demand, all D/C ratios are acceptable.

3B.2.2.3 Wall at Grid Line 4

The wall at grid line 4 is an interior wall of the RXB with two different thicknesses. The SAP2000 analysis model elevation view is shown in Figure 3B-14, along with the shell element labels.

Reinforcement drawings and section details are presented in Figure 3B-15 through Figure 3B-17.

A summary table of the element-based design check results for the wall at grid line 4 is presented in Table 3B-8. This summary table shows the maximum D/C ratios within each design check zone and highlights those design check zones that exceed a D/C ratio of 0.8. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-8a and Table 3B-8b. Table 3B-9 shows the element averaging for the horizontal reinforcement exceedance indicated in Table 3B-8. Table 3B-10 provides a summary of D/C ratios after averaging. As shown in Table 3B-10, with this further distribution of demand, all D/C ratios are acceptable.

3B.2.2.4 Wall at Grid Line 6

The walls at grid line 6 consist of several wall thicknesses. The upper stiffener wall located near the roof is 4 feet thick. The pool wall section has two section thicknesses, 7.5 feet and 5 feet. The SAP2000 analysis model elevation view is shown in Figure 3B-18, along with the shell element labels.

Reinforcement drawings and section details are presented in Figure 3B-19 through Figure 3B-21.

A summary table of the element-based design check results for the wall at grid line 6 is presented in Table 3B-11. This summary table shows the maximum D/C ratios within each design check zone. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-11a and Table 3B-11b. The highlighted entries indicate those D/C ratios that exceed 1.0. Table 3B-12 shows the element averaging for the horizontal reinforcement exceedance in Table 3B-11. Table 3B-13 provides a summary of D/C ratios after averaging. As shown in Table 3B-13, with this further distribution of demand, all D/C ratios are acceptable.

3B.2.2.5 Wall at Grid Line E

The wall at grid line E is an exterior structural wall on the south side of the RXB that is 5 feet thick. The SAP2000 analysis model elevation view is shown in Figure 3B-22, along with the shell element labels.

Reinforcement drawings, details, and sketches are presented in Figure 3B-23 and Figure 3B-24.

A summary table of the element-based design check results for the wall at grid line E is presented in Table 3B-14. This summary table shows the maximum D/C ratios within each design check zone. All design check zones have no D/C exceedances. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-14a and Table 3B-14b. Based on the above results and evaluations, the wall is acceptable.

3B.2.3 Design Approach - Slabs

The slabs are designed using the same methodology as was used for the walls in Section 3B.1.1. The design check determines the D/C ratios for the north-south and

east-west slab reinforcement including the various shear failure modes based on the combined demand forces and moments.

An iterative design check approach is used to determine the appropriate uniform reinforcement pattern for a given slab section based on the maximum combined design forces and moments. A representative slab shell element within the design check zone selected to demonstrate the element-based design check that is repeated for all shell elements within this slab. The demand forces and moments for the shell element in the design check zone combines the non-seismic (SAP2000) and seismic (SASSI2010) design value for performing the element-based design check.

The summary table of D/C ratios at each slab elevation shows the maximum D/C ratios within each design check zone. A separate check of averaging for slabs that contain elements exceeding the in-plane shear limit, or that contain elements exceeding shear friction limits is performed to ensure the D/C ratios are acceptable.

3B.2.3.1 Basemat Foundation

The reinforced concrete section for the basemat is comprised of a 10 foot thick concrete slab with 2 layers of #11 bars at 6" centers each way, top and bottom, for main reinforcing steel, and headed #6 bars at 12" centers each way. The perimeter of the main slab contains 3 layers of #11 bars at 6" centers each way, top and bottom, for main reinforcing steel, and headed #9 bars at 12" centers each way.

Figure 3B-86 and Figure 3B-87 show the two zones, Perimeter Area and Interior Area, used for design of the basemat. Figure 3B-86 and Figure 3B-87 also show the basemat solid element numbering in the RXB finite element model. Reinforcement drawings are shown in Figure 3B-88 and Figure 3B-89.

For evaluation, the total area of reinforcing steel required for axial tension, in-plane shear, and out-of-plane moment is considered. In addition, reduction of out-of-plane shear capacity of concrete due to axial tension is considered.

For the design check, bounding demand forces and moments for the basemat are considered at the following locations:

- 1) Basemat of the perimeter of the RXB structure
- 2) Basemat of the interior of the RXB structure

Table 3B-62 shows the demand forces and moments used for the design check of the perimeter and interior of the basemat of the RXB structure. Table 3B-63 shows the magnitudes of bounding static and dynamic forces and moments over the RXB basemat foundation. The static, dynamic and combined demands do not occur at the same location, and averaging of demands over elements was employed in the combined responses as explained in Section 3B.1.1.1.

The design checks for the various failure modes of the RXB foundation perimeter and interior are shown in Table 3B-64 and Table 3B-65 respectively.

3B.2.3.2 Slab at EL. 100'-0"

The slab at EL. 100'-0" is at grade level and is 3 feet thick. The outer and inner perimeter of the slab is reinforced with shear reinforcement. The SAP2000 analysis model elevation view is shown in Figure 3B-25, along with the shell element labels.

Reinforcement drawings and section details is presented in Figure 3B-26 and Figure 3B-27.

A summary table of the element-based design check results for the slab at EL. 100'-0" is presented in Table 3B-15. This summary table shows the maximum D/C ratios within each design check zone and highlights the XZ plane shear exceedance. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-15a and Table 3B-15b. Table 3B-16 shows the element averaging for that exceedance. Table 3B-17 provides a summary of D/C ratios after averaging. Based upon the results shown in Table 3B-17, the slab at EL. 100'-0" is acceptable.

3B.2.3.3 Slab at EL. 181'-0"

The roof slab is a 4 foot thick slab that begins at EL. 163'-0", slopes inward for 29.5 feet, and is flat at EL. 181'-0". The SAP2000 analysis model elevation view is shown in Figure 3B-28, along with the shell element labels.

Reinforcement drawings and section details are presented in Figure 3B-29 and Figure 3B-30.

A summary table of the element-based design check results for the roof slab is presented in Table 3B-18. This summary table shows the maximum D/C ratios within each design check zone. All design check zones have no D/C exceedances. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-18a and Table 3B-18b. Based on the above results and evaluations, the roof slab is acceptable.

3B.2.3.4 Pilasters

Pilasters are used around the perimeter of the RXB exterior walls and at two locations inside the pool walls from elevation 50'-0" to elevation 100'-0" at grid line 3. The RXB pilasters strengthen the RXB exterior walls by resisting the following types of loading:

- 1) axial tension and compression
- 2) lateral shear loading in both the north-south and east-west directions
- 3) flexural bending about the north-south and east-west axes of the pilasters

In the finite element model, the pilasters are modeled with frame elements with transverse flexural stiffness properties that represent the combined action of the walls (modeled with shell elements) and the pilasters. The forces in the artificially

stiffened frame elements could be distributed to the pilaster and wall elements but for a conservative evaluation of the pilaster, the moments and the out of plane shear forces corresponding to the strong axis are compared to the capacity of the pilaster alone. Bending about the weak axis does not need to be evaluated because the pilaster is an integral part of the wall and bending in that direction is not local behavior. It is part of the in-plane behavior of the wall and the shell elements in this area have adequate reinforcing. The pilaster stem shear in the weak axis direction, parallel to the wall, does not need to be evaluated because the in-plane capacity of the wall is capable of accommodating the minor in-plane shear loading increase from the pilaster stems.

If the 5 feet by 10 feet pilaster can resist the resulting loads without consideration of the adjacent concrete walls, the pilaster is considered qualified.

The qualification of the pilasters compares the capacities of selected members with the demands and determines the demand to capacity ratios. In the structural model, the frame elements used to represent the pilasters are located at the center of the walls.

The capacity of the pilaster is based on the reinforcing steel in the 5 feet by 10 feet zone. While the pilaster does interact with the wall, the additional capacity gained by considering the strength of the adjoining walls has been conservatively neglected.

A detailed explanation of the methodology for the design evaluation of the walls and slabs, also applicable to the pilasters in the RXB is presented in Section 3B.1.2. The SAP2000 and SASSI2010 combined design forces and moments are used for the design check. The design check determines the D/C ratios for the various failure modes based on the combined demand forces and moments.

The pilasters in the RXB are designed for strong axis bending, strong axis shear, axial compression, and axial tension only. This is due to the very long span in the weak axis direction (along the plane of the walls) that prevents the pilasters from failing. Similarly, the pilasters cannot realistically fail in torsion due to the fact that they are embedded into the 5 foot thick RXB walls. Therefore, torsion is also not considered.

3B.2.4 Pilasters at Grid Line A

The pilasters on the wall at grid line A consist of five types of pilaster. The SAP2000 analysis model elevation view is shown in Figure 3B-31, along with the pilaster frame element labels.

Reinforcement details are presented in Figure 3B-32 through Figure 3B-36 for the five pilaster types.

A summary table of the design check results for the pilasters on the wall at grid line A is presented in Table 3B-19. This summary table shows the maximum D/C ratios within each design check zone. All design check zones have no D/C exceedances and the

results acceptable. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-19a and Table 3B-19b.

3B.2.5 Beams

A detailed explanation of the methodology for the design evaluation of the concrete walls and slabs, also applicable to the beams in the RXB is presented in Section 3B.1.2. The SAP2000 and SASSI2010 combined design forces and moments are used in the design check. The design check determines the D/C ratios for the various failure modes based on the combined demand forces and moments.

An iterative design check approach is used to determine the appropriate uniform reinforcement pattern on each beam type based on the maximum combined design forces and moments. A representative beam frame element within the design check zone is selected to demonstrate the frame element design check that is repeated for all beam frame elements within this group.

The beams in the RXB are designed for strong axis bending and strong axis shear only. This is due to the very long span in the weak axis direction (along the plane of the slabs) that prevents the beams from failing. Similarly, the beams cannot realistically fail in torsion due to the fact that they are embedded into the 3 foot thick RXB slabs. Therefore, torsion is also not considered.

The summary table of D/C ratios at each slab elevation shows the maximum D/C ratios within each design check zone.

3B.2.5.1 Beams at EL. 75'-0"

The slab at EL. 75'-0" contains six beam sections running east-west and 22 beam sections running north-south. The SAP2000 analysis model plan view is shown in Figure 3B-37, along with the frame element labels.

The reinforcement details are shown in Figure 3B-38 and Figure 3B-39.

A summary table of the design check results for the beams at EL. 75'-0" is presented in Table 3B-20. This summary table shows the maximum D/C ratios within each design check zone. The D/C ratios are less than 1.0 and therefore the beams are acceptable. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-20a and Table 3B-20b.

3B.2.6 Buttresses

A detailed explanation of the methodology for the design evaluation of the walls and slabs, also applicable to the buttresses in the RXB is presented in Section 3B.1.2. The SAP2000 analysis model is used to determine the maximum non-seismic demand results for each buttress frame element. Similarly, the SASSI2010 analysis model is used to determine the seismic demand results, which are then combined with the SAP2000 results for each buttress frame element. The SAP2000 and SASSI2010 combined design forces and moments are used in the design check. The design check determines the

D/C ratios for the various failure modes based on the combined demand forces and moments.

An iterative design check approach is used to determine the appropriate uniform reinforcement pattern on each buttress type based on the maximum combined design forces and moments. A representative element within the design check zone is selected to demonstrate the frame element design check that is repeated for all elements within this group.

The buttresses in the RXB are designed for strong axis bending and strong axis shear only. This is due to the very long span in the weak axis direction (along the plane of the slabs) that prevents the buttresses from failing. Similarly, the buttresses cannot realistically fail in torsion due to the fact that they are embedded into the 5 foot thick RXB slabs. Therefore, torsion is also not considered.

3B.2.6.1 Buttress at EL. 126'-0"

The wall at grid line 1 has two buttresses. These are at elevations 126'-0" and 145'-6". The buttress at EL. 126'-0" is evaluated. The SAP2000 analysis model plan view is shown in Figure 3B-40, along with the frame element labels.

The reinforcement details are shown in Figure 3B-41.

A summary table of the design check results for the beams at elevation 126'-0" is presented in Table 3B-21. This summary table shows the maximum D/C ratios within each design check zone. The D/C ratios are less than 1.0 and therefore the buttress is acceptable. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-21a and Table 3B-21b.

3B.2.7 NuScale Power Module Bay

The NPM bays are 3-walled compartments located in the reactor pool and are designed to house the NPMs during operation. Each bay is 20'-6" wide in the north-south direction and 19'-7" deep in the east-west direction, and extends from the pool floor at EL. 25'-0" up to EL. 125'-0". The bottom of the bay is the RXB foundation slab. The walls which make up the bay are 5 feet thick reinforced concrete. The top of the bay is capped with the Bioshield during operation. The bay provides restraints to prevent the NPM from moving laterally. Restraint is provided via a NPM skirt restraint located at EL. 25'-0" and lug restraints located on the three bay walls at EL. 71'-7".

3B.2.7.1 West Wing Wall

The west wing wall is one of the walls at grid line 4. The SAP2000 analysis model elevation view is shown in Figure 3B-14, along with the shell element labels. The west wing walls have the refueling pool on one side and an NPM located on the other. (See Figure 3B-52). Because of this location, it experiences the highest forces of the NPM bay wing walls.

Reinforcement drawings and section details are presented in Figure 3B-15 and Figure 3B-16.

A summary table of the element-based design check results for the wall at Grid Line 4 is presented in Table 3B-8. This summary table shows the maximum D/C ratios within each design check zone. All design check zones have no D/C exceedances. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-8a and Table 3B-8b. Based on the above results and evaluations, the west wing wall is acceptable.

3B.2.7.2 Pool Wall

The portion of the pool wall that supports the NPMs is part of the wall at grid line B. This is an interior wall of the RXB that is 5 feet thick. The SAP2000 analysis model elevation view is shown in Figure 3B-45, along with the shell element labels.

Reinforcement drawings and section details are presented in Figure 3B-46 and Figure 3B-47.

A summary table of the element-based design check results for the wall at grid line B is presented in Table 3B-23. This summary table shows the maximum D/C ratios within each design check zone and highlights the YZ plane shear exceedance. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-23a and Table 3B-23b. Table 3B-24 shows the element averaging for that exceedance. Table 3B-25 provides a summary of D/C ratios after averaging.

3B.2.7.3 NuScale Power Module Passive Support Plates Assembly

The base of the NPM is located at the bottom of the RXB pool at EL. 25'-0". There are up to 12 NPMs located in the RXB pool in their respective bays. The pool floor liner in the NPM bay is made of half-inch thick stainless steel, whereas the wall liner is made of quarter-inch stainless steel.

The NPM is vertically supported for the dead load and seismic loads acting downwards at the base, but free to move up vertically for any uplifting forces (such as seismic load acting upwards and buoyant forces due to the water in the reactor pool). The NPM is also laterally restrained against seismic forces at the base.

The details of the NPM base support are shown in Figure 3B-48 through Figure 3B-50. The NPM base support includes the following:

- The skirt of the NPM is supported on a donut-shaped, 5 3/4 in. thick embed plate. The embed plate extends beyond the donut shape at four quadrants to support 4 passive plates. In each quadrant, the embed plate has two 8 in. openings to accommodate concrete placement and consolidation. The central opening and the additional 8 openings are to be sealed by welding a stainless steel cover plate after concrete placement. The embed plate is made of stainless steel and is anchored to the basemat concrete using steel reinforcing bars. Figure 3B-48, Figure 3B-49 and Figure 3B-50 show the details of the NPM embed plate. The NPM is free to move upward vertically, and the vertical downward NPM load is transferred to the concrete basemat in bearing.

- The NPM is laterally restrained by four 4 1/2 in. thick stainless steel passive support plates. Each passive support plate is attached to the embed plate using two groups of six bolt/pin sets at both ends. Each set of bolts/pins is designed for the full seismic load. The passive plates transfer the seismic loads to the embed plate through the two groups of bolts/pins mainly by shear. The guide plate assembly, as shown in Figure 3B-48, is welded to the passive plate. The function of the guide plate assembly is to guide NPM installation to the design position. Figure 3B-48 shows the details of passive plates and the guide plate assembly. If the NPM impacts the passive support plates, the resulting upward vertical and horizontal loads will be resisted by the anchors in tension and shear and concrete in edge bearing. Figure 3B-48 and Figure 3B-49 show the details of the passive support plate.

NuScale Power Module Model:

A SASSI building model with a detailed NPM beam model, described in Section 3.7.2, is used to perform dynamic analyses on the RXB and extract results at the NPM to RXB interface locations. The RXB analysis produces local acceleration time histories that are used as input to the NPM seismic analysis discussed in Appendix 3A.

A separate ANSYS model is used to perform a non-linear dynamic analysis of the NPM. This model only includes the pool water and one NPM (1 or 6). The analysis results are based on the envelope of the twelve runs shown in Table 3B-53. The static reaction force, including the dead weight and the static buoyancy, is 1,250 kips in the vertical direction. The maximum uplift displacement, due to seismic, of the module from the floor is less than 0.125 inch. The enveloping reaction forces between the ANSYS and SASSI models are provided in Table 3B-28 and used for the design basis in the following subsections.

Envelope Loads:

- Vertical downward load, $P = 3,144$ kips. This load includes dead load, fluid pressure load, and seismic load. Dead load is the static buoyancy load described above and is equal to 1,250 kips. The fluid pressure load is determined by the product of the NPM skirt ring area ($4,310 \text{ in}^2$), the fluid density (62.4 pcf), and the normal operating reactor pool depth (69') and is equal to 129 kips. The enveloping downward seismic load is 1,765.2 kips.
- The vertical displacement is less than 0.125 inch. The passive support plate is 4.5 inches thick, therefore, there will always be lateral support from the passive support plate.
- Lateral load:
 - East-West seismic load = 875.1 kips
 - North-South seismic load = 995.3 kips
 - Square Root Sum of Squares horizontal seismic load =
$$\sqrt{(875.1^2 + 995.3^2)} = 1,325.3 \text{ kips}$$

Considering a 5 percent load increase to account for accidental torsion, the SRSS horizontal seismic load is 1,391.4 kips.

It is possible for the support plates and anchors to experience an upward vertical force if the NPM were to strike a support plate during a seismic event. Because this force is of extremely short duration and the contact surface small, only a limited amount of force is transferred to the support plate. A coefficient of friction value between wet steel and steel of 0.2 is multiplied by the square root sum of squares of east-west and north-south seismic loads to determine this force.

$$V_{\text{uplift}} = 0.2 \times 1,391.4 \text{ kips} = 278.3 \text{ kips}$$

Materials and Material Strength:

- **Stainless Steel:** The stainless steel used for the liner plate conforms to ASTM A-167 or ASTM A-240 Type 304L and has a 0.2 percent offset yield strength of 25 ksi, and ultimate tensile strength 70 ksi.
- **Duplex Stainless:** The steel used for the 5 3/4-in.-thick bearing plate that supports the NPMs vertically is ASTM A240 Type S32205 with a yield strength of 65 ksi and ultimate tensile strength of 91.7 ksi at a design temperature of 300 degrees Fahrenheit. Passive plates and guide plates are made of the same material type.
- **Concrete for Basemat:** The concrete strength, f'_c is 5000 psi

A total of 88 #18 ASTM A706 Grade 60 steel reinforcing bars are used to anchor the embed plate in the four quadrants. The number of anchors in each quadrant (22) is designed for NPM loads.

A total of 16 threaded bolts and 32 pins made of material ASTM A564, Type 17400 with heat treatment condition of H1150, with yield strength of 105 ksi and tensile strength at 300 degrees Fahrenheit of 135 ksi, are used to attach the four passive plates to the embed plate.

Load Path:

- The vertical load is resisted by the 5 3/4 in. thick donut-shape embed plate supporting the 4 1/2 in. thick NPM skirt ring.
- The lateral load is resisted by bolts/pins that connect the passive plate to the embedded bearing plate. The bolts/pins transfer the lateral load to the embed plate, which, in turn, transfers the load, via bearing, to the concrete basemat.

Evaluation:

Vertical Load Bearing Capacity

- Area of concrete in bearing, A_{brg} , is 4310 in², therefore the bearing pressure (P_V / A_{brg}) is 0.73 ksi
- Allowable bearing pressure = $(\Phi)(0.85f'_c) = 2.76 \text{ ksi}$ [$\Phi = 0.65$]

- Vertical bearing D/C Ratio: = 0.26
- The D/C ratio of the anchor bar shear strength is equal to 0.55.

Lateral Load Resistance

- SRSS Lateral Load is 1,391.4 kips
- The D/C ratio of the bolts/pins in shear and tension is 0.60.
- The D/C ratio for concrete edge bearing due to lateral load transferred from the bearing plate is 0.58.
- The true capacity of the NPM support plate assembly, where D/C would reach a value of 1.0, occurs for a load of $1,391.4 \text{ kips} / 0.60 = 2,319 \text{ kips}$.

3B.2.7.4 Nuscale Power Module Lug Restraint

The NPM lug restraint design consists of a stainless steel bumper comprised of 2" thick plates with 2" thick stiffener plates. The bumpers are welded to 2" thick stainless steel liner plates. On the inside of the liner plate there are 3" thick, 5" wide (48" depth) steel shear lugs to transfer the lateral shear loads into the wall. Finally, the two bumpers on either side of the lug on the pool walls are bolted together with through-bolts to withstand tensile loads due to moments from the eccentric lateral shear loads. The design layout for the support system for the NPM lug restraints is shown in Figure 3B-51.

The bumpers are Stainless Steel Type 630 - H1150, with a yield strength of 100.8 ksi, and an ultimate strength of 135 ksi. The shear lugs are carbon steel ASTM A572 GR 50, with a yield strength of 50 ksi, and an ultimate strength of 65 ksi. The through-bolts are ASTM A193 GR B7, with a yield strength of 105 ksi, and an ultimate strength of 125 ksi.

A separate SAP2000 model is created for the local analysis of the RXB lug support system. This lug restraint model is a comprehensive, finite-element model of half of a single NPM wing wall. Therefore, 2.5' of the wall thickness, with two lugs on one face of the wall, are included in the model. The load is distributed as point loads to one of the lugs. The wing wall is modeled with solid elements. The liner plate, the stainless steel lug, and the bumper built-up section are modeled with shell elements. The through bolts are not modeled explicitly; however, the axial tension of the shear lugs is used to determine the tension force in the through bolts. Because the shear lugs transfer the shear loads from the bumper to concrete, the through bolts are considered to be under tension only. All welds along the load path are CJP welds. This includes the bumper built-up section, the bumper to the liner plate, and liner plate to the shear lugs.

In this local model, an assumed horizontal load of 3500 kips is applied to determine the stresses in components of the support. Modes of failure for lug components are checked, including tensile capacity of through bolts, punching shear and concrete bearing, and bending stresses on the liner plate. The most controlling mode of failure is bearing against concrete with a $D/C=0.777$. Refer to Table 3B-57 for details. Because this D/C occurs for an applied load of 3500 kips, the true capacity

of the lug assembly, where D/C would reach a value of 1.0, occurs for a load of $3500 \text{ kips}/0.777=4500 \text{ kips}$.

To check the adequacy of the lugs, the maximum seismic reaction on a lug from the NPM Seismic Analysis model is compared against the lug capacity calculated from the local lug model.

The RXB analysis produces local acceleration time histories that are used as input to the NPM seismic analysis, as described in Appendix 3A. The maximum lug reaction from the NPM Seismic Analysis model is provided in Table 8-6 of TR-0916-51502, "NuScale Power Module Seismic Analysis" (Reference 3B-6). The envelope of the maximum lug reaction forces from the ANSYS and SASSI dynamic analyses are provided in Table 3B-28. The design demand is less than the lug capacity of 4500 kips. This shows that the lugs are structurally qualified.

The NPM bay walls and location of the NPM lugs is shown in Figure 3B-52. The NPM lug restraint model is shown in Figure 3B-53 and Figure 3B-54. The liner plate and shear lugs are modeled as shell elements and are shown in Figure 3B-55 and Figure 3B-56. In Figure 3B-57, the outside of the bumper is removed in order to display the stiffener plates inside.

Section cuts were used to extract forces and moments for design of the NPM lug support. Table 3B-26 displays the forces and moments for the two 3500 kip load cases: W-Lug-PY+ (shown in Figure 3B-58) and W-Lug-PY- (shown in Figure 3B-59). Figure 3B-60 shows the liner plate section cuts at the intersection of the inside face of the bumper to the liner plate. These cuts are used to find the design moment (M1) due to design loading. Figure 3B-61 shows the shear lug section cuts (fins) that occur between the liner plate and shear lugs. The shear (F2) from these cuts is summed to verify that the total 3500 kip load is being transferred to the wall as shown in Table 3B-26. Finally, maximum tension load of 804 kips occurs on the shear lug directly below the 2" plate and the maximum shear of 790 kips occurs in the shear lug at X=88.20 inches. The sign of the F1 force for the fin at X=16.25" is negative but the deflected shape of the lug support system clearly shows this is a tension force (Figure 3B-62). These values are utilized in the shear lug evaluation.

3B.2.7.4.1

Shear Lug Evaluation

Shear lugs (steel bar fins) are used for the transfer of the NPM lug restraint loads to the concrete walls via shear. The shear lugs are rectangular shaped fins having dimensions 3" wide x 5" bar and 4 feet long embedded in the concrete.

The shear lugs are made of carbon steel (ASTM A572 Gr. 50) having a yield strength of 50 ksi and ultimate strength of 65 ksi. The 28 day strength of concrete in the walls is 5000 psi.

In addition to shear, there will be tensile load on the fins. This is because the NPM lug load is applied with an eccentricity, causing moment that results in a tensile load on some of the fins. The tensile loads are designed to be resisted by 2.5" diameter through bolts made of ASTM A193 Gr B7 material having a yield strength of 105 ksi and an ultimate strength of 125 ksi.

Figure 3B-51 shows a layout of the shear lugs and the through bolts. There are 32 through-bolts that correspond to each lug of the NPM as shown in Figure 3B-51.

The tensile capacity of the through bolts is the smaller of the bolt steel strength and the concrete strength.

The bending stress in the 2" thick liner plate can be bounded by considering the moment at the base of highest loaded shear lug as an upper bound moment in the liner plate.

From Table 3B-26, the maximum moment on the plate occurs at the shear lug at $Y = 88.2"$ for lug load in the +Y direction. Please see Table 3B-57, which provides D/C ratios for the various lug component stress checks. The D/C ratios listed in Table 3B-57 are for the individual modes of failure for components of the lug assembly. In this table, the demand is the load that is resisted by each component, due to an applied total load of 3500 kips in the SAP2000 model.

The highest D/C ratio is for concrete bearing against the shear lugs at 0.777. Since this maximum ratio is due to the 3500 kips load, the maximum capacity of the lug assembly is $3500 \text{ kips} / 0.777 = 4500 \text{ kips}$.

3B.2.7.4.2

Overall Lug Restraint Reaction

Table 3B-28 presents the envelope lug reactions, for all twelve bays, using the twelve analysis cases with Soil Type 7 for Capitola input motion with 4 percent structural damping of the SASSI RXB model and the equivalent analysis performed on the NPM detailed seismic model (Reference TR-0916-51502). Since the maximum lug reactions are below the lug support design capacity of 4,500 kips, the design is acceptable.

3B.2.8

Evaluation of RXB for Load Combinations Involving Thermal and Accident Pressure Loads

T_0 , T_a , and P_a strains in the reinforcing steel and liner steel of the RXB are given in Table 3B-58. Concrete strains under combined static load cases are given in Table 3B-59. Reinforcing steel and liner steel strains for Load Combinations 10 and 13 are given in Table 3B-60 and Table 3B-61 respectively along with demand from combined static demand and individual maximum T_0 and $T_a + P_a$ strains.

Strain averaging is employed at some localized regions as described in Section 3B.1.3. It should be noted that, for regions where averaging is employed, linear addition of T_0 and $T_a + P_a$ strains with static load cases do not necessarily give load combination 10 and 13 resultants as these strains do not necessarily occur at the same location, therefore, the maximum combined strain is not the sum of both maximum strains.

As an example, in the foundation, the total strain in the steel is less than $1.2\varepsilon_y$ (2.483×10^{-3}) at all locations except at the perimeter region for load combination 13

where it is exceeded by 5 percent. However, the static strains calculated are conservative because they are based on the maximum axial, shear, and moment components over all of the elements. These do not occur at the same location or time. If the strains were based on the forces and moments occurring simultaneously at the same location, and if averaging were used, the strains would be lower. Also, the thermal strain of 0.000367 for $T_a + P_a$ is the maximum over the entire basemat and occurs in the pool area. The thermal strains in the foundation perimeter region are lower.

The pool walls and NPM support walls are lined with a ¼" thick stainless steel plate. Per Table CC-3720-1 of ASME Boiler and Pressure Vessel Code (Reference 3B-7), the allowable strain limit for the liner plate is 0.004 in/in even for service load conditions. The total strain in the steel is less than 0.004 in/in at all locations for load combinations 10 and 13. Therefore, the steel pool liner is considered acceptable.

3B.3 Control Building

3B.3.1 Design Report

Structural Description and Geometry

The CRB is a Seismic Category I concrete structure at elevation 120'-0" and below, except as noted in Section 1.2.2.2. Above EL 120'-0" the CRB is a Seismic Category II steel structure. For a detailed description of the CRB, see Section 3.8.4.1.2. The CRB geometry and floor layout are shown in Figure 1.2-21 through Figure 1.2-27.

Structural Material Requirements

The CRB design is based on the following material properties:

- Concrete
 - Compressive Strength - 5 ksi
 - Modulus of Elasticity - 4,031 ksi
 - Shear Modulus - 1,722 ksi
 - Poisson's Ratio - 0.17
- Reinforcement
 - Yield Stress - 60 ksi (ASTM A615 Grade 60 or ASTM A706 Grade 60)
 - Tensile Strength - 90 ksi (A615 Grade 60), 80 ksi (A706 Grade 60)
 - Elongation - See ASTMs A615 and A706
- Structural Steel
 - Grade - ASTM A992 (W shapes), ASTM A500 Grade B (Tube Steel), ASTM A36 (plates)
 - Ultimate Tensile Strength - 65 ksi A992, 58 ksi A500 Grade B and A36
 - Yield Stress - 50 ksi A992, 46 ksi A500 Grade B, 36 ksi A36

- Foundation Media

For a description of the soils considered in the design of the CRB, see Section 3.8.5.4.2 and Section 3.7.1.3.1.

Structural Loads

The structural loads for the CRB are discussed in detail in Sections 3.7.1 and 3.8.4 for seismic and non-seismic loads respectively.

Structural Analysis and Design

- Design Computations of Critical Elements

The design methodology of CRB related Critical Elements is discussed in Section 3B.1. Specific CRB Critical Elements analyzed are discussed in Section 3B.3.

- Stability Calculations

Stability of the CRB is addressed in Section 3.8.5.4.1.3, Section 3.8.5.4.1.4, Section 3.8.5.5, and Section 3.8.5.6.2.

Summary of Results

See Section 3B.3.2 through Section 3B.3.5

Conclusions

The D/C ratios presented are all less than 1.0. Therefore, the Critical Elements satisfy the design criteria for loading investigated.

3B.3.2 Walls

3B.3.2.1 Wall at Grid Line 3

The wall at grid line 3 is an interior structural wall between EL. 50'-0" and EL. 120'-0" of the CRB. This wall is 2 feet thick. The SAP2000 analysis model elevation view is shown in Figure 3B-65, along with the shell element labels.

Reinforcement drawings and details are presented in Figure 3B-66 and Figure 3B-67.

A summary table of the element-based design check results for the wall at grid line 3 is presented in Table 3B-29. This summary table shows the maximum D/C ratios within each design check zone. As shown in Table 3B-29, all design check zones have no D/C exceedances. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-29a and Table 3B-29b. Based on the above results and evaluations, the wall is acceptable.

3B.3.2.2 Wall at Grid Line 4

The wall at grid line 4 is an exterior structural wall on the east side of the CRB that is 3 feet thick. The SAP2000 analysis model elevation view is shown in Figure 3B-68, along with the shell element labels.

Reinforcement drawings and details are presented in Figure 3B-69 and Figure 3B-70.

A summary table of the element-based design check results for the wall at grid line 4 is presented in Table 3B-30. This summary table shows the maximum D/C ratios within each design check zone. As shown in Table 3B-30, certain design check zones have D/C ratios in excess of 1.0. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-30a and Table 3B-30b.

The wall at grid line 4 was experiencing out of plane shear exceedances in the YZ plane as shown in Table 3B-30. In order to satisfy the demand, the section experiencing high out of plane shear was reinforced with an additional #6 stirrup leg. This is shown in Figure 3B-70. Table 3B-31 shows the design check of the worst shell element in the section, number 786, with the additional shear reinforcement. The final design check is provided in Table 3B-31. Based on Table 3B-32, where the capacity includes the added reinforcement, the wall at grid line 4 is acceptable.

3B.3.2.3 Wall at Grid Line A

The wall at grid line A is an exterior structural wall on the north side of the CRB that is 3 feet thick. The SAP2000 analysis model elevation view is shown in Figure 3B-71, along with the shell element labels.

Reinforcement drawings and details are presented in Figure 3B-72 and Figure 3B-73.

A summary table of the element-based design check results for the wall at grid line A are presented in Table 3B-33. This summary table shows the maximum D/C ratios within each design check zone. Based on Table 3B-33, all design check zones have no D/C exceedances. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-33a and Table 3B-33b. Based on the above results and evaluations, the wall is acceptable.

In-plane shear for the adequacy of concrete wall thickness was checked for all elements in the CRB. Several individual elements in the walls encountered in-plane shear exceedances. Where individual elements in the wall at grid line A exceed in-plane shear limits, the elements are averaged as shown in Table 3B-34. The cross-section was checked based on calculating the average in-plane shear over the entire wall section, and is acceptable.

3B.3.3 Slabs

3B.3.3.1 Basemat Foundation

The reinforced concrete section for the basemat is comprised of a 5 foot thick concrete slab with 3 layers of #11 bars at 12" centers each way top and bottom for main reinforcing steel, and 2 legged stirrups of #6 bars at 12" centers each way. The perimeter of the main slab contains 4 layers of #11 bars at 12" centers each way top and bottom for main reinforcing steel, and 2 legged stirrups of #6 bars at 12" centers each way. The capacity of the sections used is presented Table 3B-35 and Table 3B-36.

Figure 3B-74 shows the three zones: Tunnel Area, Perimeter Area and Interior Area, used for design of the basemat. Figure 3B-74 also shows the CRB basemat solid element numbering in the CRB finite element model. Reinforcement drawings are shown in Figure 3B-75 and Figure 3B-76.

For evaluation, total area of reinforcing steel required for axial tension, in-plane shear, and out-of-plane moment is considered. In addition, reduction of out-of-plane shear capacity of concrete due to axial tension is considered.

For the design check, bounding demand forces and moments for the basemat are considered at the following locations:

- 1) Basemat for the perimeter of the main CRB structure
- 2) Basemat for the interior of the main CRB structure
- 3) Basemat for CRB tunnel

Table 3B-37b provides the magnitudes of bounding demand forces and moments used for the design check of the perimeter of the basemat of the CRB structure. Table 3B-38b provides the magnitudes of bounding demand forces and moments used for the design check of the interior of the basemat of the main CRB structure. Table 3B-39b provides the magnitudes of bounding demand for the basemat of the CRB tunnel.

The demand forces and moments for the perimeter of the main CRB foundation evaluation are listed in Table 3B-37a and Table 3B-37b. The design check for the various failure modes of the main CRB foundation perimeter are shown in Table 3B-40.

The demand forces and moments for the main interior part of the CRB foundation evaluation are listed in Table 3B-38a and Table 3B-38b. The design check for the various failure modes of the main CRB foundation interior are shown in Table 3B-41.

Likewise, the demand forces and moments for the CRB foundation tunnel are listed in Table 3B-39a and Table 3B-39b. The design check for the various failure modes of the CRB foundation tunnel are shown in Table 3B-42.

3B.3.3.2 Slab EL. 100'-0"

The slab at EL. 100'-0" is at grade and houses the main technical support and data area for the CRB. This elevation consists of a 3' slab and 2' slab along with a 3' tunnel slab. The SAP2000 analysis model elevation view is shown in Figure 3B-77, along with the shell element labels.

Reinforcement drawings and details are presented in Figure 3B-78 and Figure 3B-79.

A summary table of the element-based design check results for the slab at EL. 100'-0" is presented in Table 3B-43. This summary table shows the maximum D/C ratios within each design check zone. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-43a and Table 3B-43b. Table 3B-47 provides a summary of D/C ratios after averaging. The tables showing the averaging performed are Table 3B-44 through Table 3B-46.

Shear friction was checked for all elements in the CRB. Some individual elements in the slabs encountered shear friction exceedances. For elements that exceed shear friction limits in the slab at EL. 100'-0", their averaging is shown in Table 3B-48.

3B.3.4 Pilasters**3B.3.4.1 Pilasters Grid Line 1**

The pilasters on the wall at grid line 1 consist of two types of pilasters. The SAP2000 analysis model elevation view is shown in Figure 3B-80, along with the pilaster frame element labels.

Reinforcement details are presented in Figure 3B-81 and Figure 3B-82 for pilaster Type 1 and Type 2, respectively.

A summary table of the design check results for the pilasters on the wall at Grid Line 1 is presented in Table 3B-49. This summary table shows the maximum D/C ratios within each design check zone. As noted in Table 3B-49, all design check zones have D/C ratios that are less than 1.0; and therefore, the pilasters are acceptable. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-49a and Table 3B-49b.

3B.3.5 T-Beams**3B.3.5.1 T-Beams at EL. 120'-0"**

The slab at elevation 120'-0" contains six T-beam sections running east-west and two T-beam sections running north-south. The SAP2000 analysis model plan view is shown in Figure 3B-83, along with the frame element labels.

The reinforcement details are shown in Figure 3B-84 and Figure 3B-85 for Type 1 and Type 2, respectively.

A summary table of the design check results for the beams at elevation 120'-0" is presented in Table 3B-50. This summary table shows the maximum D/C ratios within each design check zone. As shown in Table 3B-50, all design check zones have D/C ratios that are less than 1.0; therefore the T-Beams at elevation 120'-0" are all acceptable. The bounding static, dynamic (seismic), and final design forces and moments are shown in Table 3B-50a and Table 3B-50b.

3B.4 References

- 3B-1 SAP2000 Advanced (Version 17.1.1) [Computer Program]. (2015). Walnut Creek, CA: Computers and Structures, Inc.
- 3B-2 SASSI2010 (Version 1.0) [Computer Program]. (2012). Berkeley, CA.
- 3B-3 American Concrete Institute, "Code Requirements for Nuclear Safety-Related Concrete Structures and Commentary," ACI 349-06, Farmington Hills, MI.
- 3B-4 Not Used.
- 3B-5 Not Used.
- 3B-6 NuScale Power, LLC, "NuScale Power Module Seismic Analysis," TR-0916-51502-P, Revision 2.
- 3B-7 American Society of Mechanical Engineers, Boiler and Pressure Vessel Code, 2013 Edition, No Addenda, Section III, "Rules for Construction of Nuclear Facility Components," New York, NY.
- 3B-8 American Concrete Institute, "Reinforced Concrete Design for Thermal Effects on Nuclear Power Plant Structures," ACI 349.1R-07, Farmington Hills, MI.
- 3B-9 American Concrete Institute, "Building Code Requirements for Structural Concrete and Commentary," ACI 318-08, Farmington Hills, MI.

Table 3B-1: Identification of SAP2000 and SASSI2010 Loads

Designation	SAP2000 Output	SASSI2010 Output
Shell Element Loads		
Membrane Tension/Compression in Local X direction	F11	S_{xx}
Membrane Tension/Compression in Local Y direction	F22	S_{yy}
Maximum In-Plane Shear on all faces	F12	S_{xy}
Out-of-Plane Moment about Local Y Axis	M11	M_{xx}
Out-of-Plane Moment about Local X Axis	M22	M_{yy}
Maximum Twisting Moment on all faces	M12	M_{xy}
Out-of-Plane Shear on Local X Face	V13	V_{xz}
Out-of-Plane Shear on Local Y Face	V23	V_{yz}
Frame Element Loads		
Axial Tension or Compression	P	P1
Strong Axis Shear	V2	P2
Weak Axis Shear	V3	P3
Axial Torque	T	M1
Weak Axis Bending	M2	M2
Strong Axis Bending	M3	M3

Table 3B-2: Summary of D/C Ratios for Reactor Building Wall at Grid Line 1

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;1;E-D;24-50	D/C Ratio	0.35	0.11	0.62	0.49	0.49	0.39	20
	Element	2580	2581	2578	2577	3902	2578	
RXB;1;D-C;24-50	D/C Ratio	0.26	0.10	0.30	0.32	0.33	0.47	24
	Element	3907	3221	2583	2583	3221	2583	
RXB;1;C-B;24-50	D/C Ratio	0.25	0.08	0.28	0.32	0.36	0.51	24
	Element	3918	2593	2592	2592	3232	2591	
RXB;1;B-A;24-50	D/C Ratio	0.34	0.11	0.53	0.44	0.54	0.37	20
	Element	2595	3923	2597	2598	3923	2595	
RXB;1;E-D;50-75	D/C Ratio	0.32	0.09	0.41	0.36	0.41	0.07	20
	Element	7729	5575	7725	5575	5575	7727	
RXB;1;D-C;50-75	D/C Ratio	0.30	0.07	0.32	0.23	0.28	0.34	24
	Element	7730	5581	7735	5585	6139	7734	
RXB;1;C-B;50-75	D/C Ratio	0.35	0.08	0.39	0.23	0.28	0.31	24
	Element	7737	5590	7736	5591	6150	5588	
RXB;1;B-A;50-75	D/C Ratio	0.29	0.09	0.46	0.38	0.44	0.18	20
	Element	7746	5596	7746	6155	5596	5593	
RXB;1;E-D;75-100	D/C Ratio	0.38	0.15	0.62	0.40	0.33	0.09	14
	Element	8843	8843	10386	10386	8839	11155	
RXB;1;D-C;75-100	D/C Ratio	0.45	0.14	0.46	0.27	0.19	0.37	24
	Element	10391	10391	10392	10392	10391	10391	
RXB;1;D-C;75-100	D/C Ratio	0.45	0.14	0.46	0.27	0.19	0.37	24
	Element	10391	10391	10392	10392	10391	10392	
RXB;1;C-B;75-100	D/C Ratio	0.83	0.29	0.71	0.25	0.13	0.31	22
	Element	11167	11167	11167	9442	11166	10393	
RXB;1;B-A;75-100	D/C Ratio	0.36	0.12	0.45	0.36	0.34	0.15	20
	Element	11172	11172	11176	8860	8860	11173	
RXB;1;E-D;100-126	D/C Ratio	0.33	0.04	0.41	0.19	0.17	0.08	20
	Element	12319	12318	12316	12315	12315	12315	
RXB;1;D-C;100-126	D/C Ratio	0.47	0.10	0.42	0.09	0.10	0.08	24
	Element	13542	13542	12322	12320	13537	12325	

Table 3B-2: Summary of D/C Ratios for Reactor Building Wall at Grid Line 1 (Continued)

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;1;C-B;100-126	D/C Ratio	0.64	0.19	0.87	0.41	0.10	0.14	8
	Element	12326	12326	13544	13544	13544	12326	
RXB;1;B-A;100-126	D/C Ratio	0.45	0.10	0.49	0.20	0.21	0.09	20
	Element	13545	13545	12717	12332	12331	12331	
RXB;1;E-D;126-145	D/C Ratio	0.22	0.02	0.27	0.12	0.32	0.27	20
	Element	14613	15238	14612	14609	15580	15580	
RXB;1;D-C;126-145	D/C Ratio	0.37	0.10	0.31	0.09	0.17	0.15	24
	Element	14619	14619	14614	14929	15581	15581	
RXB;1;C-B;126-145	D/C Ratio	0.62	0.15	0.66	0.29	0.21	0.24	24
	Element	14621	14621	14625	14625	15592	15592	
RXB;1;B-A;126-145	D/C Ratio	0.30	0.09	0.31	0.16	0.35	0.33	20
	Element	14626	14626	14626	14936	15593	15593	
RXB;1;E-D;145-163	D/C Ratio	0.20	0.01	0.23	0.07	0.32	0.08	20
	Element	16645	16944	16046	16044	16047	16047	
RXB;1;D-C;145-163	D/C Ratio	0.33	0.01	0.34	0.08	0.12	0.08	24
	Element	16651	16950	16352	16048	16048	16048	
RXB;1;C-B;145-163	D/C Ratio	0.46	0.03	0.51	0.12	0.11	0.09	24
	Element	16058	16059	16058	16059	16059	16059	
RXB;1;B-A;145-163	D/C Ratio	0.26	0.02	0.31	0.11	0.35	0.08	20
	Element	16658	16359	16359	16060	16060	16060	
RXB;1;E-D;163-181	D/C Ratio	0.20	0.03	0.20	0.06	0.16	0.18	14
	Element	17248	14893	17245	17245	17245	17245	
RXB;1;D-C;163-181	D/C Ratio	0.38	0.04	0.43	0.07	0.13	0.16	24
	Element	17949	17949	17949	17949	17944	17948	
RXB;1;C-B;163-181	D/C Ratio	0.40	0.03	0.47	0.08	0.14	0.16	24
	Element	17257	17950	17950	17950	17955	17951	
RXB;1;B-A;163-181	D/C Ratio	0.24	0.08	0.23	0.07	0.14	0.05	14
	Element	17541	15191	17261	17264	17956	17570	

**Table 3B-2a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Wall
at Grid Line 1**

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	2580	-47	-197	-21	13	-22	-21	-6	-29
	2578	-47	-203	-41	3	-21	27	-2	-26
	3923	-69	-230	19	-136	-13	1	-42	2
	2591	-37	-232	-2	12	-78	-21	-2	-63
	11167	-16	-53	-28	-13	-28	9	0	-5
	8860	-25	-142	4	-90	-18	6	-20	2
	10392	-20	-110	-4	7	9	6	-6	5
	12326	-18	-121	-19	-2	8	6	1	1
	13544	-8	-120	-19	1	1	1	1	0
	15593	11	-58	6	-5	-31	6	-8	11
	16058	9	-36	-11	1	-9	3	1	3
	16060	11	-44	9	6	1	6	-7	-1
	17245	12	-9	-5	-3	-22	12	-6	-6
Dynamic	2580	83	239	282	64	115	34	22	15
	2578	60	552	163	69	123	37	12	32
	3923	126	350	176	213	38	26	69	13
	2591	51	199	175	46	95	17	8	40
	11167	485	370	531	100	67	27	13	9
	8860	96	460	174	225	28	27	43	6
	10392	137	328	344	67	111	12	27	55
	12326	440	434	428	17	57	16	8	19
	13544	346	837	394	44	46	28	12	15
	15593	18	285	165	40	26	18	62	42
	16058	57	153	387	59	31	21	22	4
	16060	46	211	165	57	28	35	65	14
	17245	37	139	117	55	31	49	27	30

Table 3B-2a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Wall at Grid Line 1 (Continued)

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Hydrodynamic	2580	6	55	2	0	4	1	0	2
	2578	3	59	0	0	4	1	0	1
	3923	0	60	4	3	1	0	1	0
	2591	8	62	3	1	8	1	0	3
	11167	10	13	8	1	4	3	0	2
	8860	5	30	3	3	1	1	2	0
	10392	6	31	0	2	1	1	1	1
	12326	1	36	2	1	4	1	0	0
	13544	1	36	3	2	1	1	0	0
	15593	4	18	2	1	8	2	2	3
	16058	3	10	3	1	2	1	0	1
	16060	3	14	2	2	1	2	2	0
	17245	1	3	0	0	5	2	1	1

Table 3B-2b: Magnitudes of Bounding Final Design Forces and Moments for RXB Wall at Grid Line 1

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
2580	43	-136	97	-490	306	78	141	55	29	45
2578	17	-111	407	-814	205	73	149	64	14	60
3923	57	-195	180	-639	199	352	52	28	111	15
2591	22	-95	29	-493	180	59	182	38	9	107
11167	479	-512	330	-435	567	113	99	39	14	16
8860	77	-126	348	-632	181	318	48	34	65	9
10392	123	-163	250	-469	349	76	121	20	34	61
12326	423	-460	348	-590	449	20	69	23	10	21
13544	338	-354	753	-992	417	47	48	30	14	15
15593	33	-12	245	-361	173	46	64	25	72	56
16058	69	-52	127	-199	401	60	42	25	24	8
16060	60	-38	181	-269	176	66	30	43	74	15
17245	49	-25	134	-151	123	58	58	62	34	36

Table 3B-3: Summary of D/C Ratios for Reactor Building Wall at Grid Line 3

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;3;D-C;24-50	D/C Ratio	1.44	1.04	1.40	0.72	0.60	0.26	84
	Element	4951	4942	4951	4951	4942	4946	
RXB;3;E-D;126-145	D/C Ratio	0.29	0.07	0.43	0.14	0.05	0.09	2
	Element	15318	15318	15318	15318	15655	15655	
RXB;3;B-A;126-145	D/C Ratio	0.29	0.07	0.44	0.15	0.05	0.08	2
	Element	15319	15319	15319	15319	15656	15656	
RXB;3;E-D;145-163	D/C Ratio	1.19	0.60	0.71	0.16	0.10	0.06	16
	Element	16128	16128	16128	16131	16128	16131	
RXB;3;B-A;145-163	D/C Ratio	1.20	0.60	0.72	0.16	0.09	0.06	16
	Element	16135	16135	16135	16132	16135	16132	
RXB;3;E-D;163-181	D/C Ratio	0.25	0.10	0.44	0.08	0.08	0.05	10
	Element	14897	17545	15226	17545	17707	17573	
RXB;3;B-A;163-181	D/C Ratio	0.29	0.10	0.43	0.08	0.08	0.05	10
	Element	14898	17546	15227	17546	17708	17574	

Note:

Highlighted items indicate those design check zones that exceed a D/C ratio of 0.8.

**Table 3B-3a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Wall
at Grid Line 3**

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	4951	-78	-41	-46	21	-1	2	1	2
	4942	-758	-329	432	9	3	-4	0	0
	4946	-144	-4	21	5	0	-1	0	0
	16135	-197	-36	92	-7	-1	-2	1	0
	16128	-198	-36	-92	-5	-1	2	-1	0
	15655	0	0	0	0	0	0	0	0
Dynamic	4951	1,234	1,196	783	247	38	89	74	25
	4942	1,043	453	523	225	31	45	85	29
	4946	290	111	50	278	29	14	24	44
	16135	586	165	235	65	11	5	11	8
	16128	585	164	233	71	12	5	12	8
	15655	34	181	118	6	30	4	9	13
Hydrodynamic	4951	5	10	3	0	1	0	0	0
	4942	7	47	24	0	1	0	0	0
	4946	20	0	1	1	0	0	0	0
	16135	51	7	17	3	0	0	0	0
	16128	50	7	16	3	0	0	0	0
	15655	0	0	0	0	0	0	0	0

Table 3B-3b: Magnitudes of Bounding Final Design Forces and Moments for RXB Wall at Grid Line 3

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
4951	1,161	-1,317	1,166	-1,248	833	268	40	92	75	27
4942	293	-1,808	172	-829	978	234	36	50	86	30
4946	165	-454	107	-116	73	284	29	15	24	45
16135	440	-835	137	-208	344	75	12	7	12	8
16128	436	-833	135	-206	342	80	13	8	13	8
15655	34	-34	181	-181	118	6	30	4	9	13

Table 3B-4: Element Averaging of Horizontal Reinforcement Exceedance for Reactor Building Wall at Grid Line 3

Average of Shell Elements 4951/4431/4421: Design Check					
Horizontal Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Horizontal Reinf. D/C Ratio
11.416	7.563	1.938	20.917	28.080	0.745
			Horiz. Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			1.39	3.34	0.416
Vertical Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Vertical Reinf. D/C Ratio
9.867	7.563	0.821	18.251	28.080	0.650
			Vertical Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			1.15	3.34	0.345
Shear Friction			IP Shear	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
16.664	36,000.0	OK	Performing averaging†	129.8	0.374
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
18.213	36,000.0	OK		129.8	0.162

Note:

† See Section 3B.2.2.2 and Table 3B-51.

Table 3B-5: Element Averaging of Horizontal Membrane Compression Stress for Reactor Building Wall at Grid Line 3

Average of Shell Elements 4942/4422: Design Check					
Horizontal Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Horizontal Reinf. D/C Ratio
4.031	11.149	1.790	16.971	28.080	0.604
			Horiz. Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			2.03	3.34	0.609
Vertical Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Vertical Reinf. D/C Ratio
1.574	11.149	0.836	13.559	28.080	0.483
			Vertical Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.97	3.34	0.291
Shear Friction			IP Shear	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
24.049	36,000.0	Performing averaging†	Performing averaging††	151.9	0.371
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
26.506	36,000.0	Performing averaging†		172.4	0.141

Notes:

† See Section 3B.2.2.2 and Table 3B-52.

†† See Section 3B.2.2.2 and Table 3B-51.

Table 3B-6: Element Averaging of Vertical Reinforcement Exceedance for Reactor Building Wall at Grid Line 3

Average of Shell Elements 4951/4950/4949: Design Check					
Horizontal Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Horizontal Reinf. D/C Ratio
15.978	7.614	1.497	25.089	28.080	0.893
			Horiz. Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			1.91	3.34	0.572
Vertical Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Vertical Reinf. D/C Ratio
11.479	7.614	0.604	19.698	28.080	0.701
			Vertical Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			1.25	3.34	0.374
Shear Friction			IP Shear	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
12.102	36,000.0	OK	Performing averaging†	129.8	0.473
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
16.601	36,000.0	OK		129.8	0.117

Note:

† See Section 3B.2.2.2 and Table 3B-51.

Table 3B-7: Summary of D/C Ratios for Reactor Building Wall at Grid Line 3 After Averaging Affected Elements

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;3;D-C;24-50	D/C Ratio	0.75	0.61	0.70	0.72	0.60	0.26	84
	Element	4951	4942	4951	4951	4942	4946	
RXB;3;E-D;126-145	D/C Ratio	0.29	0.07	0.43	0.14	0.05	0.09	2
	Element	15318	15318	15318	15318	15655	15655	
RXB;3;B-A;126-145	D/C Ratio	0.29	0.07	0.44	0.15	0.05	0.08	2
	Element	15319	15319	15319	15319	15656	15656	
RXB;3;E-D;145-163	D/C Ratio	0.75	0.60	0.71	0.16	0.10	0.06	16
	Element	16128	16128	16128	16131	16128	16131	
RXB;3;B-A;145-163	D/C Ratio	0.75	0.60	0.72	0.16	0.09	0.06	16
	Element	16135	16135	16135	16132	16135	16132	
RXB;3;E-D;163-181	D/C Ratio	0.25	0.10	0.44	0.08	0.08	0.05	10
	Element	14897	17545	15226	17545	17707	17573	
RXB;3;B-A;163-181	D/C Ratio	0.29	0.10	0.43	0.08	0.08	0.05	10
	Element	14898	17546	15227	17546	17708	17574	

Note:

The highlighted values of the D/C ratios for the corresponding element shown in this table is based on the averaged demand values using methodology shown in Section 3B.1.1.1. It should be noted that the D/C ratios of all other elements shown in this table will be proportionally reduced if the same averaging methodology is used.

Table 3B-8: Summary of D/C Ratios for Reactor Building Wall at Grid Line 4

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;4;D-C;24-50	D/C Ratio	0.40	0.19	0.68	0.76	0.24	0.83	16
	Element	4638	4638	3071	3071	4638	3071	
RXB;4;C-B;24-50	D/C Ratio	0.38	0.17	0.67	0.74	0.25	0.82	16
	Element	4645	4645	3072	3072	4645	3072	
RXB;4;D-C;50-75	D/C Ratio	0.38	0.22	0.62	0.42	0.46	0.39	20
	Element	8070	8070	8073	5781	7300	7300	
RXB;4;C-B;50-75	D/C Ratio	0.40	0.22	0.62	0.42	0.50	0.42	20
	Element	8077	8077	8074	5782	7307	7307	
RXB;4;D-C;75-100	D/C Ratio	0.32	0.18	0.61	0.40	0.39	0.41	16
	Element	11582	9082	9678	9678	11582	11585	
RXB;4;C-B;75-100	D/C Ratio	0.33	0.18	0.61	0.41	0.41	0.44	16
	Element	11589	9089	9679	9679	11589	11586	
RXB;4;D-C;100-126	D/C Ratio	0.95	0.35	0.48	0.29	0.38	0.28	16
	Element	13686	13686	13686	12459	12456	12459	
RXB;4;C-B;100-126	D/C Ratio	0.96	0.36	0.48	0.30	0.40	0.30	16
	Element	13693	13693	13693	12460	12463	12460	
RXB;4;E-D;126-145	D/C Ratio	0.35	0.11	0.49	0.22	0.06	0.12	2
	Element	15364	15364	15364	15364	15701	15701	
RXB;4;B-A;126-145	D/C Ratio	0.35	0.11	0.49	0.22	0.06	0.12	2
	Element	15365	15365	15365	15365	15702	15702	
RXB;4;E-D;145-163	D/C Ratio	1.07	0.76	0.64	0.21	0.08	0.08	16
	Element	16180	16180	16180	16183	16180	16183	
RXB;4;B-A;145-163	D/C Ratio	1.07	0.75	0.64	0.21	0.09	0.08	16
	Element	16187	16187	16187	16184	16187	16184	
RXB;4;E-D;163-181	D/C Ratio	0.23	0.11	0.34	0.11	0.05	0.04	10
	Element	17547	17547	15228	17547	17709	17709	
RXB;4;B-A;163-181	D/C Ratio	0.27	0.11	0.32	0.11	0.05	0.04	10
	Element	14900	17548	15229	17548	17710	17710	

Note:

Highlighted items indicate those design check zones that exceed a D/C ratio of 0.8.

**Table 3B-8a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Wall
at Grid Line 4**

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	13693	84	-37	18	8	3	3	0	0
	3071	-78	-421	95	2	15	2	0	2
	7307	-36	-169	-69	-18	2	2	5	-2
	16180	-231	-40	-112	-11	-1	-1	-1	0
	16187	-230	-40	111	-6	-1	0	1	0
	15701	0	0	0	0	0	0	0	0
Dynamic	13693	694	251	414	529	53	69	30	18
	3071	172	870	234	58	517	156	9	106
	7307	262	101	82	760	182	44	69	75
	16180	768	216	317	47	7	5	9	6
	16187	763	215	316	54	8	6	10	7
	15701	29	304	202	10	34	4	9	15
Hydrodynamic	13693	18	20	17	1	0	1	0	0
	3071	3	38	3	0	0	0	0	0
	7307	1	37	1	1	0	0	0	0
	16180	58	7	18	4	0	0	0	0
	16187	59	7	18	3	0	0	0	0
	15701	0	0	0	0	0	0	0	0

Table 3B-8b: Magnitudes of Bounding Final Design Forces and Moments for RXB Wall at Grid Line 4

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
13693	796	-627	234	-308	448	539	56	73	30	18
3071	97	-252	487	-1,329	331	60	532	157	9	108
7307	227	-298	-30	-307	152	779	185	46	75	78
16180	596	-1,057	182	-263	447	61	9	6	10	6
16187	592	-1,051	182	-262	445	63	10	7	11	7
15701	29	-29	304	-304	202	10	34	4	9	15

Table 3B-9: Element Averaging of Reinforcement Exceedance for Reactor Building Wall at Grid Line 4

Average of Shell Elements 16180/16479/16778: Design Check					
Horizontal Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Horizontal Reinf. D/C Ratio
4.504	5.537	0.367	10.408	18.720	0.556
			Horiz. Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.96	3.15	0.304
Vertical Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Vertical Reinf. D/C Ratio
2.174	5.537	0.089	7.800	18.720	0.417
			Vertical Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.38	3.15	0.120
Shear Friction			IP Shear	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
14.216	28,800.0	OK	Performing Averaging†	130.6	0.061
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
16.546	28,800.0	OK		151.4	0.030

Note:

† See Section 3B.2.2.2 and Table 3B-51.

Table 3B-10: Summary of D/C Ratios for RXB Wall at Grid Line 4 After Averaging Affected Elements

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;4;D-C;24-50	D/C Ratio	0.40	0.19	0.68	0.76	0.24	0.83	16
	Element	4638	4638	3071	3071	4638	3071	
RXB;4;C-B;24-50	D/C Ratio	0.38	0.17	0.67	0.74	0.25	0.82	16
	Element	4645	4645	3072	3072	4645	3072	
RXB;4;D-C;50-75	D/C Ratio	0.38	0.22	0.62	0.42	0.46	0.39	20
	Element	8070	8070	8073	5781	7300	7300	
RXB;4;C-B;50-75	D/C Ratio	0.40	0.22	0.62	0.42	0.50	0.42	20
	Element	8077	8077	8074	5782	7307	7307	
RXB;4;D-C;75-100	D/C Ratio	0.32	0.18	0.61	0.40	0.39	0.41	16
	Element	11582	9082	9678	9678	11582	11585	
RXB;4;C-B;75-100	D/C Ratio	0.33	0.18	0.61	0.41	0.41	0.44	16
	Element	11589	9089	9679	9679	11589	11586	
RXB;4;D-C;100-126	D/C Ratio	0.95	0.35	0.48	0.29	0.38	0.28	16
	Element	13686	13686	13686	12459	12456	12459	
RXB;4;C-B;100-126	D/C Ratio	0.96	0.36	0.48	0.30	0.40	0.30	16
	Element	13693	13693	13693	12460	12463	12460	
RXB;4;E-D;126-145	D/C Ratio	0.35	0.11	0.49	0.22	0.06	0.12	2
	Element	15364	15364	15364	15364	15701	15701	
RXB;4;B-A;126-145	D/C Ratio	0.35	0.11	0.49	0.22	0.06	0.12	2
	Element	15365	15365	15365	15365	15702	15702	
RXB;4;E-D;145-163	D/C Ratio	0.56	0.76	0.64	0.21	0.08	0.08	16
	Element	16180	16180	16180	16183	16180	16183	
RXB;4;B-A;145-163	D/C Ratio	0.56	0.75	0.64	0.21	0.09	0.08	16
	Element	16187	16187	16187	16184	16187	16184	
RXB;4;E-D;163-181	D/C Ratio	0.23	0.11	0.34	0.11	0.05	0.04	10
	Element	17547	17547	15228	17547	17709	17709	
RXB;4;B-A;163-181	D/C Ratio	0.27	0.11	0.32	0.11	0.05	0.04	10
	Element	14900	17548	15229	17548	17710	17710	

Note:

The highlighted values of the D/C ratios for the corresponding element shown in this table is based on the averaged demand values using methodology shown in Section 3B.1.1.1. It should be noted that the D/C ratios of all other elements shown in this table will be proportionally reduced if the same averaging methodology is used.

Table 3B-11: Summary of D/C Ratios for RXB Wall at Grid Line 6

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;6;D-C.5;24-50	D/C Ratio	0.23	0.09	0.47	0.35	0.22	0.28	12
	Element	3745	4884	3164	3164	4884	4885	
RXB;6;C.5-C;24-50	D/C Ratio	0.29	0.07	0.35	0.28	0.09	0.28	12
	Element	4887	4887	4887	3167	4357	4889	
RXB;6;C-B.5;24-50	D/C Ratio	0.29	0.07	0.33	0.28	0.10	0.29	12
	Element	4892	4892	4891	3172	4362	4890	
RXB;6;B.5-B;24-50	D/C Ratio	0.30	0.11	0.50	0.38	0.24	0.58	15
	Element	2060	2060	2060	2060	4895	2060	
RXB;6;D-C.5;50-75	D/C Ratio	0.38	0.17	0.33	0.26	0.38	0.42	15
	Element	7463	8202	6577	6577	8202	8203	
RXB;6;C-5-C;50-75	D/C Ratio	0.32	0.09	0.34	0.20	0.16	0.27	15
	Element	7151	8205	7467	6026	6580	8205	
RXB;6;C-B.5;50-75	D/C Ratio	0.36	0.11	0.34	0.21	0.07	0.26	15
	Element	8209	8209	7470	6029	7470	8210	
RXB;6;B.5-B;50-75	D/C Ratio	0.35	0.14	0.31	0.26	0.31	0.50	15
	Element	7473	8212	6032	8213	6032	8213	
RXB;6;D-C.5;75-100	D/C Ratio	0.33	0.13	0.28	0.19	0.28	0.21	12
	Element	9362	9362	9362	9362	9955	11678	
RXB;6;C.5-C;75-100	D/C Ratio	0.40	0.08	0.39	0.15	0.04	0.11	12
	Element	11681	9365	11682	9365	9958	11681	
RXB;6;C-B.5;75-100	D/C Ratio	0.41	0.08	0.39	0.15	0.04	0.11	12
	Element	11686	9963	11685	9370	9963	11686	
RXB;6;B.5-B;75-100	D/C Ratio	0.33	0.13	0.28	0.19	0.28	0.21	12
	Element	9373	9373	9373	9373	9966	11689	
RXB;6;D-C.5;100-126	D/C Ratio	0.48	0.09	0.44	0.14	0.20	0.15	12
	Element	13878	13878	13468	13878	13878	13466	
RXB;6;C.5-C;100-126	D/C Ratio	0.53	0.09	0.58	0.14	0.04	0.15	11
	Element	13469	12986	13470	12986	13881	13469	
RXB;6;C-B.5;100-126	D/C Ratio	0.53	0.09	0.58	0.14	0.04	0.15	11
	Element	13471	12991	13471	12991	13886	13472	

Table 3B-11: Summary of D/C Ratios for RXB Wall at Grid Line 6 (Continued)

		Demand/Capacity Ratios						# Elems Checked
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
RXB;6;B.5-B;100-126	D/C Ratio	0.48	0.09	0.44	0.15	0.20	0.15	12
	Element	13889	13889	13473	13889	13889	13475	
RXB;6;E-D;126-145	D/C Ratio	0.61	0.20	0.64	0.22	0.12	0.12	2
	Element	15845	15845	15845	15845	15845	15845	
RXB;6;D-C;126-145	D/C Ratio	1.27	0.59	0.40	0.19	0.33	0.14	24
	Element	15846	15846	15495	15137	15846	14842	
RXB;6;C-B;126-145	D/C Ratio	1.27	0.59	0.39	0.19	0.33	0.13	24
	Element	15857	15857	15506	15148	15857	14851	
RXB;6;B-A;126-145	D/C Ratio	0.61	0.20	0.64	0.22	0.12	0.12	2
	Element	15858	15858	15858	15858	15858	15858	
RXB;6;E-D;145-163	D/C Ratio	1.46	0.61	0.60	0.18	0.17	0.06	16
	Element	16295	16295	16295	16594	16295	17189	
RXB;6;B-A;145-163	D/C Ratio	1.47	0.61	0.60	0.18	0.17	0.05	16
	Element	16296	16296	16296	16595	16296	17196	
RXB;6;E-D;163-181	D/C Ratio	0.28	0.12	0.35	0.16	0.20	0.11	10
	Element	14903	14903	17385	14903	17713	17579	
RXB;6;B-A;163-181	D/C Ratio	0.28	0.12	0.35	0.16	0.20	0.11	10
	Element	14904	15201	17390	15201	17714	17580	

Note:

Highlighted items indicate those design check zones that exceed a D/C ratio of 0.8.

Table 3B-11a: Magnitudes of Bounding, Dynamic, and Hydrodynamic Forces and Moments for RXB Wall at Grid Line 6

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	13889	-4	-144	-42	5	17	-13	-4	-14
	2060	-48	-263	33	16	12	19	-6	49
	8202	-89	-232	36	-92	137	37	-21	-61
	13469	-14	-54	13	-5	-25	3	-1	-6
	13470	-11	-43	2	-6	-27	-1	1	-7
	6580	-55	-133	4	36	6	3	3	7
	4890	-37	-169	-1	35	130	3	1	-34
	15846	175	-12	-45	48	11	-16	5	-2
	15495	-12	-39	27	25	5	-10	4	-3
	15857	175	-11	44	47	8	15	-5	-3
	14842	-3	-38	19	-3	-9	4	1	-4
	16296	82	-1	45	-44	-11	4	-5	-1
	15845	0	0	0	0	0	0	0	0
	17713	-16	-15	-9	-9	7	-3	8	-5
	15858	0	0	0	0	0	0	0	0
Dynamic	13889	212	174	357	271	62	80	49	28
	2060	196	564	249	42	297	40	18	85
	8202	331	162	185	137	173	77	84	23
	13469	43	80	462	25	72	21	6	19
	13470	26	69	491	15	84	6	2	11
	6580	83	107	261	81	65	26	25	15
	4890	39	146	259	33	90	9	2	21
	15846	1,048	120	266	224	20	42	36	5
	15495	457	230	275	196	36	53	22	5
	15857	1,045	121	264	225	21	42	36	5
	14842	209	72	241	34	39	55	11	19
	16296	912	186	335	108	18	6	14	6
	15845	284	309	329	23	29	11	15	15
	17713	45	47	65	25	9	3	23	5
	15858	284	308	329	25	26	12	15	15

Table 3B-11a: Magnitudes of Bounding, Dynamic, and Hydrodynamic Forces and Moments for RXB Wall at Grid Line 6 (Continued)

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Hydrodynamic	13889	9	44	8	19	13	2	3	3
	2060	14	87	8	1	10	3	1	11
	8202	1	56	1	9	14	1	0	0
	13469	1	17	3	3	6	1	0	2
	13470	2	13	1	3	8	0	0	2
	6580	1	39	0	2	5	1	2	0
	4890	3	49	0	2	8	1	0	0
	15846	54	7	13	13	3	6	1	0
	15495	4	14	8	9	2	4	1	0
	15857	53	7	13	13	3	5	1	1
	14842	5	14	5	1	0	1	0	1
	16296	24	3	12	12	3	1	1	0
	15845	0	0	0	0	0	0	0	0
	17713	7	4	2	2	2	1	2	1
	15858	0	0	0	0	0	0	0	0

Table 3B-11b: Magnitudes of Bounding Final Design Forces and Moments for RXB Wall at Grid Line 6

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
13889	218	-225	74	-361	407	295	91	95	55	44
2060	162	-259	388	-914	289	59	318	62	24	145
8202	243	-421	-13	-450	222	238	324	114	105	85
13469	30	-59	43	-151	478	32	103	25	7	27
13470	18	-39	39	-125	494	24	120	7	3	21
6580	28	-139	13	-278	265	120	75	30	31	22
4890	5	-78	26	-364	260	71	229	12	3	55
15846	1,277	-927	115	-140	324	284	33	64	42	8
15495	449	-473	205	-283	309	230	43	66	27	8
15857	1,273	-923	116	-139	321	285	31	63	42	9
14842	211	-216	48	-124	264	38	48	60	13	24
16296	1,018	-853	188	-190	392	164	32	12	20	7
15845	284	-284	309	-309	329	23	29	11	15	15
17713	36	-68	36	-66	76	37	17	7	33	12
15858	284	-284	308	-308	329	25	26	12	15	15

Table 3B-12: Element Averaging of Horizontal Reinforcement Exceedance for RXB Wall at Grid Line 6

Average of Shell Elements 16296/16595: Design Check					
Horizontal Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Horizontal Reinf. D/C Ratio
10.227	5.549	1.198	16.975	18.720	0.907
			Horiz. Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			1.19	3.15	0.376
Vertical Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Vertical Reinf. D/C Ratio
3.630	5.549	0.309	9.488	18.720	0.507
			Vertical Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.49	3.15	0.156
Shear Friction			IP Shear	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
8.493	28,800.0	OK	Performing Averaging†	123.2	0.139
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
15.090	28,800.0	OK		138.4	0.036

Note:

† See Section 3B.2.2.2 and Table 3B-52.

Table 3B-13: Summary of D/C Ratios for Reactor Building Wall at Grid Line 6 after Averaging Affected Elements

		Demand/Capacity Ratios						
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;6;D-C.5;24-50	D/C Ratio	0.23	0.09	0.47	0.35	0.22	0.28	12
	Element	3745	4884	3164	3164	4884	4885	
RXB;6;C.5-C;24-50	D/C Ratio	0.29	0.07	0.35	0.28	0.09	0.28	12
	Element	4887	4887	4887	3167	4357	4889	
RXB;6;C-B.5;24-50	D/C Ratio	0.29	0.07	0.33	0.28	0.10	0.29	12
	Element	4892	4892	4891	3172	4362	4890	
RXB;6;B.5-B;24-50	D/C Ratio	0.30	0.11	0.50	0.38	0.24	0.58	15
	Element	2060	2060	2060	2060	4895	2060	
RXB;6;D-C.5;50-75	D/C Ratio	0.38	0.17	0.33	0.26	0.38	0.42	15
	Element	7463	8202	6577	6577	8202	8203	
RXB;6;C-5-C;50-75	D/C Ratio	0.32	0.09	0.34	0.20	0.16	0.27	15
	Element	7151	8205	7467	6026	6580	8205	
RXB;6;C-B.5;50-75	D/C Ratio	0.36	0.11	0.34	0.21	0.07	0.26	15
	Element	8209	8209	7470	6029	7470	8210	
RXB;6;B.5-B;50-75	D/C Ratio	0.35	0.14	0.31	0.26	0.31	0.50	15
	Element	7473	8212	6032	8213	6032	8213	
RXB;6;D-C.5;75-100	D/C Ratio	0.33	0.13	0.28	0.19	0.28	0.21	12
	Element	9362	9362	9362	9362	9955	11678	
RXB;6;C.5-C;75-100	D/C Ratio	0.40	0.08	0.39	0.15	0.04	0.11	12
	Element	11681	9365	11682	9365	9958	11681	
RXB;6;C-B.5;75-100	D/C Ratio	0.41	0.08	0.39	0.15	0.04	0.11	12
	Element	11686	9963	11685	9370	9963	11686	
RXB;6;B.5-B;75-100	D/C Ratio	0.33	0.13	0.28	0.19	0.28	0.21	12
	Element	9373	9373	9373	9373	9966	11689	
RXB;6;D-C.5;100-126	D/C Ratio	0.48	0.09	0.44	0.14	0.20	0.15	12
	Element	13878	13878	13468	13878	13878	13466	
RXB;6;C.5-C;100-126	D/C Ratio	0.53	0.09	0.58	0.14	0.04	0.15	11
	Element	13469	12986	13470	12986	13881	13469	

Table 3B-13: Summary of D/C Ratios for Reactor Building Wall at Grid Line 6 after Averaging Affected Elements (Continued)

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;6;C-B.5;100-126	D/C Ratio	0.53	0.09	0.58	0.14	0.04	0.15	11
	Element	13471	12991	13471	12991	13886	13472	
RXB;6;B.5-B;100-126	D/C Ratio	0.48	0.09	0.44	0.15	0.20	0.15	12
	Element	13889	13889	13473	13889	13889	13475	
RXB;6;E-D;126-145	D/C Ratio	0.61	0.20	0.64	0.22	0.12	0.12	2
	Element	15845	15845	15845	15845	15845	15845	
RXB;6;D-C;126-145	D/C Ratio	0.91	0.59	0.40	0.19	0.33	0.14	24
	Element	15846	15846	15495	15137	15846	14842	
RXB;6;C-B;126-145	D/C Ratio	0.91	0.59	0.39	0.19	0.33	0.13	24
	Element	15857	15857	15506	15148	15857	14851	
RXB;6;B-A;126-145	D/C Ratio	0.61	0.20	0.64	0.22	0.12	0.12	2
	Element	15858	15858	15858	15858	15858	15858	
RXB;6;E-D;145-163	D/C Ratio	0.91	0.61	0.60	0.18	0.17	0.06	16
	Element	16295	16295	16295	16594	16295	17189	
RXB;6;B-A;145-163	D/C Ratio	0.91	0.61	0.60	0.18	0.17	0.05	16
	Element	16296	16296	16296	16595	16296	17196	
RXB;6;E-D;163-181	D/C Ratio	0.28	0.12	0.35	0.16	0.20	0.11	10
	Element	14903	14903	17385	14903	17713	17579	
RXB;6;B-A;163-181	D/C Ratio	0.28	0.12	0.35	0.16	0.20	0.11	10
	Element	14904	15201	17390	15201	17714	17580	

Note:

The highlighted values of the D/C ratios for the corresponding element shown in this table is based on the averaged demand values using methodology shown in Section 3B.1.1.1. It should be noted that the D/C ratios of all other elements shown in this table will be proportionally reduced if the same averaging methodology is used.

Table 3B-14: Summary of D/C Ratios for Reactor Building Wall at Grid Line E

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;E;1-2;24-50	D/C Ratio	0.38	0.10	0.53	0.43	0.57	0.54	24
	Element	2642	3257	2599	2599	3924	4526	
RXB;E;2-3;24-50	D/C Ratio	0.33	0.11	0.59	0.51	0.26	0.60	28
	Element	2666	4005	2659	2654	2666	4559	
RXB;E;3-4;24-50	D/C Ratio	0.51	0.11	0.55	0.35	0.19	0.57	44
	Element	2669	2680	2669	2680	3424	2684	
RXB;E;4-5;24-50	D/C Ratio	0.21	0.09	0.26	0.34	0.21	0.61	48
	Element	2822	2722	2802	2774	3570	2794	
RXB;E;5-6;24-50	D/C Ratio	0.24	0.08	0.35	0.35	0.20	0.55	48
	Element	2940	2952	2940	2940	3586	2840	
RXB;E;6-7;24-50	D/C Ratio	0.23	0.09	0.30	0.35	0.34	0.48	20
	Element	2962	2962	4372	4916	4916	2962	
RXB;E;1-2;50-75	D/C Ratio	0.35	0.08	0.65	0.38	0.49	0.28	24
	Element	5613	5597	7747	6738	5597	5630	
RXB;E;2-3;50-75	D/C Ratio	0.36	0.10	0.49	0.33	0.30	0.42	28
	Element	7787	5662	5670	5670	7785	7789	
RXB;E;3-4;50-75	D/C Ratio	0.31	0.08	0.35	0.26	0.21	0.42	44
	Element	5698	5730	6262	5718	7797	7807	
RXB;E;4-5;50-75	D/C Ratio	0.18	0.06	0.24	0.26	0.13	0.44	48
	Element	5883	5810	7843	5889	6445	7843	
RXB;E;5-6;50-75	D/C Ratio	0.19	0.06	0.30	0.29	0.13	0.43	48
	Element	5913	5961	6559	6011	6463	7885	
RXB;E;6-7;50-75	D/C Ratio	0.24	0.06	0.43	0.36	0.34	0.39	20
	Element	7166	6062	7168	6062	6620	7899	
RXB;E;1-2;75-100	D/C Ratio	0.37	0.04	0.78	0.36	0.41	0.26	24
	Element	11177	9495	9453	8861	8861	8902	
RXB;E;2-3;75-100	D/C Ratio	0.35	0.09	0.41	0.21	0.30	0.41	28
	Element	8926	8921	10438	8916	8921	8966	
RXB;E;3-4;75-100	D/C Ratio	0.27	0.09	0.32	0.17	0.21	0.47	44
	Element	11267	11267	10486	9072	11241	9072	

Table 3B-14: Summary of D/C Ratios for Reactor Building Wall at Grid Line E (Continued)

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;E;4-5;75-100	D/C Ratio	0.28	0.09	0.33	0.17	0.16	0.46	48
	Element	11269	11269	10576	9210	10560	9094	
RXB;E;5-6;75-100	D/C Ratio	0.21	0.05	0.37	0.23	0.13	0.41	48
	Element	10654	11301	10728	9350	10652	9234	
RXB;E;6-7;75-100	D/C Ratio	0.23	0.04	0.48	0.32	0.28	0.33	20
	Element	9386	9406	10748	9406	9406	9378	
RXB;E;1-2;100-126	D/C Ratio	0.31	0.03	0.70	0.19	0.20	0.26	24
	Element	12333	13584	12333	12333	12333	13584	
RXB;E;2-3;100-126	D/C Ratio	0.30	0.06	0.40	0.15	0.24	0.39	26
	Element	13596	13623	12375	12375	13173	12395	
RXB;E;3-4;100-126	D/C Ratio	0.47	0.12	0.31	0.08	0.20	0.43	44
	Element	13660	13660	12415	12819	12399	13269	
RXB;E;4-5;100-126	D/C Ratio	0.36	0.08	0.25	0.09	0.13	0.34	48
	Element	13283	13695	13771	12527	13777	13695	
RXB;E;5-6;100-126	D/C Ratio	0.25	0.05	0.33	0.15	0.14	0.25	48
	Element	13797	13791	12599	12599	13791	12539	
RXB;E;6-7;100-126	D/C Ratio	0.19	0.01	0.46	0.18	0.18	0.16	20
	Element	13025	13891	13025	12655	13488	13025	
RXB;E;1-2;126-145	D/C Ratio	0.26	0.05	0.42	0.12	0.35	0.38	24
	Element	15613	15613	14631	14631	15613	15608	
RXB;E;2-3;126-145	D/C Ratio	0.39	0.10	0.23	0.07	0.21	0.37	28
	Element	15651	15651	14661	14661	14669	14685	
RXB;E;3-4;126-145	D/C Ratio	0.47	0.13	0.27	0.06	0.26	0.69	44
	Element	15348	15348	15697	15697	15697	15360	
RXB;E;4-5;126-145	D/C Ratio	0.42	0.11	0.31	0.07	0.20	0.65	48
	Element	15703	15366	15766	15766	15766	14791	
RXB;E;5-6;126-145	D/C Ratio	0.44	0.09	0.38	0.11	0.22	0.65	48
	Element	15779	15779	15779	15841	15779	14795	
RXB;E;6-7;126-145	D/C Ratio	0.13	0.03	0.35	0.13	0.13	0.20	20
	Element	15859	15859	14859	14859	14859	14853	

Table 3B-14: Summary of D/C Ratios for Reactor Building Wall at Grid Line E (Continued)

		Demand/Capacity Ratios						
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;E;1-2;145-163	D/C Ratio	0.34	0.09	0.21	0.06	0.31	0.27	24
	Element	16985	16985	16065	16065	16088	16387	
RXB;E;2-3;145-163	D/C Ratio	0.60	0.16	0.25	0.04	0.21	0.46	28
	Element	17021	17021	16124	16100	16124	16423	
RXB;E;3-4;145-163	D/C Ratio	0.59	0.16	0.29	0.04	0.36	0.57	44
	Element	17033	17049	16176	16176	16176	16475	
RXB;E;4-5;145-163	D/C Ratio	0.54	0.15	0.32	0.04	0.32	0.56	48
	Element	17105	17101	16232	16188	16188	16531	
RXB;E;5-6;145-163	D/C Ratio	0.54	0.12	0.43	0.09	0.31	0.54	48
	Element	16543	17153	16244	16288	16244	16543	
RXB;E;6-7;145-163	D/C Ratio	0.29	0.04	0.36	0.10	0.18	0.19	20
	Element	16898	17205	16300	16300	17197	16599	

Table 3B-14a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Wall at Grid Line E

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	2669	-64	-307	-8	18	-70	-30	5	-68
	3924	-60	-227	8	-149	-5	-20	-55	2
	2794	-49	-286	-12	-22	-138	6	0	-73
	2666	-60	-304	6	-6	-83	26	1	-69
	2659	-49	-284	5	-21	-162	6	1	-75
	4559	-45	-239	-2	-12	-42	4	8	54
	11177	-1	-84	-13	-30	-11	15	-6	4
	9453	-14	-114	-5	-72	-13	10	-19	-5
	5597	-52	-207	3	-160	-19	3	-51	3
	9072	-38	-159	10	9	13	-2	1	-6
	17021	-5	0	-10	-20	-17	4	0	-13
	12333	5	-61	-10	-15	-12	9	-1	-4
	16176	-13	-31	-18	-29	-82	-5	24	-3
	15360	-14	-49	-3	-15	-26	1	12	28
Dynamic	2669	92	160	340	29	270	100	24	50
	3924	110	368	114	171	38	49	65	19
	2794	87	223	128	59	278	15	4	58
	2666	103	221	353	17	396	110	67	50
	2659	111	506	215	152	729	78	18	47
	4559	107	340	163	27	108	18	7	94
	11177	33	409	170	194	25	65	61	11
	9453	42	483	160	192	35	29	58	28
	5597	83	389	121	142	37	49	57	13
	9072	54	93	143	12	67	80	5	100
	17021	358	53	87	58	49	53	28	72
	12333	28	383	164	162	18	94	43	15
	16176	263	65	86	107	407	31	39	48
	15360	198	71	79	52	219	50	11	128

Table 3B-14a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Wall at Grid Line E (Continued)

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Hydrodynamic	2669	12	78	8	2	3	0	1	3
	3924	1	60	4	4	1	0	1	0
	2794	11	75	2	2	11	0	0	3
	2666	11	78	2	0	5	0	1	3
	2659	9	72	6	2	10	0	0	3
	4559	6	65	6	1	3	0	0	1
	11177	4	18	2	7	1	1	3	1
	9453	3	24	1	3	0	0	2	1
	5597	1	49	3	3	1	0	0	0
	9072	1	42	1	1	0	1	0	1
	17021	5	2	1	7	2	0	1	3
	12333	4	13	0	7	1	1	3	1
	16176	3	3	2	8	15	0	4	1
	15360	4	9	0	2	7	2	2	5

Table 3B-14b: Magnitudes of Bounding Final Design Forces and Moments for RXB Wall at Grid Line E

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
2669	40	-168	-68	-546	357	49	344	130	29	121
3924	50	-171	201	-655	126	325	44	69	120	22
2794	49	-147	11	-583	142	83	428	21	5	134
2666	53	-174	-5	-604	361	24	484	137	69	122
2659	70	-169	294	-863	226	174	901	84	19	125
4559	68	-158	166	-643	171	40	153	22	15	149
11177	35	-38	343	-510	186	231	37	81	70	16
9453	31	-59	393	-621	167	268	48	40	79	35
5597	32	-136	231	-645	128	305	57	53	109	16
9072	18	-93	-24	-294	153	22	80	82	7	107
17021	358	-368	54	-55	97	85	68	58	30	89
12333	37	-27	335	-456	175	184	31	105	47	21
16176	253	-280	37	-98	107	144	504	36	67	51
15360	187	-215	32	-129	83	69	252	53	25	161

Table 3B-15: Summary of D/C Ratios for Reactor Building Slab at EL. 100'-0"

		Demand/Capacity Ratios						# Elems Checked
Section		East-West Reinf.	E-W Comp. Stress	North-South Reinf.	N-S Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
RXB;100;1-2;D-E.a	D/C Ratio	0.49	0.08	0.53	0.34	1.30	0.90	17
	Element	11738	11758	11760	11782	11738	11704	
RXB;100;2-3;D-E.a	D/C Ratio	0.47	0.12	0.68	0.22	0.23	0.46	31
	Element	11810	11818	11804	11804	11810	11857	
RXB;100;3-4;D-E.a	D/C Ratio	0.37	0.07	0.87	0.27	0.25	0.81	55
	Element	11960	11966	11970	11970	11937	11966	
RXB;100;4-5;D-E.a	D/C Ratio	0.18	0.06	0.67	0.25	0.28	0.79	60
	Element	11990	11976	11980	11980	11978	11976	
RXB;100;5-6;D-E.a	D/C Ratio	0.18	0.07	0.51	0.19	0.16	0.52	60
	Element	12200	12210	12100	12100	12209	12210	
RXB;100;6-7;D-E.a	D/C Ratio	0.18	0.11	0.25	0.16	0.19	0.46	18
	Element	12280	12220	12242	12220	12296	12220	
RXB;100;1-2;C-D.a	D/C Ratio	0.62	0.15	0.64	0.35	0.24	0.44	36
	Element	11788	11788	11783	11783	11788	11690	
RXB;100;6-7;C-D.a	D/C Ratio	0.18	0.10	0.17	0.09	0.19	0.22	30
	Element	12301	12221	12243	12221	12222	12224	
RXB;100;1-2;B-C.a	D/C Ratio	0.61	0.15	0.66	0.35	0.27	0.94	36
	Element	11789	11789	11794	11794	11696	11697	
RXB;100;6-7;B-C.a	D/C Ratio	0.17	0.10	0.17	0.09	0.19	0.23	30
	Element	12254	12232	12254	12232	12231	12229	
RXB;100;1-2;A-B.a	D/C Ratio	0.40	0.12	0.44	0.30	1.06	0.42	21
	Element	11755	11755	11717	11795	11755	11775	
RXB;100;2-3;A-B.a	D/C Ratio	0.36	0.06	0.52	0.18	0.20	0.45	35
	Element	11805	11807	11805	11805	11864	11864	
RXB;100;3-4;A-B.a	D/C Ratio	0.35	0.07	0.87	0.27	0.25	0.82	55
	Element	11961	11975	11971	11971	11944	11975	
RXB;100;4-5;A-B.a	D/C Ratio	0.18	0.07	0.67	0.25	0.27	0.80	60
	Element	11991	11985	11981	11981	11983	11985	
RXB;100;5-6;A-B.a	D/C Ratio	0.19	0.08	0.51	0.19	0.16	0.53	60
	Element	12201	12211	12101	12101	12212	12211	

Table 3B-15: Summary of D/C Ratios for Reactor Building Slab at EL. 100'-0" (Continued)

Section		Demand/Capacity Ratios						# Elems Checked
		East-West Reinf.	E-W Comp. Stress	North-South Reinf.	N-S Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
RXB;100;6-7;A-B.a	D/C Ratio	0.18	0.11	0.26	0.17	0.19	0.47	18
	Element	12295	12233	12233	12233	12311	12233	

Note:
Highlighted items indicate those design check zones that exceed a D/C ratio of 0.8.

**Table 3B-15a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Slab
at EL. 100'-0"**

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	11788	-1	-11	2	-31	-7	-2	11	0
	11971	6	-23	22	-1	-1	1	1	-1
	11738	4	-41	20	-3	-2	2	-4	-3
	11697	-1	-5	8	-10	-3	-1	-6	2
Dynamic	11788	147	67	143	39	14	11	13	11
	11971	33	251	106	34	228	7	11	60
	11738	83	56	105	50	113	62	150	12
	11697	32	224	42	50	41	13	24	90
Hydrodynamic	11788	3	15	1	9	2	0	3	0
	11971	1	3	1	1	2	0	0	1
	11738	7	9	5	0	1	0	1	1
	11697	1	9	4	0	1	0	1	0

Table 3B-15b: Magnitudes of Bounding Final Design Forces and Moments for RXB Slab at EL. 100'-0"

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
11788	149	-151	71	-93	147	79	24	13	26	11
11971	40	-29	231	-276	129	35	232	9	12	62
11738	93	-85	24	-107	130	53	116	64	155	16
11697	32	-34	228	-238	55	61	45	15	31	92

Table 3B-16: Element Averaging of XZ Plane Shear Exceedance for Reactor Building Slab at EL. 100'-0"

Average of Shell Elements 11738/11739: Design Check					
East-West Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	East-West Reinf. D/C Ratio
1.310	1.747	0.885	3.942	9.360	0.421
			E-W Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.17	2.84	0.060
North-South Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	North-South Reinf. D/C Ratio
0.590	1.747	1.144	3.482	9.360	0.372
			N-S Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.30	2.84	0.107
Shear Friction			IP Shear	OOP Shear	
XZ-Plane Shear-Friction A_{vf_x} (in ²)	$\phi_v V_{nx} = \phi_v A_{vf_x} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
8.050	21,600.0	OK	OK	122.9	0.727
YZ-Plane Shear-Friction A_{vf_y} (in ²)	$\phi_v V_{ny} = \phi_v A_{vf_y} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
8.770	21,600.0	OK		129.7	0.121

Table 3B-17: Summary of D/C Ratios for Reactor Building Slab at EL. 100'-0" After Averaging Affected Elements

		Demand/Capacity Ratios						# Elems Checked
Section		East-West Reinf.	E-W Comp. Stress	North-South Reinf.	N-S Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
RXB;100;1-2;D-E.a	D/C Ratio	0.49	0.08	0.53	0.34	0.73	0.90	17
	Element	11738	11758	11760	11782	11738	11704	
RXB;100;2-3;D-E.a	D/C Ratio	0.47	0.12	0.68	0.22	0.23	0.46	31
	Element	11810	11818	11804	11804	11810	11857	
RXB;100;3-4;D-E.a	D/C Ratio	0.37	0.07	0.87	0.27	0.25	0.81	55
	Element	11960	11966	11970	11970	11937	11966	
RXB;100;4-5;D-E.a	D/C Ratio	0.18	0.06	0.67	0.25	0.28	0.79	60
	Element	11990	11976	11980	11980	11978	11976	
RXB;100;5-6;D-E.a	D/C Ratio	0.18	0.07	0.51	0.19	0.16	0.52	60
	Element	12200	12210	12100	12100	12209	12210	
RXB;100;6-7;D-E.a	D/C Ratio	0.18	0.11	0.25	0.16	0.19	0.46	18
	Element	12280	12220	12242	12220	12296	12220	
RXB;100;1-2;C-D.a	D/C Ratio	0.62	0.15	0.64	0.35	0.24	0.44	36
	Element	11788	11788	11783	11783	11788	11690	
RXB;100;6-7;C-D.a	D/C Ratio	0.18	0.10	0.17	0.09	0.19	0.22	30
	Element	12301	12221	12243	12221	12222	12224	
RXB;100;1-2;B-C.a	D/C Ratio	0.61	0.15	0.66	0.35	0.27	0.94	36
	Element	11789	11789	11794	11794	11696	11697	
RXB;100;6-7;B-C.a	D/C Ratio	0.17	0.10	0.17	0.09	0.19	0.23	30
	Element	12254	12232	12254	12232	12231	12229	
RXB;100;1-2;A-B.a	D/C Ratio	0.40	0.12	0.44	0.30	0.73	0.42	21
	Element	11755	11755	11717	11795	11755	11775	
RXB;100;2-3;A-B.a	D/C Ratio	0.36	0.06	0.52	0.18	0.20	0.45	35
	Element	11805	11807	11805	11805	11864	11864	
RXB;100;3-4;A-B.a	D/C Ratio	0.35	0.07	0.87	0.27	0.25	0.82	55
	Element	11961	11975	11971	11971	11944	11975	
RXB;100;4-5;A-B.a	D/C Ratio	0.18	0.07	0.67	0.25	0.27	0.80	60
	Element	11991	11985	11981	11981	11983	11985	

Table 3B-17: Summary of D/C Ratios for Reactor Building Slab at EL. 100'-0" After Averaging Affected Elements (Continued)

Demand/Capacity Ratios								
Section		East-West Reinf.	E-W Comp. Stress	North-South Reinf.	N-S Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
RXB;100;5-6;A-B.a	D/C Ratio	0.19	0.08	0.51	0.19	0.16	0.53	60
	Element	12201	12211	12101	12101	12212	12211	
RXB;100;6-7;A-B.a	D/C Ratio	0.18	0.11	0.26	0.17	0.19	0.47	18
	Element	12295	12233	12233	12233	12311	12233	

Note:
The highlighted values of the D/C ratios for the corresponding element shown in this table is based on the averaged demand values using methodology shown in Section 3B.1.1.1. It should be noted that the D/C ratios of all other elements shown in this table will be proportionally reduced if the same averaging methodology is used.

Table 3B-18: Summary of D/C Ratios for RXB Roof Slab

		Demand/Capacity Ratios						# Elems Checked
Section		East-West Reinf.	E-W Comp. Stress	North-South Reinf.	N-S Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
RXB;181;1-2;D.3-E	D/C Ratio	0.26	0.12	0.26	0.04	0.11	0.24	24
	Element	17275	17275	17967	17275	17583	17967	
RXB;181;2-3;D.3-E	D/C Ratio	0.42	0.21	0.34	0.07	0.18	0.42	28
	Element	17295	17295	17981	17295	17755	17981	
RXB;181;3-4;D.3-E	D/C Ratio	0.37	0.21	0.34	0.08	0.29	0.51	44
	Element	17305	17309	17983	17303	17777	18003	
RXB;181;4-5;D.3-E	D/C Ratio	0.39	0.20	0.41	0.07	0.26	0.49	48
	Element	17653	17339	18027	17331	17779	18005	
RXB;181;5-6;D.3-E	D/C Ratio	0.38	0.16	0.42	0.08	0.23	0.48	48
	Element	17677	17367	18049	17677	17803	18029	
RXB;181;6-7;D.3-E	D/C Ratio	0.19	0.07	0.27	0.07	0.22	0.29	20
	Element	18053	18053	18053	17679	17391	17391	
RXB;181;1-2;C-D.3	D/C Ratio	0.63	0.08	0.49	0.04	0.36	0.27	42
	Element	18083	18147	18147	18083	18083	18147	
RXB;181;2-3;C-D.3	D/C Ratio	0.43	0.12	0.54	0.05	0.09	0.44	49
	Element	18161	18245	18245	18245	18167	18245	
RXB;181;3-4;C-D.3	D/C Ratio	0.36	0.13	0.54	0.05	0.07	0.48	77
	Element	18259	18399	18259	18259	18399	18399	
RXB;181;4-5;C-D.3	D/C Ratio	0.37	0.13	0.61	0.05	0.08	0.48	84
	Element	18567	18413	18567	18413	18567	18567	
RXB;181;5-6;C-D.3	D/C Ratio	0.43	0.10	0.59	0.06	0.10	0.48	84
	Element	18735	18581	18735	18735	18735	18581	
RXB;181;6-7;C-D.3	D/C Ratio	0.50	0.07	0.49	0.06	0.34	0.29	35
	Element	18811	18749	18749	18749	18811	18749	
RXB;181;1-2;A.7-C	D/C Ratio	0.63	0.08	0.49	0.04	0.36	0.27	42
	Element	18084	18160	18160	18084	18084	18160	
RXB;181;2-3;A.7-C	D/C Ratio	0.43	0.12	0.54	0.05	0.09	0.45	49
	Element	18174	18258	18258	18258	18168	18258	
RXB;181;3-4;A.7-C	D/C Ratio	0.36	0.13	0.54	0.05	0.07	0.47	77
	Element	18272	18412	18272	18272	18412	18412	

Table 3B-18: Summary of D/C Ratios for RXB Roof Slab (Continued)

		Demand/Capacity Ratios						# Elems Checked
Section		East-West Reinf.	E-W Comp. Stress	North-South Reinf.	N-S Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
RXB;181;4-5;A.7-C	D/C Ratio	0.37	0.13	0.60	0.04	0.07	0.48	84
	Element	18580	18426	18580	18426	18580	18580	
RXB;181;5-6;A.7-C	D/C Ratio	0.43	0.11	0.59	0.06	0.10	0.47	84
	Element	18748	18594	18748	18748	18748	18594	
RXB;181;6-7;A.7-C	D/C Ratio	0.50	0.08	0.49	0.06	0.34	0.29	35
	Element	18812	18762	18762	18762	18812	18762	
RXB;181;1-2;A-A.7	D/C Ratio	0.28	0.13	0.28	0.05	0.10	0.24	24
	Element	17276	17276	17968	17276	17584	17968	
RXB;181;2-3;A-A.7	D/C Ratio	0.42	0.20	0.34	0.08	0.18	0.42	28
	Element	17296	17296	17982	17296	17756	17982	
RXB;181;3-4;A-A.7	D/C Ratio	0.38	0.21	0.35	0.08	0.29	0.51	44
	Element	17306	17312	17984	17304	17778	18004	
RXB;181;4-5;A-A.7	D/C Ratio	0.39	0.20	0.41	0.06	0.26	0.49	48
	Element	17654	17340	18028	17332	17780	18006	
RXB;181;5-6;A-A.7	D/C Ratio	0.38	0.16	0.42	0.08	0.23	0.48	48
	Element	17678	17368	18050	17678	17804	18030	
RXB;181;6-7;A-A.7	D/C Ratio	0.18	0.07	0.27	0.07	0.22	0.30	20
	Element	18054	18054	18054	17680	17392	17392	

Table 3B-18a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Roof Slab

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	18084	3	5	6	-265	-40	-8	-27	-5
	18567	-9	2	2	-71	-372	9	1	-30
	18083	3	5	-8	-265	-40	8	-27	5
	18003	1	40	1	-6	-143	10	-7	30
Dynamic	18084	41	59	284	214	60	24	24	24
	18567	137	48	141	83	453	40	10	40
	18083	41	65	277	214	45	25	24	21
	18003	201	69	49	12	174	21	12	38
Hydrodynamic	18084	0	2	1	74	11	2	7	1
	18567	4	6	1	19	101	3	0	8
	18083	0	1	2	74	11	2	8	1
	18003	1	18	2	2	41	3	2	8

Table 3B-18b: Magnitudes of Bounding Final Design Forces and Moments for RXB Roof

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
18084	44	-39	65	-56	291	553	112	34	59	30
18567	132	-151	55	-52	144	174	925	52	11	78
18083	44	-39	72	-61	286	553	96	35	59	28
18003	202	-201	127	-47	52	20	358	34	20	76

Table 3B-19: Summary of D/C Ratios for Reactor Building Pilasters on Grid Line A Wall

		Demand/Capacity Ratios				
Section		Moment Axis 2	Shear Axis 3	Compression	Tension	# Elems Checked
RXB;PI;A2;24-50	D/C Ratio	0.66	0.70	0.20	0.13	4
	Element	879	2030	1320	2030	
RXB;PI;A2;50-75	D/C Ratio	0.38	0.31	0.18	0.15	4
	Element	3060	2348	2348	2348	
RXB;PI;A2;75-100	D/C Ratio	0.62	0.28	0.14	0.13	4
	Element	5147	3803	3803	5147	
RXB;PI;A2;100-126	D/C Ratio	0.60	0.42	0.08	0.16	4
	Element	5342	5431	5342	5342	
RXB;PI;A2;126-163	D/C Ratio	0.61	0.45	0.06	0.11	8
	Element	6106	6258	5668	5872	
RXB;PI;A3;24-50	D/C Ratio	0.66	0.63	0.19	0.08	4
	Element	897	2036	897	2036	
RXB;PI;A3;50-75	D/C Ratio	0.44	0.31	0.17	0.09	4
	Element	3440	2378	2378	2641	
RXB;PI;A3;75-100	D/C Ratio	0.73	0.40	0.10	0.04	4
	Element	5151	3833	3833	3833	
RXB;PI;A3;100-126	D/C Ratio	0.45	0.71	0.05	0.02	4
	Element	5344	5433	5433	5628	
RXB;PI;A3;126-163	D/C Ratio	0.68	0.53	0.05	0.03	8
	Element	5874	6260	5874	5874	
RXB;PI;A4;24-50	D/C Ratio	0.42	0.47	0.17	0.00	4
	Element	935	935	935	2039	
RXB;PI;A4;50-75	D/C Ratio	0.39	0.26	0.13	0.02	4
	Element	2679	3442	2418	3442	
RXB;PI;A4;75-100	D/C Ratio	0.58	0.49	0.09	0.02	4
	Element	4719	3911	3911	5159	
RXB;PI;A4;100-126	D/C Ratio	0.63	0.58	0.05	0.03	4
	Element	5366	5630	5366	5630	
RXB;PI;A4;126-163	D/C Ratio	0.71	0.63	0.06	0.05	8
	Element	6110	5876	5876	5876	

Table 3B-19: Summary of D/C Ratios for Reactor Building Pilasters on Grid Line A Wall (Continued)

Demand/Capacity Ratios						
Section		Moment Axis 2	Shear Axis 3	Compression	Tension	# Elems Checked
RXB;PI;A5;24-50	D/C Ratio	0.44	0.44	0.17	0.01	4
	Element	1009	1009	1009	2085	
RXB;PI;A5;50-75	D/C Ratio	0.63	0.31	0.14	0.05	4
	Element	2733	3458	2476	3458	
RXB;PI;A5;75-100	D/C Ratio	0.65	0.42	0.09	0.03	4
	Element	5169	3993	3993	5169	
RXB;PI;A5;100-126	D/C Ratio	0.53	0.36	0.06	0.05	4
	Element	5368	5441	5632	5632	
RXB;PI;A5;126-163	D/C Ratio	0.72	0.68	0.07	0.07	8
	Element	6112	5782	5878	5878	
RXB;PI;A6;24-50	D/C Ratio	0.36	0.44	0.18	0.07	4
	Element	1500	1087	1087	2144	
RXB;PI;A6;50-75	D/C Ratio	0.51	0.31	0.17	0.14	4
	Element	2797	3478	2544	3478	
RXB;PI;A6;75-100	D/C Ratio	0.52	0.27	0.14	0.17	4
	Element	4883	4077	4077	4883	
RXB;PI;A6;100-126	D/C Ratio	0.51	0.18	0.11	0.26	4
	Element	5385	5385	5385	5385	
RXB;PI;A6;126-163	D/C Ratio	0.55	0.33	0.10	0.26	8
	Element	5880	5784	5880	5880	

Table 3B-19a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Pilasters on Grid Line A Wall

Load	Element	P (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
Static	2733	-1,031	6	110	17	4,441	88
	3458	-873	12	274	7	2,495	209
	2544	-1,059	29	272	5	1,674	442
	4883	-615	16	9	25	384	107
	5169	-563	1	38	7	1,464	131
	935	-1,470	2	626	9	6,047	40
	1087	-1,355	14	520	48	2,520	74
	2144	-1,115	44	377	15	3,187	491
	5151	-500	2	52	2	2,769	112
	2030	-1,094	47	283	95	3,284	501
	1320	-1,179	19	224	145	3,681	145
	5385	-543	29	73	6	388	123
	5342	-467	51	20	19	373	335
	5431	-428	38	17	42	199	137
	5880	-283	24	129	75	4,659	306
	5366	-521	15	70	10	3,328	183
	5630	-446	9	7	48	3,250	57
	5668	-331	16	105	84	522	211
	5872	-305	23	174	53	4,670	345
	5344	-474	28	27	10	3,135	216
	5433	-489	21	53	32	3,457	100
	5628	-300	7	108	5	1,234	105
	6112	-159	13	105	26	14,043	172
	5782	-427	32	341	9	2,978	368
	5878	-335	16	506	24	12,476	358

Table 3B-19a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Pilasters on Grid Line A Wall (Continued)

Load	Element	P (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
Dynamic	2733	783	107	256	57	7,240	890
	3458	888	87	406	69	8,276	779
	2544	1,306	115	369	76	4,406	987
	4883	1,304	110	87	91	9,256	1,644
	5169	566	117	290	117	21,376	1,044
	935	773	160	403	124	8,509	1,959
	1087	1,121	241	409	81	8,464	2,569
	2144	1,240	151	369	78	3,235	1,026
	5151	560	127	266	94	33,127	1,276
	2030	1,715	290	1,107	496	9,661	1,678
	1320	1,619	367	576	155	27,784	4,367
	5385	1,687	97	284	217	8,914	1,734
	5342	1,301	100	739	356	20,935	2,452
	5431	1,216	89	885	470	13,601	1,909
	5880	1,759	161	448	318	13,879	2,168
	5366	511	137	621	90	28,577	909
	5630	544	244	1,298	315	11,127	2,703
	5668	991	115	542	525	15,787	1,272
	5872	1,004	142	482	108	25,518	2,736
	5344	542	105	1,140	160	35,645	1,104
	5433	560	113	1,418	275	24,225	1,095
	5628	463	144	1,239	100	14,935	1,491
	6112	977	217	645	165	45,609	2,817
	5782	871	326	1,940	201	19,587	2,147
	5878	1,240	192	1,548	287	42,602	4,450

Table 3B-19a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Pilasters on Grid Line A Wall (Continued)

Load	Element	P (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
Hydrodynamic	2733	287	2	4	3	79	13
	3458	248	3	7	2	47	29
	2544	300	7	1	1	30	52
	4883	170	3	1	3	56	52
	5169	158	2	1	1	95	33
	935	409	0	23	1	207	2
	1087	390	7	24	2	335	74
	2144	318	3	1	1	103	55
	5151	152	4	2	3	162	40
	2030	303	5	1	3	111	73
	1320	338	6	11	5	46	83
	5385	147	1	15	9	303	66
	5342	118	2	2	5	159	61
	5431	111	0	2	3	185	42
	5880	87	1	29	11	1,171	4
	5366	147	1	16	5	330	20
	5630	118	5	4	4	437	29
	5668	86	2	24	14	133	27
	5872	79	1	41	5	989	7
	5344	146	2	27	5	308	25
	5433	147	2	34	5	677	11
	5628	82	2	21	2	414	61
	6112	18	1	26	1	3,226	22
	5782	100	3	60	5	906	85
	5878	73	7	108	2	2,896	48

Table 3B-19b: Magnitudes of Bounding Final Design Forces and Moments for RXB Pilasters on Grid Line A Wall

Element	P MAX (k)	P MIN (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
2733	39	-2,101	115	370	77	11,760	990
3458	263	-2,009	102	687	78	10,818	1,016
2544	547	-2,665	151	642	82	6,110	1,481
4883	860	-2,089	129	96	119	9,695	1,804
5169	162	-1,288	120	329	125	22,935	1,208
935	-288	-2,653	162	1,052	134	14,763	2,001
1087	156	-2,865	262	953	131	11,319	2,717
2144	442	-2,673	198	747	94	6,525	1,573
5151	212	-1,211	133	320	99	36,059	1,427
2030	923	-3,112	342	1,392	595	13,055	2,253
1320	777	-3,135	392	811	305	31,510	4,595
5385	1,291	-2,377	128	371	232	9,605	1,922
5342	952	-1,886	152	760	381	21,467	2,848
5431	899	-1,755	128	903	515	13,985	2,088
5880	1,563	-2,128	185	606	404	19,709	2,478
5366	137	-1,180	153	706	105	32,235	1,113
5630	216	-1,108	259	1,309	366	14,814	2,789
5668	747	-1,408	133	671	623	16,442	1,510
5872	779	-1,388	166	697	165	31,177	3,089
5344	213	-1,162	135	1,194	175	39,088	1,345
5433	217	-1,196	136	1,505	313	28,359	1,206
5628	246	-845	153	1,368	107	16,583	1,657
6112	836	-1,154	231	775	191	62,879	3,011
5782	543	-1,398	361	2,341	215	23,470	2,600
5878	978	-1,648	215	2,162	313	57,974	4,856

Table 3B-20: Summary of D/C Ratios for Reactor Building Beams on EL. 75'-0" Slab

		Demand/Capacity Ratios				
Section		Moment Axis 3	Shear Axis 2	Compression	Tension	# Elems Checked
RXB;TB;75;A-B;2-2	D/C Ratio	0.36	0.23	0.21	0.14	5
	Element	3658	3657	3654	3654	
RXB;TB;75;A-B;2-3	D/C Ratio	0.20	0.10	0.06	0.06	5
	Element	3664	3668	3668	3668	
RXB;TB;75;A-B;3-3	D/C Ratio	0.33	0.30	0.08	0.12	5
	Element	3678	3674	3678	3678	
RXB;TB;75;A-B;3-4	D/C Ratio	0.39	0.51	0.05	0.06	5
	Element	3684	3684	3688	3688	
RXB;TB;75;A-B;4-4	D/C Ratio	0.35	0.58	0.14	0.13	5
	Element	3694	3694	3694	3698	
RXB;TB;75;A-B;4-5(1)	D/C Ratio	0.45	0.48	0.11	0.07	5
	Element	3704	3704	3704	3708	
RXB;TB;75;A-B;4-5(2)	D/C Ratio	0.48	0.52	0.09	0.08	5
	Element	3714	3714	3714	3718	
RXB;TB;75;A-B;5-5	D/C Ratio	0.46	0.51	0.11	0.16	5
	Element	3724	3724	3728	3728	
RXB;TB;75;A-B;5-6(1)	D/C Ratio	0.39	0.44	0.09	0.08	5
	Element	3734	3734	3734	3736	
RXB;TB;75;A-B;5-6(2)	D/C Ratio	0.40	0.48	0.08	0.06	5
	Element	3744	3744	3744	3748	
RXB;TB;75;A-B;6-6	D/C Ratio	0.38	0.58	0.18	0.21	5
	Element	3754	3754	3754	3754	
RXB;TB;75;6-7;B-C	D/C Ratio	0.38	0.22	0.07	0.06	5
	Element	3773	3773	3767	3767	
RXB;TB;75;6-7;C-C	D/C Ratio	0.50	0.26	0.06	0.04	5
	Element	3772	3772	3772	3760	
RXB;TB;75;6-7;C-D	D/C Ratio	0.41	0.22	0.07	0.05	5
	Element	3771	3771	3765	3765	
RXB;TB;75;D-E;2-2	D/C Ratio	0.26	0.14	0.20	0.11	5
	Element	3653	3653	3653	3653	

Table 3B-20: Summary of D/C Ratios for Reactor Building Beams on EL. 75'-0" Slab (Continued)

		Demand/Capacity Ratios				
Section		Moment Axis 3	Shear Axis 2	Compression	Tension	# Elems Checked
RXB;TB;75;D-E;2-3	D/C Ratio	0.29	0.18	0.16	0.16	5
	Element	3663	3659	3660	3659	
RXB;TB;75;D-E;3-3	D/C Ratio	0.70	0.55	0.10	0.18	5
	Element	3673	3673	3669	3669	
RXB;TB;75;D-E;3-4	D/C Ratio	0.41	0.54	0.06	0.07	5
	Element	3683	3683	3679	3679	
RXB;TB;75;D-E;4-4	D/C Ratio	0.37	0.59	0.14	0.13	5
	Element	3693	3693	3693	3689	
RXB;TB;75;D-E;4-5(1)	D/C Ratio	0.46	0.48	0.11	0.07	5
	Element	3703	3703	3703	3699	
RXB;TB;75;D-E;4-5(2)	D/C Ratio	0.48	0.53	0.09	0.10	5
	Element	3713	3713	3713	3711	
RXB;TB;75;D-E;5-5	D/C Ratio	0.46	0.51	0.11	0.16	5
	Element	3723	3723	3719	3719	
RXB;TB;75;D-E;5-6(1)	D/C Ratio	0.38	0.44	0.08	0.08	5
	Element	3733	3733	3733	3731	
RXB;TB;75;D-E;5-6(2)	D/C Ratio	0.40	0.48	0.08	0.06	5
	Element	3743	3743	3743	3739	
RXB;TB;75;D-E;6-6	D/C Ratio	0.28	0.59	0.18	0.21	5
	Element	3753	3753	3753	3753	
RXB;TB;75;1-2;B-C	D/C Ratio	0.16	0.10	0.04	0.05	6
	Element	3633	3633	3648	3648	
RXB;TB;75;1-2;C-C	D/C Ratio	0.22	0.18	0.09	0.15	6
	Element	3647	3647	3647	3647	
RXB;TB;75;1-2;C-D	D/C Ratio	0.19	0.09	0.03	0.05	6
	Element	3646	3646	3643	3646	

Table 3B-20a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Beams on EL. 75'-0" Slab

Load	Element	P (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
Static	3673	-56	95	2	1	10	833
	3754	-162	58	24	6	225	309
	3654	-249	9	12	0	49	98
	3693	-163	84	11	0	67	525
	3753	-161	59	24	6	229	315
Dynamic	3673	69	158	34	13	140	1,951
	3754	401	194	56	10	444	1,218
	3654	389	29	35	12	240	748
	3693	283	186	122	8	1,216	1,573
	3753	400	195	57	9	444	1,222
Hydrodynamic	3673	2	24	0	0	2	175
	3754	9	13	1	1	11	78
	3654	22	2	1	0	5	21
	3693	9	11	1	0	8	49
	3753	9	14	1	1	11	80

**Table 3B-20b: Magnitudes of Bounding Final Design Forces and Moments for RXB Beams
on EL. 75'-0" Slab**

Element	P MAX (k)	P MIN (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
3673	15	-126	278	36	14	152	2,959
3754	248	-572	266	81	16	680	1,605
3654	162	-660	40	48	13	294	867
3693	129	-454	280	134	8	1,291	2,146
3753	247	-570	267	82	16	684	1,616

Table 3B-21: Summary of D/C Ratios for Reactor Building Buttress at Grid Line 1 on EL. 126'-0" Slab

Demand/Capacity Ratios						
Section		Moment Axis 2	Shear Axis 3	Compression	Tension	# Elems Checked
RXB;B;1;126;B-A	D/C Ratio	0.35	0.17	0.08	0.30	5
	Element	5657	5658	5657	5657	
RXB;B;1;126;C-B	D/C Ratio	0.43	0.24	0.16	0.58	6
	Element	5656	5655	5652	5652	
RXB;B;1;126;D-C	D/C Ratio	0.43	0.18	0.10	0.36	6
	Element	5645	5646	5650	5650	
RXB;B;1;126;E-D	D/C Ratio	0.38	0.25	0.01	0.06	5
	Element	5644	5644	5640	5640	

Table 3B-21a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Buttress at Grid Line 1 on EL. 126'-0" Slab

Load	Element	P (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
Static	5645	84	31	29	7	196	477
	5644	96	6	37	3	397	274
	5652	167	98	16	21	789	870
Dynamic	5645	311	927	204	210	7,455	11,965
	5644	99	762	355	92	6,529	6,550
	5652	2,683	1,464	209	132	4,213	15,281
Hydrodynamic	5645	40	7	9	5	229	82
	5644	39	1	16	7	65	38
	5652	80	29	4	2	94	294

**Table 3B-21b: Magnitudes of Bounding Final Design Forces and Moments for RXB Buttress
at Grid Line 1 on EL. 126'-0" Slab**

Element	P MAX (k)	P MIN (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
5645	435	-267	966	243	221	7,880	12,524
5644	235	-42	769	409	102	6,991	6,862
5652	2,929	-2,596	1,591	228	155	5,097	16,445

Table 3B-22: Not Used

Table 3B-23: Summary of D/C Ratios for Reactor Building Pool Wall at Grid Line B

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	Elms Checked
RXB;B;1-2;24-50	D/C Ratio	0.35	0.18	0.43	0.40	0.18	0.28	20
	Element	3971	3971	2613	2634	4528	4528	
RXB;B;2-3;24-50	D/C Ratio	0.40	0.12	0.65	0.34	0.28	0.54	28
	Element	3016	4545	3016	3016	4545	4578	
RXB;B;3-4;24-50	D/C Ratio	0.57	0.07	0.55	0.22	0.97	0.58	44
	Element	4596	3046	4046	3057	4584	4596	
RXB;B;4-5;24-50	D/C Ratio	0.32	0.06	0.41	0.19	0.28	0.46	48
	Element	4116	3077	3077	4650	4650	4650	
RXB;B;5-6;24-50	D/C Ratio	0.37	0.12	0.63	0.37	0.33	0.35	48
	Element	3161	4878	3163	3163	4878	4878	
RXB;B;1-2;50-75	D/C Ratio	0.34	0.16	0.50	0.31	0.47	0.20	21
	Element	6774	6770	6130	5621	6774	6130	
RXB;B;2-3;50-75	D/C Ratio	0.41	0.12	0.52	0.25	0.40	0.54	35
	Element	5651	8010	5651	5651	8010	5651	
RXB;B;3-4;50-75	D/C Ratio	0.60	0.10	0.39	0.28	0.59	0.42	55
	Element	7294	8068	5770	5701	5701	8068	
RXB;B;4-5;50-75	D/C Ratio	0.54	0.10	0.43	0.21	0.45	0.96	60
	Element	7314	7314	5892	8080	7314	8084	
RXB;B;5-6;50-75	D/C Ratio	0.46	0.13	0.67	0.32	0.42	0.65	60
	Element	7457	6014	6014	6014	6014	6014	
RXB;B;1-2;75-100	D/C Ratio	0.41	0.11	0.37	0.23	0.34	0.32	20
	Element	11377	10434	10788	8894	11377	11377	
RXB;B;2-3;75-100	D/C Ratio	0.54	0.09	0.55	0.20	0.39	0.38	28
	Element	11536	8919	11536	8919	11536	8919	
RXB;B;3-4;75-100	D/C Ratio	0.46	0.08	0.35	0.22	0.55	0.44	44
	Element	9075	9075	9075	9075	9075	9075	
RXB;B;4-5;75-100	D/C Ratio	0.35	0.06	0.35	0.23	0.43	0.41	48
	Element	10858	9121	9214	9214	11591	9096	
RXB;B;5-6;75-100	D/C Ratio	0.44	0.13	0.59	0.26	0.39	0.54	48
	Element	9947	9354	9354	9354	9354	9354	

Table 3B-23: Summary of D/C Ratios for Reactor Building Pool Wall at Grid Line B (Continued)

		Demand/Capacity Ratios						Elems Checked
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
RXB;B;1-2;100-126	D/C Ratio	0.43	0.10	0.45	0.23	0.27	0.49	20
	Element	13171	13171	13554	13554	12337	13554	
RXB;B;2-3;100-126	D/C Ratio	0.32	0.09	0.58	0.28	0.27	0.36	28
	Element	12371	13176	12371	12371	12371	12371	
RXB;B;3-4;100-126	D/C Ratio	0.49	0.06	0.52	0.19	0.77	0.54	44
	Element	13683	12450	13683	12450	13683	12450	
RXB;B;4-5;100-126	D/C Ratio	0.40	0.05	0.37	0.20	0.63	0.51	48
	Element	13715	13747	13779	12517	13697	12469	
RXB;B;5-6;100-126	D/C Ratio	0.57	0.09	0.39	0.20	0.45	0.35	48
	Element	13875	13875	13463	12541	13793	12541	
RXB;B;1-2;126-145	D/C Ratio	0.72	0.12	0.39	0.21	0.42	0.22	24
	Element	15601	15601	14634	14634	15601	15601	
RXB;B;2-3;126-145	D/C Ratio	0.24	0.07	0.36	0.12	0.15	0.38	28
	Element	15633	15641	15649	14997	14997	14997	
RXB;B;3-4;126-145	D/C Ratio	0.32	0.05	0.53	0.23	0.58	1.00	44
	Element	15699	15683	14739	14739	14739	14739	
RXB;B;4-5;126-145	D/C Ratio	0.46	0.13	0.58	0.27	0.50	0.93	54
	Element	15401	12682	15713	14761	15738	14746	
RXB;B;5-6;126-145	D/C Ratio	0.63	0.12	0.47	0.21	0.90	0.76	51
	Element	12688	12688	15786	15094	15440	14797	
RXB;B;6-7;126-145	D/C Ratio	0.49	0.10	0.43	0.14	0.42	0.68	19
	Element	14855	14855	14855	15510	15861	15861	

Note:

Highlighted items indicate those design check zones that exceed a D/C ratio of 0.8.

Table 3B-23a: Magnitudes of Bounding Static, Dynamic, and Hydrodynamic Forces and Moments for RXB Pool Wall at Grid Line B

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	15601	39	-42	-19	45	35	-23	-1	-5
	6014	-99	-168	-28	-102	31	3	-32	26
	4584	-38	-153	-62	-96	21	-4	-66	-47
	14739	5	-92	-6	25	38	-2	6	-12
Dynamic	15601	208	141	132	285	34	54	66	36
	6014	103	290	197	115	283	28	53	89
	4584	50	102	159	233	115	18	130	65
	14739	45	227	108	190	320	65	105	153
Hydrodynamic	15601	11	12	3	13	10	6	1	1
	6014	1	41	1	0	1	1	0	0
	4584	6	49	6	0	4	1	0	1
	14739	3	38	6	5	5	0	2	9

Table 3B-23b: Magnitudes of Bounding Final Design Forces and Moments for RXB Pool Wall at Grid Line B

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
15601	257	-179	110	-194	154	343	79	83	68	42
6014	4	-202	162	-498	225	217	315	32	85	116
4584	19	-94	-2	-304	227	329	141	24	197	113
14739	54	-43	173	-356	120	221	363	68	114	174

Table 3B-24: Element Averaging of YZ Plane Shear Exceedance for Reactor Building Pool Wall at Grid Line B

Average of Shell Elements 14739/14746: Design Check					
Horizontal Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Horizontal Reinf. D/C Ratio
1.086	0.914	1.499	3.500	12.480	0.280
			Horiz. Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.09	2.77	0.033
Vertical Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Vertical Reinf. D/C Ratio
2.994	0.914	2.399	6.307	12.480	0.505
			Vertical Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.61	2.77	0.220
Shear Friction			IP Shear	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
11.394	32,400.0	OK	OK	195.0	0.503
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
9.486	32,400.0	OK		176.8	0.960

Table 3B-25: Summary of D/C Ratios for Reactor Building Pool Wall at Grid Line B After Averaging Affected Elements

		Demand/Capacity Ratios						Elems Checked
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
RXB;B;1-2;24-50	D/C Ratio	0.35	0.18	0.43	0.40	0.18	0.28	20
	Element	3971	3971	2613	2634	4528	4528	
RXB;B;2-3;24-50	D/C Ratio	0.40	0.12	0.65	0.34	0.28	0.54	28
	Element	3016	4545	3016	3016	4545	4578	
RXB;B;3-4;24-50	D/C Ratio	0.57	0.07	0.55	0.22	0.97	0.58	44
	Element	4596	3046	4046	3057	4584	4596	
RXB;B;4-5;24-50	D/C Ratio	0.32	0.06	0.41	0.19	0.28	0.46	48
	Element	4116	3077	3077	4650	4650	4650	
RXB;B;5-6;24-50	D/C Ratio	0.37	0.12	0.63	0.37	0.33	0.35	48
	Element	3161	4878	3163	3163	4878	4878	
RXB;B;1-2;50-75	D/C Ratio	0.34	0.16	0.50	0.31	0.47	0.20	21
	Element	6774	6770	6130	5621	6774	6130	
RXB;B;2-3;50-75	D/C Ratio	0.41	0.12	0.52	0.25	0.40	0.54	35
	Element	5651	8010	5651	5651	8010	5651	
RXB;B;3-4;50-75	D/C Ratio	0.60	0.10	0.39	0.28	0.59	0.42	55
	Element	7294	8068	5770	5701	5701	8068	
RXB;B;4-5;50-75	D/C Ratio	0.54	0.10	0.43	0.21	0.45	0.96	60
	Element	7314	7314	5892	8080	7314	8084	
RXB;B;5-6;50-75	D/C Ratio	0.46	0.13	0.67	0.32	0.42	0.65	60
	Element	7457	6014	6014	6014	6014	6014	
RXB;B;1-2;75-100	D/C Ratio	0.41	0.11	0.37	0.23	0.34	0.32	20
	Element	11377	10434	10788	8894	11377	11377	
RXB;B;2-3;75-100	D/C Ratio	0.54	0.09	0.55	0.20	0.39	0.38	28
	Element	11536	8919	11536	8919	11536	8919	
RXB;B;3-4;75-100	D/C Ratio	0.46	0.08	0.35	0.22	0.55	0.44	44
	Element	9075	9075	9075	9075	9075	9075	
RXB;B;4-5;75-100	D/C Ratio	0.35	0.06	0.35	0.23	0.43	0.41	48
	Element	10858	9121	9214	9214	11591	9096	

Table 3B-25: Summary of D/C Ratios for Reactor Building Pool Wall at Grid Line B After Averaging Affected Elements (Continued)

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	Elms Checked
RXB;B;5-6;75-100	D/C Ratio	0.44	0.13	0.59	0.26	0.39	0.54	48
	Element	9947	9354	9354	9354	9354	9354	
RXB;B;1-2;100-126	D/C Ratio	0.43	0.10	0.45	0.23	0.27	0.49	20
	Element	13171	13171	13554	13554	12337	13554	
RXB;B;2-3;100-126	D/C Ratio	0.32	0.09	0.58	0.28	0.27	0.36	28
	Element	12371	13176	12371	12371	12371	12371	
RXB;B;3-4;100-126	D/C Ratio	0.49	0.06	0.52	0.19	0.77	0.54	44
	Element	13683	12450	13683	12450	13683	12450	
RXB;B;4-5;100-126	D/C Ratio	0.40	0.05	0.37	0.20	0.63	0.51	48
	Element	13715	13747	13779	12517	13697	12469	
RXB;B;5-6;100-126	D/C Ratio	0.57	0.09	0.39	0.20	0.45	0.35	48
	Element	13875	13875	13463	12541	13793	12541	
RXB;B;1-2;126-145	D/C Ratio	0.72	0.12	0.39	0.21	0.42	0.22	24
	Element	15601	15601	14634	14634	15601	15601	
RXB;B;2-3;126-145	D/C Ratio	0.24	0.07	0.36	0.12	0.15	0.38	28
	Element	15633	15641	15649	14997	14997	14997	
RXB;B;3-4;126-145	D/C Ratio	0.32	0.05	0.53	0.23	0.58	0.96	44
	Element	15699	15683	14739	14739	14739	14739	
RXB;B;4-5;126-145	D/C Ratio	0.46	0.13	0.58	0.27	0.50	0.93	54
	Element	15401	12682	15713	14761	15738	14746	
RXB;B;5-6;126-145	D/C Ratio	0.63	0.12	0.47	0.21	0.90	0.76	51
	Element	12688	12688	15786	15094	15440	14797	
RXB;B;6-7;126-145	D/C Ratio	0.49	0.10	0.43	0.14	0.42	0.68	19
	Element	14855	14855	14855	15510	15861	15861	

Note: The highlighted values of the D/C ratios for the corresponding element shown in this table is based on the averaged demand values. It should be noted that the D/C ratios of all other elements shown in this table will be proportionally reduced if the same averaging methodology is used.

Table 3B-26: NuScale Power Module Lug Support Model Cut Section Forces and Moments

TABLE: Section Cut Forces - Analysis								
SectionCut	OutputCase	CaseType	F1	F2	F3	M1	M2	M3
Text	Text	Text	Lb	Lb	Lb	Lb-in	Lb-in	Lb-in
2"PL_Y=-16.25"	W-Lug-PY-	LinStatic	-55,982	-1,194,526	341	11,300	620	557,494
2"PL_Y=16.25"	W-Lug-PY-	LinStatic	5,454	884,513	756	-19,923	381	37,563
Fin_Y=00.00"	W-Lug-PY-	LinStatic	-50,509	-309,993	1,097	-1,879	1,000	-403,151
Fin_Y=-16.25"	W-Lug-PY-	LinStatic	-803,922	-375,879	1,056	-13,850	7,480	-312,109
Fin_Y=16.25"	W-Lug-PY-	LinStatic	-67,116	-154,332	1,157	10,798	10,194	-205,216
Fin_Y=-32.24"	W-Lug-PY-	LinStatic	-33,420	-468,831	691	-23,053	4,726	-540,523
Fin_Y=32.24"	W-Lug-PY-	LinStatic	37,226	-121,274	745	22,770	7,199	-154,530
Fin_Y=-48.23"	W-Lug-PY-	LinStatic	150,232	-488,802	71	-30,142	660	-584,991
Fin_Y=48.23"	W-Lug-PY-	LinStatic	53,268	-132,962	110	35,642	2,789	-165,157
Fin_Y=-64.22"	W-Lug-PY-	LinStatic	258,209	-483,067	-767	-34,319	-1,405	-576,203
Fin_Y=64.22"	W-Lug-PY-	LinStatic	52,628	-181,955	-779	50,037	-2,294	-225,438
Fin_Y=-88.20"	W-Lug-PY-	LinStatic	484,861	-488,810	-1,391	-33,526	-12,081	-594,724
Fin_Y=88.20"	W-Lug-PY-	LinStatic	-81,465	-293,957	-1,989	65,712	-18,272	-324,996
Total			-3,499,861					
2"PL_Y=-16.25"	W-Lug-PY+	LinStatic	7,442	-424,764	-279	-44,910	-433	-60,054
2"PL_Y=16.25"	W-Lug-PY+	LinStatic	-52,098	722,175	234	43,923	576	-519,329
Fin_Y=00.00"	W-Lug-PY+	LinStatic	-44,640	297,392	-45	7,337	143	388,025
Fin_Y=-16.25"	W-Lug-PY+	LinStatic	-16,757	144,367	8	7,183	433	182,939
Fin_Y=16.25"	W-Lug-PY+	LinStatic	-742,945	361,735	-145	6,587	682	305,731
Fin_Y=-32.24"	W-Lug-PY+	LinStatic	8,663	92,366	231	6,948	-64	115,492
Fin_Y=32.24"	W-Lug-PY+	LinStatic	-65,131	477,854	-7	3,244	-1,629	555,769
Fin_Y=-48.23"	W-Lug-PY+	LinStatic	11,264	70,026	301	7,001	346	86,663
Fin_Y=48.23"	W-Lug-PY+	LinStatic	98,943	540,322	104	-2,716	-2,074	649,873
Fin_Y=-64.22"	W-Lug-PY+	LinStatic	8,318	62,330	222	7,076	-590	76,984
Fin_Y=64.22"	W-Lug-PY+	LinStatic	198,163	608,247	242	-11,824	-424	732,111
Fin_Y=-88.20"	W-Lug-PY+	LinStatic	-18,932	55,657	-483	5,903	307	62,272
Fin_Y=88.20"	W-Lug-PY+	LinStatic	563,052	789,567	-427	-23,311	2,871	924,761
Total			3,499,864					

Table 3B-27: Not Used

**Table 3B-28: Enveloped NPM Lug Support and Skirt Support Reaction Forces
Using Soil Type 7 (CSDRS) and Design Capacities (x10³ kips)**

Enveloped Input Case	SRSS Horizontal Skirt Reaction	Vertical Skirt Reaction *	East Wing Wall N-S Lug Reaction	Pool Wall E-W Lug Reaction	West Wing Wall N-S Lug Reaction	Skirt Support Plate Capacity	Lug Assembly Capacity
NPM Seismic Analysis	1.33	1.77	1.93	1.98	1.68	2.32	4.50
SASSI Building Seismic Analysis	0.72	1.625	1.38	1.54	1.33		
*Vertical skirt reactions are not resisted by the support plates, the NPM is free to move vertically							

Table 3B-29: Summary of D/C Ratios for Control Building Wall at Grid Line 3

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
CRB;3;B-A;50-76	D/C Ratio	0.39	0.06	0.37	0.17	0.38	0.43	15
	Element	714	927	716	714	1487	1488	
CRB;3;B-A;76-100	D/C Ratio	0.43	0.07	0.46	0.10	0.30	0.43	15
	Element	2178	2178	2029	2029	2030	2482	
CRB;3;B-A;100-120	D/C Ratio	0.34	0.06	0.43	0.11	0.22	0.70	11
	Element	3131	3275	2994	3276	3276	3276	
CRB;3;B-A;120-141	D/C Ratio	0.27	0.06	0.38	0.07	0.34	0.94	6
	Element	3712	3712	3712	3777	3712	3712	
CRB;3;C-B;50-76	D/C Ratio	0.60	0.09	0.41	0.17	0.26	0.36	29
	Element	709	709	711	710	1479	1479	
CRB;3;C-B;76-100	D/C Ratio	0.49	0.07	0.55	0.20	0.13	0.49	28
	Element	2028	2176	2028	2026	2175	2026	
CRB;3;C-B;100-120	D/C Ratio	0.38	0.06	0.51	0.13	0.16	0.61	22
	Element	2993	3127	2993	2993	3268	2993	
CRB;3;D-C;50-76	D/C Ratio	0.52	0.07	0.42	0.14	0.28	0.33	7
	Element	708	916	708	708	1476	1476	
CRB;3;D-C;76-100	D/C Ratio	0.42	0.08	0.35	0.10	0.20	0.33	7
	Element	2169	2169	2024	2024	2471	2024	
CRB;3;D-C;100-120	D/C Ratio	0.21	0.03	0.21	0.06	0.28	0.25	5
	Element	3121	3121	2987	2987	3264	2987	
CRB;3;E-D;50-76	D/C Ratio	0.52	0.09	0.47	0.16	0.22	0.34	18
	Element	706	706	705	705	1471	1472	
CRB;3;E-D;76-100	D/C Ratio	0.33	0.06	0.37	0.08	0.15	0.31	20
	Element	2022	2167	2022	2021	2318	2023	
CRB;3;E-D;100-120	D/C Ratio	0.13	0.04	0.13	0.05	0.15	0.18	14
	Element	3120	3120	2986	3259	3263	3263	

Table 3B-29a: Magnitudes of Bounding Static and Dynamic Forces and Moments for CRB Wall at Grid Line 3

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	709	-8	-49	9	1	1	-1	0	-1
	1487	-20	-24	-9	0	-1	-1	5	2
	2028	-16	-55	-24	-1	-7	-1	0	-1
	3712	1	0	-4	-4	-16	2	-2	-5
Dynamic	709	52	48	90	3	1	1	1	1
	1487	16	29	46	3	8	1	5	4
	2028	10	47	91	3	17	3	1	5
	3712	39	47	36	5	18	4	5	12

Table 3B-29b: Magnitudes of Bounding Final Design Forces and Moments for CRB Wall at Grid Line 3

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
709	44	-60	-1	-98	99	3	3	2	2	2
1487	-4	-36	5	-53	55	4	9	1	10	7
2028	-6	-26	-8	-102	115	4	24	4	1	7
3712	40	-38	47	-48	39	9	34	5	6	17

Table 3B-30: Summary of D/C Ratios for Control Building Wall at Grid Line 4

		Demand/Capacity Ratios						# Elems Checked
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
CRB;4;B-A;50-76	D/C Ratio	0.63	0.11	0.78	0.21	0.55	1.16	24
	Element	790	793	789	789	793	788	
CRB;4;B-A;76-100	D/C Ratio	0.28	0.06	0.22	0.13	0.42	0.34	24
	Element	2233	2082	2382	2082	2082	2077	
CRB;4;B-A;100-120	D/C Ratio	0.20	0.05	0.28	0.10	0.34	0.32	17
	Element	3328	3327	3043	3043	3185	3043	
CRB;4;B-A;120-140	D/C Ratio	0.18	0.05	0.18	0.07	0.20	0.15	8
	Element	3937	3937	3750	3750	3937	3749	
CRB;4;C-B;50-76	D/C Ratio	0.48	0.09	0.77	0.24	0.40	1.38	32
	Element	781	781	786	786	999	786	
CRB;4;C-B;76-100	D/C Ratio	0.22	0.03	0.29	0.08	0.16	0.35	32
	Element	2524	2076	2221	2221	2372	2528	
CRB;4;C-B;100-120	D/C Ratio	0.18	0.04	0.13	0.03	0.17	0.20	23
	Element	3324	3324	3032	3032	3173	3038	
CRB;4;D-C;50-76	D/C Ratio	0.33	0.06	0.43	0.15	0.36	0.65	8
	Element	779	778	778	778	778	779	
CRB;4;D-C;76-100	D/C Ratio	0.20	0.03	0.17	0.09	0.25	0.19	8
	Element	2218	2068	2067	2067	2218	2523	
CRB;4;D-C;100-120	D/C Ratio	0.12	0.02	0.14	0.04	0.18	0.34	5
	Element	3172	3172	3031	3031	3315	3031	
CRB;4;E-D;50-76	D/C Ratio	0.58	0.09	0.53	0.22	0.49	0.59	28
	Element	777	777	775	775	1341	774	
CRB;4;E-D;76-100	D/C Ratio	0.30	0.06	0.24	0.12	0.46	0.27	28
	Element	2211	2060	2367	2060	2060	2064	
CRB;4;E-D;100-120	D/C Ratio	0.25	0.05	0.23	0.09	0.43	0.28	20
	Element	3310	3309	3025	3025	3165	3030	
CRB;4;E-D;120-140	D/C Ratio	0.26	0.06	0.18	0.06	0.25	0.14	8
	Element	3740	3928	3740	3739	3928	3740	

Note: Highlighted items indicate those design check zones that exceed a D/C ratio of 0.8.

Table 3B-30a: Magnitudes of Bounding Static and Dynamic Forces and Moments for CRB Wall at Grid Line 4

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	790	-19	-64	-14	20	-15	11	1	-27
	789	-17	-62	-12	18	-15	-11	1	-27
	793	-18	-68	-20	-32	-4	-3	15	-4
	786	-13	-51	-5	11	-5	2	2	-16
	3740	1	-7	-5	-2	2	0	-2	1
	3043	5	-13	26	-42	-9	4	7	-2
	3165	5	-8	-25	-5	1	3	-7	1
	3031	-1	-8	-2	-3	-7	2	2	-1
Dyanmic	790	78	103	137	21	54	8	30	28
	789	52	156	125	53	97	7	26	50
	793	96	101	61	17	32	7	24	36
	786	68	190	112	19	71	6	9	67
	3740	56	42	59	11	7	4	4	4
	3043	16	91	26	25	6	4	4	5
	3165	21	28	18	10	5	3	7	1
	3031	11	33	56	6	8	3	2	10

Table 3B-30b: Magnitudes of Bounding Final Design Forces and Moments for CRB Wall at Grid Line 4

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
790	59	-97	39	-167	151	41	68	19	30	55
789	35	-70	93	-218	137	71	112	18	27	77
793	78	-114	33	-169	80	49	36	9	39	41
786	55	-81	138	-241	117	30	76	8	11	84
3740	57	-54	35	-49	64	14	8	4	6	4
3043	20	-11	78	-103	52	68	15	8	11	8
3165	26	-16	19	-36	43	15	6	6	14	2
3031	10	-12	25	-40	58	9	15	4	4	11

Table 3B-31: Control Building Wall at Grid Line 4 - Shell Element 786 with added Shear Reinforcement

Shell Element 786 in Section [CRB;4;C-B;50-76]: Design Check					
Horizontal Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Horizontal Reinf. D/C Ratio
1.016	1.581	0.310	2.908	6.240	0.466
			Horiz. Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.21	2.63	0.080
Vertical Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	Vertical Reinf. D/C Ratio
2.559	1.581	0.694	4.835	6.240	0.775
			Vertical Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.62	2.63	0.236
Shear Friction			Code Check	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
5.224	19,589.8	OK	OK	122.1	0.086
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
3.681	13,802.6	OK		108.0	0.775

Table 3B-32: Summary of D/C Ratios for Control Building Wall at Grid Line 4 After Averaging Affected Elements

		Demand/Capacity Ratios						# Elms Checked
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
CRB;4;B-A;50-76	D/C Ratio	0.63	0.11	0.78	0.21	0.55	0.78	24
	Element	790	793	789	789	793	788	
CRB;4;B-A;76-100	D/C Ratio	0.28	0.06	0.22	0.13	0.42	0.34	24
	Element	2233	2082	2382	2082	2082	2077	
CRB;4;B-A;100-120	D/C Ratio	0.20	0.05	0.28	0.10	0.34	0.32	17
	Element	3328	3327	3043	3043	3185	3043	
CRB;4;B-A;120-140	D/C Ratio	0.18	0.05	0.18	0.07	0.20	0.15	8
	Element	3937	3937	3750	3750	3937	3749	
CRB;4;C-B;50-76	D/C Ratio	0.48	0.09	0.77	0.24	0.40	0.78	32
	Element	781	781	786	786	999	786	
CRB;4;C-B;76-100	D/C Ratio	0.22	0.03	0.29	0.08	0.16	0.35	32
	Element	2524	2076	2221	2221	2372	2528	
CRB;4;C-B;100-120	D/C Ratio	0.18	0.04	0.13	0.03	0.17	0.20	23
	Element	3324	3324	3032	3032	3173	3038	
CRB;4;D-C;50-76	D/C Ratio	0.33	0.06	0.43	0.15	0.36	0.65	8
	Element	779	778	778	778	778	779	
CRB;4;D-C;76-100	D/C Ratio	0.20	0.03	0.17	0.09	0.25	0.19	8
	Element	2218	2068	2067	2067	2218	2523	
CRB;4;D-C;100-120	D/C Ratio	0.12	0.02	0.14	0.04	0.18	0.34	5
	Element	3172	3172	3031	3031	3315	3031	
CRB;4;E-D;50-76	D/C Ratio	0.58	0.09	0.53	0.22	0.49	0.59	28
	Element	777	777	775	775	1341	774	
CRB;4;E-D;76-100	D/C Ratio	0.30	0.06	0.24	0.12	0.46	0.27	28
	Element	2211	2060	2367	2060	2060	2064	
CRB;4;E-D;100-120	D/C Ratio	0.25	0.05	0.23	0.09	0.43	0.28	20
	Element	3310	3309	3025	3025	3165	3030	

Table 3B-32: Summary of D/C Ratios for Control Building Wall at Grid Line 4 After Averaging Affected Elements (Continued)

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
CRB;4;E-D;120-140	D/C Ratio	0.26	0.06	0.18	0.06	0.25	0.14	8
	Element	3740	3928	3740	3739	3928	3740	

Note:
The highlighted values of the D/C ratios for the corresponding element shown in this table are based on the averaged demand values. It should be noted that the D/C ratios of the other elements shown in this table will be proportionally reduced if the same averaging methodology is used.

Table 3B-33: Summary of D/C Ratios for Control Building Wall at Grid Line A

Demand/Capacity Ratios								
Section		Horizontal Reinf.	Horiz. Comp. Stress	Vertical Reinf.	Vert. Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	# Elems Checked
CRB;A;1-2;50-63	D/C Ratio	0.90	0.11	0.89	0.22	0.67	0.95	16
	Element	643	635	639	647	635	639	
CRB;A;2-2.8;50-63	D/C Ratio	0.52	0.09	0.39	0.16	0.46	0.43	6
	Element	692	692	692	903	698	692	
CRB;A;2.8-4;50-63	D/C Ratio	0.54	0.09	0.47	0.21	0.54	0.84	12
	Element	770	770	770	770	982	770	
CRB;A;1-2;63-76	D/C Ratio	0.56	0.07	0.56	0.16	0.54	0.62	16
	Element	1220	1200	1212	1200	1200	1416	
CRB;A;2-2.8;63-76	D/C Ratio	0.43	0.06	0.32	0.15	0.50	0.25	6
	Element	1258	1241	1251	1258	1461	1444	
CRB;A;2.8-4;63-76	D/C Ratio	0.34	0.05	0.24	0.15	0.76	0.12	12
	Element	1469	1340	1296	1266	1469	1521	
CRB;A;1-2;76-100	D/C Ratio	0.41	0.05	0.39	0.13	0.40	0.51	32
	Element	2122	1990	1990	1978	2273	1987	
CRB;A;2-2.8;76-100	D/C Ratio	0.37	0.04	0.21	0.11	0.48	0.29	12
	Element	2306	2002	2005	2002	2011	2002	
CRB;A;2.8-4;76-100	D/C Ratio	0.28	0.05	0.20	0.13	0.71	0.16	24
	Element	2049	2018	2514	2059	2018	2502	
CRB;A;1-2;100-120	D/C Ratio	0.23	0.02	0.16	0.05	0.18	0.19	24
	Element	3230	2955	2937	2937	3233	3230	
CRB;A;2-2.8;100-120	D/C Ratio	0.33	0.04	0.31	0.06	0.36	0.15	9
	Element	3251	3251	3251	3251	2975	2961	
CRB;A;2.8-4;100-120	D/C Ratio	0.20	0.04	0.25	0.08	0.78	0.41	18
	Element	2982	3283	3024	3024	2982	3014	
CRB;A;2.8-4;120-140	D/C Ratio	0.26	0.06	0.23	0.08	0.46	0.28	24
	Element	3906	3711	3711	3711	3906	3711	

Table 3B-33a: Magnitudes of Bounding Static and Dynamic Forces and Moments for CRB Wall at Grid Line A

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	643	-1	-86	91	-19	21	11	-2	31
	639	-13	-60	89	-14	15	27	-2	25
	1469	-20	-73	21	81	5	-7	45	-3
	3251	7	-6	9	-9	-11	-6	2	1
	2982	2	-15	-12	-36	-14	-13	16	2
	3014	3	-16	4	50	-18	5	-1	8
Dynamic	643	111	125	98	12	35	8	19	25
	639	70	151	86	32	69	11	7	41
	1469	30	54	64	34	6	7	17	2
	3251	47	55	72	16	7	6	5	2
	2982	28	37	34	25	6	8	9	2
	3014	13	46	28	32	15	4	1	5

Table 3B-33b: Magnitudes of Bounding Final Design Forces and Moments for CRB Wall at Grid Line A

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
643	111	-112	39	-211	188	31	56	19	20	55
639	58	-83	91	-211	175	47	84	39	9	65
1469	10	-50	-19	-127	85	114	11	14	62	5
3251	54	-39	48	-61	81	24	17	13	7	2
2982	30	-27	22	-52	47	61	20	22	25	5
3014	16	-9	30	-63	32	82	33	9	2	13

Table 3B-34: Element Averaging of IP Shear Exceedance of Control Building Wall at Grid Line A

Element		Length (in)	Thickness (in)	Shell Sxy (kip/in)	IP Shear Demand (kip)	f'_c (psi)	IP Shear Capacity $\phi_v 8A_{cv}\sqrt{f'_c}$ (kip)
Shell	635	64.33	36	12.83	825.1	5000	982.5
Shell	639	64.33	36	14.59	938.4	5000	982.5
Shell	643	64.33	36	15.69	1009.6	5000	982.5
Shell	647	58.33	36	15.35	895.6	5000	890.9
Shell	651	58.33	36	15.81	922.1	5000	890.9
Shell	655	58.33	36	12.46	726.6	5000	890.9
				Sum =	5317.4	<	5620.3

Table 3B-35: Moment and Shear Capacity: 5 Foot Thick Control Building Basemat Foundation (Type 1)

Description	Parameters	Value
Information	-	5'-0" Basemat; 3 Layers EWEF (#11 @ 12" c/c); 2-Leg Stirrups (#6 @ 12" c/c)
Section thickness	h (in)	60
Concrete cover dimension	c (in)	3
Rebar diameter	d_t (in)	1.41
Stirrup diameter	d_s (in)	0.75
Rebar area	$A_{st(t)}$ (in ²)	1.560
Stirrup area	$A_{st(s)}$ (in ²)	0.44
Effective depth	d (in)	51.32
Lever arm	jd (in)	48.57
Out-of-Plane Moment Capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1,023
Shear Capacity provided by Concrete $\phi V_c = \phi_v 2bdv(f_c')$	$\phi_v V_c$ (kip/ft)	65
Shear Capacity provided by Stirrups $\phi V_s = \phi_v ((A_{st(s)} f_y d) / s_s)$	$\phi_v V_s$ (kip/ft)	169
In-Plane Shear Capacity by Concrete $\phi V_{conc} = \phi A_{cv} (\alpha_c \sqrt{f_c'})$	$\phi_v V_{conc}$ (kip/ft)	76
In-Plane Shear Capacity $\phi V_{in-plane} = \text{Minimum of}$ $\phi A_{cv} (\alpha_c \sqrt{f_c'} + \rho_t f_y)$ or $\phi_v 8A_{cv} \sqrt{f_c'}$	$\phi_v V_{in-plane}$ (kip/ft)	305

Table 3B-36: Moment and Shear Capacity: 5 Foot Thick Control Building Basemat Foundation (Type 2)

Description	Parameters	Value
Information	-	5'-0" Basemat; 4 Layers EWEF (#11 @ 12" c/c); 2-Leg Stirrups (#6 @ 12" c/c)
Section thickness	h (in)	60
Concrete cover dimension	c (in)	3
Rebar diameter	d_t (in)	1.41
Stirrup diameter	d_s (in)	0.75
Rebar area	$A_{st(t)}$ (in ²)	1.560
Stirrup area	$A_{st(s)}$ (in ²)	0.44
Effective depth	d (in)	49.91
Lever arm	jd (in)	46.24
Out-of-Plane Moment Capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1298
Shear Capacity provided by Concrete $\phi V_c = \phi_v 2bdv(f_c')$	$\phi_v V_c$ (kip/ft)	64
Shear Capacity provided by Stirrups $\phi V_s = \phi_v ((A_{st(s)} f_y d) / s_s)$	$\phi_v V_s$ (kip/ft)	165
In-Plane Shear Capacity by Concrete $\phi V_{conc} = \phi A_{cv} (\alpha_c \sqrt{f_c'})$	$\phi v V_{conc}$ (kip/ft)	76
In-Plane Shear Capacity $\phi V_{in-plane} = \text{Minimum of}$ $\phi A_{cv} (\alpha_c \sqrt{f_c'} + \rho_t f_y)$ or $\phi_v 8A_{cv} \sqrt{f_c'}$	$\phi_v V_{in-plane}$ (kip/ft)	305

Table 3B-37a: Magnitudes of Bounding Static and Dynamic Forces and Moments for Perimeter of CRB Basemat Slab

Load		FX(Sxx) k/ft	FY(Syy) k/ft	Sxy k/ft	Vxz k/ft	Vyz k/ft	MX(Myy) k-ft/ft	MY(Mxx) k-ft/ft
Static	Maximum	271	93	64	86	82	304	230
	Elm. No.	7	300	391	20	300	92	387
Dynamic	Maximum	353	292	211	103	99	355	525
	Elm. No.	390	369	1	1	376	391	23

Table 3B-37b: Magnitudes of Bounding Final Design Forces and Moments for Perimeter of Main Control Building Basemat Slab

	FX(S_{xx})	FY(S_{yy})	S_{xy}	V_{xz}	V_{yz}	MX(M_{yy})	MY(M_{xx})
	k/ft	k/ft	k/ft	k/ft	k/ft	k-ft/ft	k-ft/ft
Maximum	312	291	216	143	125	406	593
Elm. No.	386	375	373	373	345	69	386

Note:

The shear forces and bending moments are obtained by the absolute sum of the static and seismic results

Table 3B-38a: Magnitudes of Bounding Static and Dynamic Forces and Moments for Interior of CRB Basemat Slab

Load		FX(Sxx) k/ft	FY(Syy) k/ft	Sxy k/ft	Vxz k/ft	Vyz k/ft	MX(Myy) k-ft/ft	MY(Mxx) k-ft/ft
Static	Maximum	123	48	40	49	41	192	191
	Elm. No.	30	251	60	61	129	129	60
Dynamic	Maximum	145	98	71	26	32	135	142
	Elm. No.	32	350	352	44	287	45	45

Table 3B-38b: Magnitudes of Bounding Final Design Forces and Moments for Interior of Main Control Building Basemat Slab

	FX(Sxx)	FY(Syy)	Sxy	Vxz	Vyz	MX(Myy)	MY(Mxx)
	k/ft	k/ft	k/ft	k/ft	k/ft	k-ft/ft	k-ft/ft
Maximum	309	228	135	114	83	302	326
Elm. No.	45	347	25	45	45	99	45

Note:

The shear forces and bending moments are obtained by the absolute sum of the static and seismic results.

Table 3B-39a: Magnitudes of Bounding Static and Dynamic Forces and Moments for Basemat of CRB Tunnel

Load		FX(Sxx)† k/ft	FY(Syy)† k/ft	Sxy k/ft	Vxz k/ft	Vyz k/ft	MX(My)† k-ft/ft	MY(Mxx)† k-ft/ft
Static	Maximum	-	-	78	105	103	339	398
	Elm. No.	-	-	400	516	485	488	486
Dynamic	Maximum	-	-	206	248	140	357	357
	Elm. No.	-	-	547	550	548	397	397

†Forces are not calculated since the west end of the tunnel is separated from the RXB by a nominal 6 inch gap.

**Table 3B-39b: Magnitudes of Bounding Final Design Forces and Moments
for Control Building Basemat of Control Building Tunnel**

	$FX(S_{xx})^{\dagger}$	$FY(S_{yy})^{\dagger}$	S_{xy}	V_{xz}	V_{yz}	$MX(M_{yy})$	$MY(M_{xx})$
	k/ft	k/ft	k/ft	k/ft	k/ft	k-ft/ft	k-ft/ft
Maximum	-	-	230	196	212	732	793
Elm. No.	-	-	547	516	485	488	486

[†] Forces are not calculated since the west end of the tunnel is separated from the RXB by a nominal 6 inch gap

Table 3B-40: Design Check Control Building Basemat Foundation of Perimeter of the Main Slab

Basemat Foundation for CRB Perimeter: Design Check					
East-West Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	East-West Reinf. D/C Ratio
5.772	3.107	2.848	11.727	12.480	0.940
North-South Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	North-South Reinf. D/C Ratio
5.393	3.107	1.952	10.452	12.480	0.838
Shear Friction			Code Check	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
6.708	25,154.2	OK	OK	173.2	0.826
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
7.087	26,577.8	OK		176.8	0.704

Table 3B-41: Design Check Control Building Basemat Foundation of Interior of the Main Slab

Basemat Foundation for CRB Interior: Design Check					
East-West Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	East-West Reinf. D/C Ratio
5.713	1.292	1.491	8.496	9.360	0.908
North-South Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	North-South Reinf. D/C Ratio
4.215	1.292	1.382	6.889	9.360	0.736
Shear Friction			Code Check	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
3.647	13,676.4	OK	OK	178.7	0.637
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
5.145	19,294.4	OK		193.4	0.431

Table 3B-42: Design Check for Control Building Basemat Foundation for the Control Building Tunnel

Basemat Foundation for CRB Tunnel: Design Check					
East-West Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	East-West Reinf. D/C Ratio
0.000	3.410	3.629	7.039	9.360	0.752
North-South Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	North-South Reinf. D/C Ratio
0.000	3.410	3.347	6.756	9.360	0.722
Shear Friction			Code Check	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
9.360	35,100.0	OK	OK	234.7	0.835
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
9.360	35,100.0	OK		234.7	0.905

Table 3B-43: Summary of D/C Ratios for Control Building Slab at EL. 100'-0"

		Demand/Capacity Ratios						# Elems Checked
Section		East-West Reinf.	E-W Comp. Stress	North-South Reinf.	N-S Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
CRB;100;7-1;D-E	D/C Ratio	0.82	0.19	0.84	0.14	0.51	1.13	10
	Element	2543	2539	2538	2538	2539	2538	
CRB;100;1-2;D-E	D/C Ratio	0.96	0.17	0.38	0.03	0.80	0.50	55
	Element	2562	2562	2561	2718	2562	2649	
CRB;100;2-3;D-E	D/C Ratio	0.33	0.05	0.27	0.06	0.51	0.38	22
	Element	2742	2764	2764	2764	2764	2747	
CRB;100;3-4;D-E	D/C Ratio	0.17	0.03	0.09	0.02	0.53	0.30	25
	Element	2895	2824	2893	2827	2897	2827	
CRB;100;7-1;C-D	D/C Ratio	0.84	0.21	0.62	0.10	0.56	0.95	10
	Element	2540	2557	2541	2541	2540	2541	
CRB;100;1-2;C-D	D/C Ratio	1.00	0.16	0.30	0.03	1.01	0.48	16
	Element	2565	2565	2610	2564	2565	2679	
CRB;100;2-3;C-D	D/C Ratio	0.20	0.03	0.30	0.03	0.37	0.39	8
	Element	2749	2749	2748	2748	2789	2809	
CRB;100;3-4;C-D	D/C Ratio	0.15	0.04	0.12	0.02	0.52	0.44	10
	Element	2829	2899	2899	2899	2898	2899	
CRB;100;1-2;B-C	D/C Ratio	1.09	0.13	0.53	0.04	0.84	0.32	64
	Element	2566	2566	2566	2567	2573	2566	
CRB;100;2-3;B-C	D/C Ratio	0.25	0.03	0.19	0.03	0.66	0.35	32
	Element	2812	2750	2817	2816	2817	2816	
CRB;100;3-4;B-C	D/C Ratio	0.26	0.06	0.15	0.03	0.50	0.44	40
	Element	2837	2907	2900	2834	2835	2900	
CRB;100;1-2;A-B	D/C Ratio	0.47	0.03	0.38	0.03	0.83	0.47	48
	Element	2574	2574	2671	2740	2574	2694	
CRB;100;2-3;A-B	D/C Ratio	0.40	0.03	0.35	0.06	0.60	0.48	20
	Element	2822	2822	2763	2802	2822	2763	
CRB;100;3-4;A-B	D/C Ratio	0.28	0.06	0.18	0.03	0.58	0.35	14
	Element	2838	2908	2891	2890	2839	2838	

Note: Highlighted items indicate those design check zones that exceed a D/C ratio of 0.8.

Table 3B-43a: Magnitudes of Bounding Static and Dynamic Forces and Moments for CRB Slab at EL. 100'-0"

Load	Element	Sxx (k/ft)	Syy (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static	2540	-1	-10	2	-4	-27	3	0	1
	2538	-2	-11	-8	-6	-50	-8	1	-5
	2540	-1	-10	2	-4	-27	3	0	1
	2566	-8	-2	7	-29	-11	-8	-7	2
	2565	-8	-2	11	-15	-6	-6	-5	1
	2649	1	-6	4	-12	-50	-1	0	-9
	2838	-6	-3	6	-23	-5	-3	-5	1
	2891	-3	5	-14	2	-1	-1	1	1
	2900	-10	-1	12	-11	-2	-1	4	0
Dynamic	2540	216	75	74	36	118	29	27	25
	2538	114	127	104	42	84	58	10	70
	2540	216	75	74	36	118	29	27	25
	2566	121	33	72	36	18	14	9	10
	2565	155	27	32	26	15	12	8	9
	2649	17	22	21	6	32	5	3	10
	2838	25	13	17	18	4	6	4	8
	2891	20	19	16	8	5	3	4	6
	2900	21	16	23	11	3	4	3	10

Table 3B-43b: Magnitudes of Bounding Final Design Forces and Moments for CRB Slab at EL. 100'-0"

Element	Sxx MAX (k/ft)	Sxx MIN (k/ft)	Syy MAX (k/ft)	Syy MIN (k/ft)	Sxy (k/ft)	Mxx (k-ft/ft)	Myy (k-ft/ft)	Mxy (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
2540	216	-217	65	-85	76	40	145	33	28	26
2538	113	-116	117	-138	112	48	134	65	12	75
2540	216	-217	65	-85	76	40	145	33	28	26
2566	113	-128	32	-35	78	64	29	22	16	11
2565	147	-163	25	-29	43	41	21	18	14	10
2649	18	-17	16	-27	25	18	82	6	3	19
2838	19	-31	10	-16	22	41	9	9	9	9
2891	17	-23	24	-13	30	10	6	4	5	7
2900	12	-31	15	-16	35	23	5	5	7	11

Table 3B-44: Element Averaging of East-West Reinforcement Exceedance - Control Building Slab at EL. 100'-0"

Average of Shell Elements 2566/2567: Design Check					
East-West Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	East-West Reinf. D/C Ratio
1.337	0.645	0.636	2.618	3.120	0.839
			E-W Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.21	2.42	0.087
North-South Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	North-South Reinf. D/C Ratio
0.602	0.645	0.302	1.549	3.120	0.496
			N-S Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.09	2.42	0.036
Shear Friction			Code Check	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
1.783	6,686.1	OK	OK	28.1	0.540
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
2.518	9,442.8	OK		35.8	0.277

Table 3B-45: Element Averaging of XZ Plane Shear Exceedance - Control Building Slab at EL. 100'-0"

Average of Shell Elements 2565/2564: Design Check					
East-West Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	East-West Reinf. D/C Ratio
2.392	0.058	0.300	2.750	3.120	0.881
			E-W Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.35	2.42	0.145
North-South Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	North-South Reinf. D/C Ratio
0.446	0.058	0.227	0.731	3.120	0.234
			N-S Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.07	2.42	0.030
Shear Friction			Code Check	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
0.728	2,730.2	Performing Averaging†	OK	17.0	0.727
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
2.674	10,028.2	OK		37.5	0.248

Note:

† See text in Section 3B.3.3.2 and Table 3B-48.

Table 3B-46: Element Averaging of YZ Plane Shear Exceedance - Control Building Slab at EL. 100'-0"

Average of Shell Elements 2538/2542: Design Check					
East-West Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	East-West Reinf. D/C Ratio
2.148	1.538	0.865	4.551	6.240	0.729
			E-W Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.31	2.63	0.117
North-South Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	North-South Reinf. D/C Ratio
1.275	1.538	1.313	4.126	6.240	0.661
			N-S Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.21	2.63	0.081
Shear Friction			Code Check	OOP Shear	
XZ-Plane Shear-Friction A_{vfX} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfX} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
4.092	15,343.3	OK	OK	66.6	0.187
YZ-Plane Shear-Friction A_{vfY} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfY} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
4.965	18,618.4	OK		74.8	0.601

Table 3B-47: Summary of D/C Ratios for Control Building Slab at EL. 100'-0" After Averaging Affected Elements

		Demand/Capacity Ratios						# Elems Checked
Section		East-West Reinf.	E-W Comp. Stress	North-South Reinf.	N-S Comp. Stress	XZ-Plane Shear	YZ-Plane Shear	
CRB;100;7-1;D-E	D/C Ratio	0.82	0.19	0.84	0.14	0.51	0.60	10
	Element	2543	2539	2538	2538	2539	2538	
CRB;100;1-2;D-E	D/C Ratio	0.96	0.17	0.38	0.03	0.80	0.50	55
	Element	2562	2562	2561	2718	2562	2649	
CRB;100;2-3;D-E	D/C Ratio	0.33	0.05	0.27	0.06	0.51	0.38	22
	Element	2742	2764	2764	2764	2764	2747	
CRB;100;3-4;D-E	D/C Ratio	0.17	0.03	0.09	0.02	0.53	0.30	25
	Element	2895	2824	2893	2827	2897	2827	
CRB;100;7-1;C-D	D/C Ratio	0.84	0.21	0.62	0.10	0.56	0.95	10
	Element	2540	2557	2541	2541	2540	2541	
CRB;100;1-2;C-D	D/C Ratio	0.84	0.16	0.30	0.03	0.73	0.48	16
	Element	2565	2565	2610	2564	2565	2679	
CRB;100;2-3;C-D	D/C Ratio	0.20	0.03	0.30	0.03	0.37	0.39	8
	Element	2749	2749	2748	2748	2789	2809	
CRB;100;3-4;C-D	D/C Ratio	0.15	0.04	0.12	0.02	0.52	0.44	10
	Element	2829	2899	2899	2899	2898	2899	
CRB;100;1-2;B-C	D/C Ratio	0.84	0.13	0.53	0.04	0.84	0.32	64
	Element	2566	2566	2566	2567	2573	2566	
CRB;100;2-3;B-C	D/C Ratio	0.25	0.03	0.19	0.03	0.66	0.35	32
	Element	2812	2750	2817	2816	2817	2816	
CRB;100;3-4;B-C	D/C Ratio	0.26	0.06	0.15	0.03	0.50	0.44	40
	Element	2837	2907	2900	2834	2835	2900	
CRB;100;1-2;A-B	D/C Ratio	0.47	0.03	0.38	0.03	0.83	0.47	48
	Element	2574	2574	2671	2740	2574	2694	
CRB;100;2-3;A-B	D/C Ratio	0.40	0.03	0.35	0.06	0.60	0.48	20
	Element	2822	2822	2763	2802	2822	2763	
CRB;100;3-4;A-B	D/C Ratio	0.28	0.06	0.18	0.03	0.58	0.35	14
	Element	2838	2908	2891	2890	2839	2838	

Note: The highlighted values of the D-C ratios for the corresponding element shown in this Table is based on the averaged demand values using methodology shown in Section 3B.1.1.1. It should be noted that the D-C ratios of all other elements shown in this Table will be proportionally reduced if the same averaging methodology is used.

Table 3B-48: Element Averaging of Shear Friction Exceedance for Control Building Slab at EL. 100'-0"

Average of Shell Elements 2566/2567: Design Check					
East-West Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	East-West Reinf. D/C Ratio
1.337	0.645	0.636	2.618	3.120	0.839
			E-W Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.21	2.42	0.087
North-South Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	North-South Reinf. D/C Ratio
0.602	0.645	0.302	1.549	3.120	0.496
			N-S Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.09	2.42	0.036
Shear Friction			Code Check	OOP Shear	
XZ-Plane Shear-Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
1.783	6,686.1	OK	OK	28.1	0.540
YZ-Plane Shear-Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
2.518	9,442.8	OK		35.8	0.277

Table 3B-49: Summary of D/C Ratios for Control Building Pilasters on Grid Line 1 Wall

		Demand/Capacity Ratios				# Elems Checked
Section		Moment Axis 3	Shear Axis 2	Compression	Tension	
CRB;PI;1C;50-63	D/C Ratio	0.50	0.33	0.06	0.06	3
	Element	245	2	245	646	
CRB;PI;1B;50-76	D/C Ratio	0.62	0.95	0.06	0.04	5
	Element	647	667	246	667	
CRB;PI;1C;63-76	D/C Ratio	0.15	0.12	0.02	0.07	2
	Element	666	666	656	666	
CRB;PI;1C;76-100	D/C Ratio	0.41	0.24	0.02	0.09	4
	Element	696	706	706	696	
CRB;PI;1B;76-100	D/C Ratio	0.52	0.84	0.03	0.04	4
	Element	697	677	677	677	
CRB;PI;1C;100-120	D/C Ratio	0.51	0.32	0.03	0.08	3
	Element	821	801	801	801	
CRB;PI;1B;100-120	D/C Ratio	0.67	0.39	0.02	0.02	3
	Element	822	812	822	802	

Table 3B-49a: Magnitudes of Bounding Static and Dynamic Forces and Moments for CRB Pilasters on Grid Line 1

Load	Element	P (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
Static	821	-25	43	11	18	122	861
	2	-91	102	31	7	198	691
	245	-210	42	28	33	191	984
	696	27	14	12	28	153	424
	822	-54	79	15	13	124	2,239
	667	-81	285	8	37	68	1,777
	246	-214	240	9	41	58	1,239
Dynamic	821	62	24	24	21	143	774
	2	103	58	122	48	839	475
	245	253	62	153	19	971	618
	696	143	35	33	22	270	902
	822	89	64	21	16	130	1,904
	667	189	152	49	38	331	1,219
	246	205	133	79	68	542	1,082

Table 3B-49b: Magnitudes of Bounding Final Design Forces and Moments for CRB Pilasters on Grid Line 1

Element	P MAX (k)	P MIN (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
821	37	-87	67	35	40	265	1,636
2	12	-194	160	153	55	1,037	1,167
245	44	-463	104	181	52	1,162	1,602
696	170	-117	48	45	51	423	1,326
822	36	-143	143	36	28	254	4,143
667	108	-270	437	57	76	399	2,996
246	-10	-419	373	87	110	599	2,321

Table 3B-50: Summary of D/C Ratios for Control Building T-Beams on EL. 120'-0" Slab

Demand/Capacity Ratios						
Section		Moment Axis 3	Shear Axis 2	Compression	Tension	# Elems Checked
CRB;TB;120;D-E;1-2(1)	D/C Ratio	0.32	0.17	0.00	0.02	7
	Element	850	854	852	853	
CRB;TB;120;D-E;1-2(2)	D/C Ratio	0.27	0.16	0.00	0.01	7
	Element	879	879	874	874	
CRB;TB;120;1-3;C-C	D/C Ratio	0.45	0.19	0.00	0.01	12
	Element	830	830	886	904	
CRB;TB;120;1-3;B-C(2)	D/C Ratio	0.59	0.21	0.00	0.01	12
	Element	868	837	843	831	
CRB;TB;120;1-3;B-C(1)	D/C Ratio	0.77	0.25	0.00	0.01	12
	Element	869	838	844	832	
CRB;TB;120;1-3;B-B	D/C Ratio	0.75	0.45	0.01	0.01	12
	Element	833	833	833	833	
CRB;TB;120;1-3;A-B(2)	D/C Ratio	0.58	0.21	0.01	0.05	12
	Element	871	914	914	914	
CRB;TB;120;1-3;A-B(1)	D/C Ratio	0.30	0.25	0.02	0.11	11
	Element	872	909	909	909	

**Table 3B-50a: Magnitudes of Bounding Static and Dynamic Forces and Moments for CRB
T-Beams on EL. 120'-0" Slab**

Load	Element	P (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
Static	869	-8	1	1	2	15	1,056
	838	-6	56	5	3	25	192
	909	19	64	14	36	51	464
	833	-6	92	8	6	39	1,638
Dynamic	869	15	16	9	5	85	1,184
	838	18	45	16	14	58	258
	909	154	29	11	35	42	341
	833	37	85	18	20	91	1,658

**Table 3B-50b: Magnitudes of Bounding Final Design Forces and Moments for CRB T-Beams
on EL. 120'-0" Slab**

Element	P MAX (k)	P MIN (k)	V2 (k)	V3 (k)	T (k-ft)	M2 (k-ft)	M3 (k-ft)
869	7	-23	17	10	7	100	2,240
838	12	-24	100	21	17	83	450
909	173	-135	92	25	71	93	805
833	31	-44	177	26	26	131	3,296

Table 3B-51: Element Averaging of IP Shear Exceedance of Reactor Building Wall at Grid Line 3

Element		Length (in)	Thickness (in)	Shell Sxy (kip/in)	IP Shear Demand (kip)	f'_c (psi)	IP Shear Capacity $\phi_v 8A_{cv} \sqrt{f'_c}$ (kip)
Shell	4942	46.5	60	81.53	3791.2	5000	1183.7
Shell	4943	46.5	60	20.73	964.2	5000	1183.7
Shell	4944	53	60	9.86	522.8	5000	1349.2
Shell	4945	37	60	7.16	264.9	5000	941.9
Shell	4946	37	60	6.07	224.6	5000	941.9
Shell	4947	37	60	5.77	213.5	5000	941.9
Shell	4948	55	60	6.37	350.5	5000	1400.1
Shell	4949	52.5	60	10.17	533.9	5000	1336.4
Shell	4950	44.25	60	25.91	1146.4	5000	1126.4
Shell	4951	44.25	60	69.39	3070.5	5000	1126.4
Sum =					11082.6	<	11531.5

Table 3B-52: Element Averaging of Shear Friction Exceedance of Reactor Building Wall at Grid Line 3

Average of Shell Elements 4951/4431/4421: Design Check					
Horizontal Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total As (in ²)	As Provided (in ²)	Horizontal Reinf. D/C Ratio
11.416	7.563	1.938	20.917	28.080	0.745
			Horiz. Membrane Comp. Stress fxx (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			1.39	3.34	0.416
Vertical Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total As (in ²)	As Provided (in ²)	Vertical Reinf. D/C Ratio
9.867	7.563	0.821	18.251	28.080	0.650
			Vertical Membrane Comp. Stress fyy (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			1.15	3.34	0.345
Shear Friction			IP Shear	OOP Shear	
XZ-Plane Shear- Friction A_{vfx} (in ²)	$\mu_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
16.664	36,000.0	OK	OK	129.8	0.374
YZ-Plane Shear- Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
18.213	36,000.0	OK		129.8	0.162

Table 3B-53: Analysis Cases for NuScale Power Modules

Run Case ID	Ground Motion Seed	Soil Type	NPM Module	Concrete Section	NPM Module Stiffness
1	Capitola	7	1	Cracked	Nominal
2	Capitola	7	1	Cracked	Reduced (Scaled to 77%)
3	Capitola	7	1	Cracked	Increased (Scaled to 130%)
4	Capitola	7	1	Uncracked	Nominal
5	Capitola	7	1	Uncracked	Reduced (Scaled to 77%)
6	Capitola	7	1	Uncracked	Increased (Scaled to 130%)
7	Capitola	7	6	Cracked	Nominal
8	Capitola	7	6	Cracked	Reduced (Scaled to 77%)
9	Capitola	7	6	Cracked	Increased (Scaled to 130%)
10	Capitola	7	6	Uncracked	Nominal
11	Capitola	7	6	Uncracked	Reduced (Scaled to 77%)
12	Capitola	7	6	Uncracked	Increased (Scaled to 130%)

Table 3B-54: Strength Reduction Factors for Reinforced Concrete Design

Strength Reduction Factor	Value
Tension controlled	$\phi_m=0.9$
Compression controlled (without spiral)	$\phi_c=0.65$
Shear and torsion	$\phi_v=0.75$

Table 3B-55: RXB Critical Sections

Structure Type	Location	Figure Reference	Critical Dimension *
Walls			
	Wall at grid line 1 - West outer perimeter wall at foundation level	3B-8, 3B-9	5'-0"
	Wall at grid line 3 - Interior weir wall	3B-11, 3B-12	5'-0"
	Wall at grid line 3 - Interior upper stiffener	3B-11, 3B-13	4'-0"
	Wall at grid line 4 - Interior wall of RXB	3B-15, 3B-16	5'-0"
	Wall at grid line 4 - Interior wall of RXB	3B-15, 3B-17	4'-0"
	Wall at grid line 6 - Upper stiffener wall	3B-19, 3B-20	4'-0"
	Wall at grid line 6 - Pool wall	3B-19, 3B-21	5'-0"
	Wall at grid line 6 - Pool wall	3B-19, 3B-21	7'-6"
	Wall at grid line E - South exterior wall extending upward from foundation level	3B-23, 3B-24	5'-0"
Slabs			
	Basemat Foundation	3B-88, 3B-89	10'-0"
	Slab at EL. 100'-0" - Slab at grade	3B-29, 3B-27	3'-0"
	Slab at EL. 181'-0" - Slab at roof	3B-29, 3B-30	4'-0"
Pilasters			
	Pilasters at grid line A	3B-32, 3B-33, 3B-34, 3B-35, 3B-36	5'-0"
Beams			
	Beam at EL. 75'-0"	3B-38, 3B-39	2'-0"
Buttresses			
	Buttress at EL. 126'-0"	3B-41	5'-0"
NPM Bay			
	West wing wall	3B-15, 3B-16	5'-0"
	Pool wall	3B-46, 3B-47	5'-0"

*Dimensions shall be acceptable if found within the tolerances specified in ACI 117-06

Table 3B-56: CRB Critical Sections

Structure Type	Location	Figure Reference	Critical Dimension *
Walls			
	Wall at grid line 3 - Interior structural wall	3B-66, 3B-67	2'-0"
	Wall at grid line 4 - East exterior structural wall	3B-69, 3B-70	3'-0"
	Wall at grid line A - North exterior structural wall	3B-72, 3B-73	3'-0"
Slabs			
	Basemat foundation	3B-75, 3B-76	5'-0"
	Slab at EL. 100'-0" - Slab at grade	3B-78, 3B-79	3'-0"
	Slab at EL. 100'-0" - Slab at grade	3B-78, 3B-79	2'-0"
Pilasters			
	Pilasters at grid line 1	3B-81, 3B-82	3'-0"
T-Beams			
	T-Beam at EL. 120'-0"	3B-84, 3B-85	3'-0"
	T-Beam at EL. 120'-0"	3B-84, 3B-85	2'-0"

*Dimensions shall be acceptable if found within the tolerances specified in ACI 117-06

Table 3B-57: D/C Ratios for Structural Components of the Lug Supports

Structural Component	Stress Check	Demand	Capacity	D/C
Shear Lug Plates	Concrete Bearing	3.29 ksi	4.23 ksi	77.8%
Shear Lug Plates	Plate Bending	41.1 in-k	67.5 in-k	60.9%
Shear Lug Plates	Plate Shear (Steel Plate Check)	16.5 kips	90 kips	18.3%
Shear Lug Plates	Plate Shear (Concrete Check-Single)	790 kips	2523 kips	31.3%
Shear Lug Plates	Plate Shear (Concrete Check-Group)	3500 kips	5573 kips	62.8%
Shear Lug Plates	Shear Friction (At the tip of the lugs)	3500 kips	6966 kips	50.2%
Through Bolts	Tensile Stress	804 kips	1576 kips	51.0%
RXM Support Wall	Punching Shear	888 kips	3394 kips	26.1%
Pool Wall	Punching Shear	888 kips	4412 kips	20.1%
2" Liner Plate	Bearing Stress	804 kips	1989 kips	40.4%
2" Liner Plate	Bending Stress	11.6 ksi	100.8 ksi	11.5%

**Table 3B-58: ANSYS RXB Reinforcing Steel and Liner Steel Elastic Strain Summary
for T_0 and T_a+P_a**

Type	Location	Maximum Strain ($\times 10^{-3}$)			
		T_0	P_a^*	T_a	T_a+P_a
Reinforcing Steel	All Sections	0.514	0.181	1.342	1.343
	Outer Wall - North	0.373	0.055	0.666	0.672
	Outer Wall - East	0.231	0.063	0.426	0.426
	Outer Wall - West	0.256	0.062	0.677	0.687
	Pool Wall - North	0.393			1.053
	Pool Wall - East	0.317			0.850
	Pool Wall - West	0.352			1.016
	Pool Wall - Middle	0.444			1.057
	Pool Gate Support Wall	0.459			1.343
	Roof Support Stiffeners	0.333			0.870
	Roof Support Wall Above Crane	0.240			0.665
	NPM Support Walls	0.294			0.776
	Roof	0.115	0.181	0.485	0.488
	Major Slabs	0.514			0.961
	Pilasters	0.373			0.672
	Buttresses	0.237			0.616
	T-Beams	0.514			0.961
	Foundation	0.112			0.367
Liner Steel	Steel Pool Liner	0.895			2.181

* Shaded cell resultants are not extracted for individual load case and locations

Table 3B-59: ANSYS RXB Strain Based Concrete Design Check for SDH Loads

Location	Max $\epsilon_c(\times 10^{-3})$ from SDH		$\epsilon_c < \epsilon_{cu}$?
	X	Y	Concrete
Outer Wall – North (Grid Line A)	0.348	1.173	OK
Outer Wall – East (Grid Line 7)	0.323	0.786	OK
Outer Wall – West (Grid Line 1)	0.290	0.434	OK
Pool Wall – North (Grid Line B)	0.764	1.182	OK
Pool Wall – East (Grid Line 6)	0.616	0.354	OK
Pool Wall – West (Grid Line 2)	0.574	0.322	OK
Pool Wall – Middle (Grid Line C)	2.094*	2.025*	OK
Pool Gate Support Wall	0.786	0.330	OK
Roof Support Stiffeners (Grid Lines 2, 3, 4, 5, 6)	0.576	0.170	OK
Roof Support Wall Above Crane (Grid Line A.7)	0.399	1.140	OK
NPM Support Walls (Grid Lines 4, 4.3, 4.7, 5, 5.3, 5.7)	0.607	0.920	OK
Roof	0.564	1.062	OK
Major Slabs (TOC EL 50', 75', 100', 126')	0.572	1.069	OK
Pilasters at Grid Line A	1.007	1.007	OK
Buttress at TOC EL 126'-0" and 145'-0"	0.918	0.918	OK
T-Beams at TOC EL 50'-0", 75'-0", and 100'-0"	0.872	0.872	OK
RXB Basemat (Perimeter Region)	0.919	0.852	OK
RXB Basemat (Interior Region)	0.806	0.687	OK

*Bold cell indicates averaging was employed.

**Table 3B-60: ANSYS RXB Reinforcing Steel and Liner Steel Elastic Strain Summary
for Load Combination 10**

Type	Location	Max ϵ_s ($\times 10^{-3}$) from SDH Loads		Max ϵ_s ($\times 10^{-3}$) from T_0	Max ϵ_s ($\times 10^{-3}$) from LC 10	$\epsilon_s < 1.2 \epsilon_y$?
		X	Y	X, Y	X, Y	LC 10
Reinforcing Steel	Outer Wall – North	0.746	1.962	0.373	2.335	OK
	Outer Wall – East	1.352	1.339	0.231	1.583	OK
	Outer Wall – West	1.076	1.516	0.256	1.772	OK
	Pool Wall – North	1.574	1.782	0.393	2.175	OK
	Pool Wall – East	1.838	0.698	0.317	2.155*	OK
	Pool Wall – West	1.451	0.945	0.352	1.803	OK
	Pool Wall – Middle	2.137	2.020	0.444	2.461*	OK
	Pool Gate Support Wall	2.023	1.351	0.459	2.482*	OK
	Roof Support Stiffeners	1.864	1.080	0.333	2.197*	OK
	Roof Support Wall Above Crane	0.955	1.770	0.240	2.010	OK
	NPM Support Walls	1.909	1.451	0.294	2.203	OK
	Roof	1.507	1.834	0.115	1.949	OK
	Major Slabs	1.406	2.228	0.514	2.443*	OK
	Pilasters	2.131	2.131	0.373	2.482*	OK
	Buttress	1.937	1.937	0.373	2.310	OK
	T-Beams	1.913	1.913	0.514	2.427	OK
	Foundation	2.157	2.230	0.112	2.342	OK
	Steel Pool Liner	0.363	0.066	0.895	1.258	OK

*Bold cell indicates averaging was employed.

**Table 3B-61: ANSYS RXB Reinforcing Steel and Liner Steel Elastic Strain Summary
for Load Combination 13**

Type	Location	Max ϵ_s ($\times 10^{-3}$) from SDH Loads		Max ϵ_s ($\times 10^{-3}$) from $T_a + P_a$	Max ϵ_s ($\times 10^{-3}$) from LC 13	$\epsilon_s < 1.2 \epsilon_y$?
		X	Y	X, Y	X, Y	LC 13
Reinforcing Steel	Outer Wall – North	0.746	1.962	0.672	2.469*	OK
	Outer Wall – East	1.352	1.339	0.426	1.778	OK
	Outer Wall – West	1.076	1.516	0.687	2.203	OK
	Pool Wall – North	1.368	1.627	1.053	2.481*	OK
	Pool Wall – East	1.511	0.698	0.850	2.361*	OK
	Pool Wall – West	1.451	0.945	1.016	2.467	OK
	Pool Wall – Middle	1.370	1.718	1.057	2.479*	OK
	Pool Gate Support Wall	1.229	0.976	1.343	2.402*	OK
	Roof Support Stiffeners	1.308	1.139	0.870	2.178*	OK
	Roof Support Wall Above Crane	0.955	1.770	0.665	2.435	OK
	NPM Support Walls	1.487	1.451	0.776	2.263*	OK
	Roof	1.507	1.834	0.488	2.322	OK
	Major Slabs	1.406	2.164	0.961	2.469*	OK
	Pilasters	2.078	2.078	0.672	2.468*	OK
	Buttress	1.862	1.862	0.616	2.478*	OK
	T-Beams	1.405	1.405	0.961	2.366*	OK
	Foundation	2.157	2.230	0.367	2.597	OK
	Steel Pool Liner	0.363	0.066	2.181	2.544	OK

*Bold cell indicates averaging was employed.

Table 3B-62: Combined Maximum‡ Values for RXB Basemat Forces and Moments

Element	FX(Sxx)† (k/ft)	FY(Syy)† (k/ft)	Sxy (k/ft)	MX(Myy) (k-ft/ft)	MY(Mxx) (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Perimeter Region	456	558	47	196	117	2749	3022
Element No.	S326	S125	S216	S1627	S204	S296	S326
Interior Region	125	149	70	142	228	1781	2054
Element No.	S527	S528	S828	S498	S488	S737	S826

†FX and FY are in tension.

‡Element averaging was employed.

The values have been increased by 5% to account to the effect of accidental torsion.

Table 3B-63: Magnitudes of Bounding Static and Dynamic RXB Basemat Forces and Moments

Element	FX(Sxx) (k/ft)	FY(Syy) (k/ft)	Sxy (k/ft)	MX(Myy) (k-ft/ft)	MY(Mxx) (k-ft/ft)	Vxz (k/ft)	Vyz (k/ft)
Static Force or Moment	156	262	49	2554	2554	358	438
Element No.	S135	S845	S828	S1690	S1690	S829	S1706
Dynamic Force or Moment	818	916	22	3174	3174	632	926
Element No.	S326	S125	S1685	S305	S305	S1689	S536

Table 3B-64: Design Check for Reactor Building Basemat Foundation for Perimeter Region

Basemat Foundation for RXB (Perimeter Region): Design Check					
East-West Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	East-West Reinf. D/C Ratio
8.453	0	6.611	15.063	18.72	0.805
			E-W Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.74	2.59	0.287
North-South Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	North-South Reinf. D/C Ratio
10.335	0	6.015	16.349	18.72	0.873
			N-S Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.68	2.59	0.264
Shear Friction			Code Check	OOP Shear	
XZ-Plane Shear- Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
10.268	38,503.10	OK	OK	403.3	0.486
YZ-Plane Shear- Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
8.385	31,444.80	OK		384.1	0.304

Table 3B-65: Design Check for Reactor Building Basemat Foundation for Interior Region

Basemat Foundation for RXB (Interior Region): Design Check					
East-West Reinforcement (Local X)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	East-West Reinf. D/C Ratio
2.308	0	4.297	6.605	12.48	0.529
			E-W Membrane Comp. Stress f_{xx} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.16	2.46	0.064
North-South Reinforcement (Local Y)					
Membrane Tension A_{s1} (in ²)	In-Plane Shear A_{s2} (in ²)	OOP Moment A_{s3} (in ²)	Total A_s (in ²)	A_s Provided (in ²)	North-South Reinf. D/C Ratio
2.755	0	3.724	6.48	12.48	0.519
			N-S Membrane Comp. Stress f_{yy} (ksi)	Membrane Compression Strength (ksi)	Membrane Compression Stress D/C Ratio
			0.21	2.46	0.086
Shear Friction			Code Check	OOP Shear	
XZ-Plane Shear- Friction A_{vfx} (in ²)	$\phi_v V_{nx} = \phi_v A_{vfx} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{nx} ?$	$S_{xy} < \phi_v V_{in-plane} ?$	XZ-Plane Shear Capacity (kip)	XZ-Plane D/C Ratio
10.172	38,144.80	OK	OK	297	0.479
YZ-Plane Shear- Friction A_{vfy} (in ²)	$\phi_v V_{ny} = \phi_v A_{vfy} f_y \mu$ (lb)	$S_{xy} < \phi_v V_{ny} ?$		YZ-Plane Shear Capacity (kip)	YZ-Plane D/C Ratio
9.725	36,467.70	OK		292.3	0.78

Table 3B-66: Design Summary - Wall at Grid Line 1, EL 24'-75'

Description	Parameters	Value
Reinforcement Schedule	-	2-#11 @ 6" oc, EWEF, #11 @ 6" oc, EW on both sides of wall centerline, with #9 headed bars @12" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	13.0
Nominal moment capacity	M_N (kip-ft/ft)	2,186
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1,967
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	305
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	214

Table 3B-67: Design Summary - Wall at Grid Line 1, EL 75'-100'

Description	Parameters	Value
Reinforcement schedule	-	4-#11 @ 6" oc, EWEF, with #9 headed bars @12" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	17.0
Nominal moment capacity	M_N (kip-ft/ft)	2,618
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	2,356
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	305
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	210

Table 3B-68: Design Summary - Wall at Grid Line 1, EL 100'-145'-6"

Description	Parameters	Value
Reinforcement	-	4-#11 @ 6" oc, EWEF. See Ref. 1.4.1, S33, W/S57, with #9 headed bars @12" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	7,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	15.6
Nominal moment capacity	M_N (kip-ft/ft)	2,800
Strength reduction factor for flexure (Reference 1.4.9, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	2,520
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	361
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	217

Table 3B-69: Design Summary - Wall at Grid Line 1, EL 145'-6"-181'

Description	Parameters	Value
Reinforcement schedule	-	2-#11 @ 6" oc, EWEF, #11 @ 6" oc, EW on both sides of wall centerline, with #9 headed bars @12" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	7,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	11.5
Nominal moment capacity	M_N (kip-ft/ft)	2,255
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	2030
In-plane shear capacity	$\phi V_{In-plane}$ (kip/ft)	361
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	225

Table 3B-70: Design Summary - Interior Weir Wall at Grid Line 3

Description	Parameters	Value
Reinforcement schedule	-	3 curtains of #11 bars, spaced at 6"-3.25"-6"-3.25" oc EWEF, one similar curtain at the centerline of the wall, with #9 headed bars @ 9¼" horizontally and 18½" vertically oc.
Section thickness	h (in)	60
Concrete cover dimension	c _c (in)	6
Concrete compressive strength	f _c ' (psi)	5,000
Rebar yield strength	f _y (psi)	60,000
Distance from neutral axis to compression face	c (in)	17.0
Nominal moment capacity	M _N (kip-ft/ft)	2,717
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	Φ _M	0.90
Out-of-plane moment capacity ΦM _N = Φ _M M _N	ΦM _N (kip-ft/ft)	2,445
In-plane shear capacity	ΦV _{In-plane} (kip/ft)	305
Out-of-plane shear capacity	ΦV _{Out-plane} (kip/ft)	196

Table 3B-71: Design Summary - 4'-Thick Interior Upper Stiffener Wall at Grid Line 3

Description	Parameters	Value
Reinforcement schedule	-	2- #11 bars, spaced at 6" oc EWEF, with #9 headed bars @12" oc, EW.
Section thickness	h (in)	48
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	8.3
Nominal moment capacity	M_N (kip-ft/ft)	1,167
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1,051
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	244
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	186

Table 3B-72: Design Summary - 5'-Thick Interior Wall at Grid Line 4

Description	Parameters	Value
Reinforcement schedule	-	3 curtains of #11 bars, spaced at 6"-3.25"-6"-3.25" oc, EWEF, one similar curtain at the center line of the wall, with 2 #9 headed bars @ 18½" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	6
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	17.5
Nominal moment capacity	M_N (kip-ft/ft)	2,826
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	2,543
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	305
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	196

Table 3B-73: Design Summary - Reactor Building 4'-Thick Interior Wall at Grid Line 4

Description	Parameters	Value
Reinforcement schedule	-	3- #11 bars, spaced at 6" oc, EWEF, with #9 headed bars @12" oc, EW.
Section thickness	h (in)	48
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	11.5
Nominal moment capacity	M_N (kip-ft/ft)	1,600
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1,440
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	244
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	190

Table 3B-74: Design Summary - 4'-Thick Pool Wall at Grid Line 6

Description	Parameters	Value
Reinforcement schedule	-	3- #11 bars, spaced at 6" oc, EWEF, with #9 headed bars @12" oc, EW.
Section thickness	h (in)	48
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	11.5
Nominal moment capacity	M_N (kip-ft/ft)	1,600
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1,440
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	244
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	190

Table 3B-75: Design Summary - Pool Wall at Grid Line 6 above EL 123'

Description	Parameters	Value
Reinforcement schedule	-	3-#11 bars, spaced at 6" oc, EWEF, 1-#11 @ 6" on both sides of the centerline of the wall, with #8 headed bars @ 12" vertically and @ 12½" -6"-12½"-6" horizontally oc.
Section thickness	h (in)	60
Concrete cover dimension (inner)	c_c (in)	6
Concrete cover dimension (outer)	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	15.8
Nominal moment capacity	M_N (kip-ft/ft)	2,583
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	2,324
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	275
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	217

Table 3B-76: Design Summary - Pool Wall at Grid Line 6 below EL 123'

Description	Parameters	Value
Reinforcement schedule	-	3 curtains of #11 bars, spaced at 6"-3.25"-6"-3.25" oc, EWEF, with #8 headed bars @ 12" vertically and @ 12½"-6"-12½"-6" horizontally oc.
Section thickness	h (in)	60
Concrete cover dimension (inner)	c_c (in)	6
Concrete cover dimension (outer)	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	12.7
Nominal moment capacity	M_N (kip-ft/ft)	2,548
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	2,293
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	275
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	236

Table 3B-77: Design Summary - Pool Wall at Grid Line 6 - 7'-6" Thick Section below EL 123'

Description	Parameters	Value
Reinforcement schedule	-	3 curtains of #11 bars, spaced at 6"-3.25"-6"-3.25" oc EWEF, with #9 headed bars @ 12" vertically and @ 12½"-6"-12½"-6" horizontally oc.
Section thickness	h (in)	90
Concrete cover dimension (inner)	c_c (in)	6
Concrete cover dimension (outer)	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	12.7
Nominal moment capacity	M_N (kip-ft/ft)	4,370
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	3.933
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	428
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	327

Table 3B-78: Design Summary - Exterior Wall at Grid Line E below EL 50'

Description	Parameters	Value
Reinforcement schedule	-	2-#11 bars, spaced at 6" oc, EWEF, 1-#11 @ 6" at the centerline of the wall, with #9 headed bars @12" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	10.4
Nominal moment capacity	M_N (kip-ft/ft)	1,884
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1,696
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	305
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	233

Table 3B-79: Design Summary - Exterior Wall at Grid Line E between EL 50' and EL 100'

Description	Parameters	Value
Reinforcement schedule	-	2-#11 bars, spaced at 6" oc, EWEF, with #9 headed bars @12" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	8.3
Nominal moment capacity	M_N (kip-ft/ft)	1,542
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_{NNew} (kip-ft/ft)	1,388
In-plane shear capacity	$\phi V_{In-plane}$ (kip/ft)	305
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	238

Table 3B-80: Design Summary - Exterior Wall at Grid Line above EL 100'

Description	Parameters	Value
Reinforcement schedule	-	2-#11 bars, spaced at 6" oc, EWEF, with #9 headed bars @12" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	7,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	7.7
Nominal moment capacity	M_N (kip-ft/ft)	1,582
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1,424
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	361
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	240

Table 3B-81: Design Summary - Reactor Building Basemat Perimeter

Description	Parameters	Value
Reinforcement schedule	-	3-#11 bars, spaced at 6" oc, top and bottom, with #9 headed bars @ 12 oc, EW.
Section thickness	h (in)	120
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	11.5
Nominal moment capacity	M_N (kip-ft/ft)	4,970
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	4,473
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	611
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	500

Table 3B-82: Design Summary - Reactor Building Basemat Interior

Description	Parameters	Value
Reinforcement schedule	-	2-#11 bars, spaced at 6" oc, top and bottom, with #6 headed bars @ 12 oc, EW.
Section thickness	h (in)	120
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	8.3
Nominal moment capacity	M_N (kip-ft/ft)	3,414
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	3,073
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	611
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	328

Table 3B-83: Design Summary - Reactor Building Slab at EL 100'

Description	Parameters	Value
Reinforcement schedule	-	Outer layer of #11 bars @ 6" oc, EW, top and bottom, inner layer of #11 bars @ 12" oc EW, top and bottom, with 2 #6 shear ties @ 12 oc, EW.
Section thickness	h (in)	36
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	6.96
Nominal moment capacity	M_N (kip-ft/ft)	639
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	575
In-plane shear capacity	$\phi V_{In-plane}$ (kip/ft)	183
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	129

Table 3B-84: Design Summary - Reactor Building Roof Slab at EL 181'

Description	Parameters	Value
Reinforcement schedule	-	Two curtains of #11 bars spaced at 6"-3"-3"-6" EW, T&B, with #9 headed bars @ 12" oc, EW.
Section thickness	h (in)	48
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	9.8
Nominal moment capacity	M_N (kip-ft/ft)	1,684
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1,516
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	244
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	204

Table 3B-85: Design Summary - West Wing Wall

Description	Parameters	Value
Reinforcement schedule	-	3 curtains of #11 bars, spaced at 6"-3.25"-6"-3.25" oc EWEF, one similar curtain at the center line of the wall, with 2 #9 headed bars @ 18½" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	6
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	17.5
Nominal moment capacity	M_N (kip-ft/ft)	2,826
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	2,543
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	305
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	196

Table 3B-86: Design Summary - Pool Wall at Grid Line B

Description	Parameters	Value
Reinforcement schedule	-	2-#11 bars, spaced at 6" oc, EWEF, with #9 headed bars @ 12" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	8.3
Nominal moment capacity	M_N (kip-ft/ft)	1,542
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1,388
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	275
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	239

Table 3B-87: Design Summary - Control Building Interior Wall at Grid Line 3

Description	Parameters	Value
Reinforcement schedule	-	2-#9 bars, spaced at 12" oc, EWEF.
Section thickness	h (in)	24
Concrete cover dimension	c_c (in)	0.75
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	3.8
Nominal moment capacity	M_N (kip-ft/ft)	202
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_{NNew} (kip-ft/ft)	182
In-plane shear capacity	$\phi V_{In-plane}$ (kip/ft)	122
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	26

Table 3B-88: Design Summary - Control Building Exterior Wall at Grid Line 4

Description	Parameters	Value
Reinforcement schedule	-	2-#11 bars, spaced at 12" oc, EWEF, #6 stirrups @ 12" oc (below EL 100').
Section thickness	h (in)	36
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	6.25
Nominal moment capacity	M_N (kip-ft/ft)	451
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	406
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	183
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	84

Table 3B-89: Design Summary - Control Building Exterior Wall at Grid Line A

Description	Parameters	Value
Reinforcement schedule	-	2-#11 bars, spaced at 12" oc, EWEF, with #6stirrup@12"oc,EW (below EL 100').
Section thickness	h (in)	36
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	6.25
Nominal moment capacity	M_N (kip-ft/ft)	451
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	406
In-plane shear capacity	$\phi V_{In-plane}$ (kip/ft)	183
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	84

Table 3B-90: Design Summary - Control Building Basemat Perimeter

Description	Parameters	Value
Reinforcement schedule	-	4-#11 bars, spaced at 12" oc, top and bottom, with 2 #6 ties @ 12" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	10.9
Nominal moment capacity	M_N (kip-ft/ft)	1,499
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1,349
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	305
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	129

Table 3B-91: Design Summary - Control Building Basemat Interior

Description	Parameters	Value
Reinforcement schedule	-	3-#11 bars, spaced at 12" oc, top and bottom, with 2 #6 ties @ 12" oc, EW.
Section thickness	h (in)	60
Concrete cover dimension	c_c (in)	3
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	8.6
Nominal moment capacity	M_N (kip-ft/ft)	1,181
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	1,063
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	305
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	134

Table 3B-92: Design Summary - Control Building 2'-Thick Slab at EL 100'

Description	Parameters	Value
Reinforcement schedule	-	#11 bars, spaced at 12" oc, top and bottom.
Section thickness	h (in)	24
Concrete cover dimension	c_c (in)	0.75
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	2.8
Nominal moment capacity	M_N (kip-ft/ft)	157
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	141
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	122
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	27

Table 3B-93: Design Summary - Control Building 3'-Thick Slab at EL 100'

Description	Parameters	Value
Reinforcement schedule	-	#11 bars, spaced at 12" oc, top and bottom.
Section thickness	h (in)	36
Concrete cover dimension	c_c (in)	0.75
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	2.8
Nominal moment capacity	M_N (kip-ft/ft)	251
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	226
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	183
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	43

Table 3B-94: Design Summary - Control Building Tunnel Slab

Description	Parameters	Value
Reinforcement schedule	-	2-#11 bars, spaced at 12" oc, top and bottom, with #6 stirrups @ 12" oc, EW.
Section thickness	h (in)	36
Concrete cover dimension	c_c (in)	2
Concrete compressive strength	f'_c (psi)	5,000
Rebar yield strength	f_y (psi)	60,000
Distance from neutral axis to compression face	c (in)	5.8
Nominal moment capacity	M_N (kip-ft/ft)	460
Strength reduction factor for flexure (ACI 349-06, Section 9.3.2.1)	ϕ_M	0.90
Out-of-plane moment capacity $\phi M_N = \phi_M M_N$	ϕM_N (kip-ft/ft)	414
In-plane shear capacity	$\phi V_{\text{In-plane}}$ (kip/ft)	183
Out-of-plane shear capacity	ϕV_{OOP} (kip/ft)	87

Figure 3B-1: Whitney Rectangular Stress Block




Figure 3B-2: SAP2000 Membrane and Shear Force Definition




Figure 3B-3: SAP2000 Bending Moment Definition




Figure 3B-4: SASSI2010 Membrane, Shear Force, and Bending Moment Definitions




Figure 3B-5: SAP2000 Frame Element Results Definition




Figure 3B-6: SASSI2010 Frame Element Results Definition





Figure 3B-7: SAP2000 Elevation View and Shell Element Numbers at RXB Grid Line 1 (Looking West)

Figure 3B-8: RXB Reinforcement Elevation at Grid Line 1 Wall





Figure 3B-9: RXB Reinforcement Section View of Wall on Grid Line 1

SECTION W
SCALE: NTS FIGURE 3B-8

Tier 2



Figure 3B-11: RXB Reinforcement Elevation at Grid Line 3 Wall





Figure 3B-12: RXB Reinforcement Section View of Pool Weir Wall on Grid Line 3




WEIR PILASTER DETAIL

SCALE: NTS

8

FIGURE 3B-11

Figure 3B-13: RXB Reinforcement Section View of Stiffener Wall on Grid Line 3



SECTION
SCALE: NTS

T
FIGURE 3B-11

Figure 3B-14: SAP2000 Elevation View and Shell Element Numbers at RXB Grid Line 4 (Looking West)







Figure 3B-15: RXB Reinforcement Elevation at Grid Line 4 Wall

Figure 3B-16: RXB Reinforcement Section View of 5 ft Thick Wall on Grid Line 4



SECTION V
SCALE: NTS FIGURE 3B-15

Figure 3B-17: RXB Reinforcement Section View of 4 ft Thick Wall on Grid Line 4



SECTION
SCALE: NTS

GG
FIGURE 3B-15

Figure 3B-18: SAP2000 Elevation View and Shell Element Numbers at RXB Grid Line 6 (Looking West)






Figure 3B-19: RXB Reinforcement Elevation at Grid Line 6 Wall

Figure 3B-20: RXB Reinforcement Section View of Upper Stiffener Wall on Grid Line 6

SECTION

GG

SCALE: NTS

FIGURE 3B-19, 3B-43


Figure 3B-21: RXB Reinforcement Section Views of Pool Wall on Grid Line 6

Figure 3B-22: SAP2000 Elevation View and Shell Element Numbers at RXB Grid Line E (Looking North)




Figure 3B-23: RXB Reinforcement Elevation at Grid Line E Wall





Figure 3B-24: RXB Reinforcement Section View of Wall on Grid Line E



SECTION:
SCALE: NTS

S
FIGURE 3B-23


Tier 2



Figure 3B-26: RXB Reinforcement Plan at EL 100'-0"

{{ Withheld - See Part 9 }}

Figure 3B-27: RXB Reinforcement Section View of Slab at EL 100'-0"



SECTION
SCALE: NTS

E
FIGURE 3B-26

Figure 3B-28: SAP2000 Plan View and Shell Element Numbers on RXB Roof Slab




Figure 3B-29: RXB Reinforcement Plan for Roof Slab




Figure 3B-30: RXB Reinforcement Section View of Roof Slab




Figure 3B-31: SAP2000 View and Frame Element Numbers of Pilasters on RXB Grid Line A Wall




Figure 3B-32: RXB Reinforcement Detail for Pilaster Type 1




Figure 3B-33: RXB Reinforcement Detail for Pilaster Type 2




Figure 3B-34: RXB Reinforcement Detail for Pilaster Type 3




Figure 3B-35: RXB Reinforcement Detail for Pilaster Type 4




Figure 3B-36: RXB Reinforcement Detail for Pilaster Type 5




Figure 3B-37: SAP2000 View and Frame Element Numbers of Beams on RXB EL 75'-0" Slab






Figure 3B-38: RXB Reinforcement Detail for Type 1 T-Beams at EL 75'-0"



TYPICAL DETAILS OF REINFORCING STEEL IN THE T-BEAM AND SLAB

Figure 3B-39: RXB Reinforcement Detail for Type 2 T-Beams at EL 75'-0"



TYPICAL DETAILS OF REINFORCING STEEL IN THE T-BEAM AND SLAB

Figure 3B-40: SAP2000 View and Frame Element Numbers of Buttresses at Grid Line 1 on RXB EL. 126'-0"




Figure 3B-41: RXB Reinforcement Detail for Buttress Type 1




Figure 3B-42: Not Used

Figure 3B-43: Not Used

Figure 3B-44: Not Used

Figure 3B-45: SAP2000 Elevation View and Shell Element Numbers at RXB Wall at Grid Line B (Looking North)




Figure 3B-46: RXB Reinforcement Elevation at RXB Wall at Grid Line B





Figure 3B-47: RXB Reinforcement Section View of RXB Wall at Grid Line B

SECTION
SCALE: NTS

X
FIGURE 3B-46



Figure 3B-48: NuScale Power Module Base Support Assembly at Reactor Building Pool Floor

Figure 3B-49: Plan View and Cross Sections of NPM Embed Plate




Figure 3B-50: Plan View of NPM Embed Plate Anchorage and Passive Plate





Figure 3B-51: NPM Lug Support Plan View and Details



PLAN VIEW

NOTES:

1. THE FINAL LOCATION OF THE STEEL THREADED RODS WILL BE IN BETWEEN THE #11 REBAR SPACING. THE FINAL POSITION OF THE SHEAR LUGS WILL BE ADJUSTED ACCORDINGLY.
2. CONSTRUCTION: NOTE THE RXM LUG SUPPORTS NEED TO BE SHOP ASSEMBLED REBAR/LINER/RXM. LUG SUPPORTS WILL NEED TO BE MODELED TO BE CONSTRUCTIBLE.
3. THE SHEAR TIES WILL EXTEND THOROUGH THE 66" X 66" ANCHOR PLATE AND THE FINAL LOCATIN WILL BE BETWEEN THE #11 REBAR SPACING.




Figure 3B-52: NPM Lug Location




Figure 3B-53: NPM Lug Support SAP2000 Model




Figure 3B-54: NPM Lug Support SAP2000 Model Close-Up




Figure 3B-55: NPM Lug Support Liner Plate Section




Figure 3B-56: NPM Lug Support Liner Plate and Shear Lugs (Shown in Red)




Figure 3B-57: NPM Lug Support Model showing internal Stiffener Plates




Figure 3B-58: NPM Lug Support Loading (W-Lug-PY+)




Figure 3B-59: NPM Lug Support Loading (W-Lug-PY-)




Figure 3B-60: NPM Lug Support SAP2000 Model Restraints




Figure 3B-61: Stiffener Plate Section Cut Groups (Fins)




Figure 3B-62: S11 Stress plotted on the Deflected Shape due to Load Combination W-Lug-PY+ (psi)




Figure 3B-63: Not Used

Figure 3B-64: Not Used

Figure 3B-65: SAP2000 Elevation View and Shell Element Numbers at CRB Grid Line 3 (Looking North)




Figure 3B-66: CRB Reinforcement Elevation at Grid Line 3 Wall




Figure 3B-67: CRB Reinforcement Section View of Wall on Grid Line 3




Figure 3B-68: SAP2000 Elevation View and Shell Element Numbers at CRB Grid Line 4 (Looking West)

3927	3928	3929		3930			3931		3932			3933			3934			3935		3936		3937	3938
3869	3870	3871		3872			3873		3874			3875			3876			3877		3878		3879	3880
3804	3805	3806		3807			3808		3809			3810			3811			3812		3813		3814	3815
3739	3740	3741		3742			3743		3744			3745			3746			3747		3748		3749	3750
3308	3309	3310	3311	3312	3313	3314	3315	3316	3317	3318	3319	3320	3321	3322	3323	3324	3325	3326	3327	3328	3329	3330	
3164	3165	3166	3167	3168	3169	3170	3171	3172	3173	3174	3175	3176	3177	3178	3179	3180	3181	3182	3183	3184	3185	3186	
3025		3026	3027	3028	3029	3030	3031			3032	3033	3034	3035	3036	3037	3038	3039	3040	3041	3042		3043	
2515	2516	2517	2518	2519	2520	2521	2522	2523	2524	2525	2526	2527	2528	2529	2530	2531	2532	2533	2534	2535	2536	2537	
2363	2364	2365	2366	2367	2368	2369	2370	2371	2372	2373	2374	2375	2376	2377	2378	2379	2380	2381	2382	2383	2384	2385	
2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	
2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	
1544	1545	1546	1547	1548	1549	1550	1551	1552	1553	1554	1555	1556	1557	1558	1559	1560	1561	1562	1563	1564	1565	1566	
1341	1342	1343	1344	1345	1346	1347	1348	1349	1350	1351	1352	1353	1354	1355	1356	1357	1358	1359	1360	1361	1362	1363	
983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000	1001	1002	1003	1004	1005	
771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	
163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	

Figure 3B-69: CRB Reinforcement Elevation at Grid Line 4 Wall




Figure 3B-70: CRB Reinforcement Section View of Wall on Grid Line 4




Figure 3B-71: SAP2000 Elevation View and Shell Element Numbers at Grid Line A (Looking West)

3892			3894			3896					3906	3910	3914	3918	3922	3926
3827			3829			3831					3841	3848	3853	3858	3864	3868
3762			3764			3766					3776	3783	3788	3793	3799	3803
3697			3699			3701					3711	3718	3723	3728	3734	3738
3212	3215	3218	3221	3224	3227	3230	3233	3236	3245	3251	3258	3283	3289	3295	3302	3307
3069	3072	3075	3078	3081	3084	3087	3090	3093	3102	3108	3115	3140	3146	3152	3158	3163
2937	2940	2943	2946	2949	2952	2955	2958	2961	2970	2975	2982	3002	3008	3014	3020	3024
2425	2428	2431	2434	2437	2440	2443	2446	2449	2452	2458	2465	2490	2496	2502	2509	2514
2273	2276	2279	2282	2285	2288	2291	2294	2297	2300	2306	2313	2338	2344	2350	2357	2362
2122	2125	2128	2131	2134	2137	2140	2143	2146	2149	2155	2162	2187	2193	2199	2205	2210
1978	1981	1984	1987	1990	1993	1996	1999	2002	2005	2011	2018	2037	2043	2049	2055	2059
1404	1408	1412	1416	1420	1424	1437	1440	1444	1454	1461	1469	1499	1510	1521	1533	1543
1200	1204	1208	1212	1216	1220	1233	1237	1241	1251	1258	1266	1296	1307	1318	1330	1340
835	839	843	847	851	855	869	874	881	897	903	909	939	950	961	972	982
635	639	643	647	651	655	667	672	679	692	698	704	727	738	749	760	770
27	31	35	39	43	47	61	66	73	91	99	107	118	129	140	152	162




Figure 3B-73: CRB Reinforcement Section View of Wall on Grid Line A




Figure 3B-74: CRB Basemat View of Finite Element Model




Figure 3B-75: CRB Reinforcement Plan of Basemat Foundation





Figure 3B-76: Cross Section of CRB Basemat Showing Reinforcing Steel



					2579	2602	2625	2648	2671	2694	2717	2740	2763												
					2578	2601	2624	2647	2670	2693	2716	2739	2762						2783	2803					
					2577	2600	2623	2646	2669	2692	2715	2738	2761	2782	2802	2822						2892	2911		
					2576	2599	2622	2645	2668	2691	2714	2737	2760	2781	2801	2821									
					2575	2598	2621	2644	2667	2690	2713	2736	2759	2780	2800	2820	2839	2856	2873	2890	2909				
					2574	2597	2620	2643	2666	2689	2712	2735	2758	2779	2799	2819	2838	2855	2872	2889	2908				
					2573	2596	2619	2642	2665	2688	2711	2734	2757	2778	2798	2818	2837	2854	2871	2888	2907				
					2572	2595	2618	2641	2664	2687	2710	2733	2756	2777	2797	2817	2836	2853	2870	2887	2906				
					2571	2594	2617	2640	2663	2686	2709	2732	2755	2776	2796	2816	2835	2852	2869	2886	2905				
					2570	2593	2616	2639	2662	2685	2708	2731	2754	2775	2795	2815	2834	2851	2868	2885	2904				
					2569	2592	2615	2638	2661	2684	2707	2730	2753	2774	2794	2814	2833	2850	2867	2884	2903				
					2568	2591	2614	2637	2660	2683	2706	2729	2752	2773	2793	2813	2832	2849	2866	2883	2902				
					2567	2590	2613	2636	2659	2682	2705	2728	2751	2772	2792	2812	2831	2848	2865	2882	2901				
					2566	2589	2612	2635	2658	2681	2704	2727	2750	2771	2791	2811	2830	2847	2864	2881	2900				
					2541	2545	2549	2553	2557	2565	2588	2611	2634	2657	2680	2703	2726	2749	2770	2790	2810	2829	2846	2863	2880
2540	2544	2548	2552	2556	2564	2587	2610	2633	2656	2679	2702	2725	2748	2769	2789	2809	2828	2845	2862	2879	2898				
2539	2543	2547	2551	2555	2563	2586	2609	2632	2655	2678	2701	2724	2747	2768	2788	2808	2827	2844	2861	2878	2897				
2538	2542	2546	2550	2554	2562	2585	2608	2631	2654	2677	2700	2723	2746	2767	2787	2807	2826	2843	2860	2877	2896				
					2561	2584	2607	2630	2653	2676	2699	2722	2745	2766	2786	2806	2825	2842	2859	2876	2895				
					2560	2583	2606	2629	2652	2675	2698	2721	2744	2765	2785	2805	2824	2841	2858	2875	2894				
					2559	2582	2605	2628	2651	2674	2697	2720	2743	2764	2784	2804	2823	2840	2857	2874	2893				
					2558	2581	2604	2627	2650	2673	2696	2719	2742												
						2580	2603	2626	2649	2672	2695	2718	2741												

Figure 3B-78: CRB Reinforcement Plan at EL. 100'-0"




Figure 3B-79: CRB Reinforcement Section Views of Slab at EL. 100'-0"




Figure 3B-80: SAP2000 View and Frame Element Numbers of Pilasters on CRB Grid Line 1 Wall




Figure 3B-81: CRB Reinforcement Detail for Pilaster Type 1




Figure 3B-82: CRB Reinforcement Detail for Pilaster Type 2





Figure 3B-83: SAP2000 View and Frame Element Numbers of T-Beams on CRB EL. 120'-0" Slab

Figure 3B-84: CRB Reinforcement Detail for T-Beam (Type 1) at EL. 120'-0"




Figure 3B-85: CRB Reinforcement Detail for T-Beam (Type 2) at EL. 120'-0"




Figure 3B-86: Reactor Building Basemat Perimeter Elements




Figure 3B-87: Reactor Building Basemat Interior Elements







Figure 3B-88: Reactor Building Reinforcement Plan of Basemat Foundation



RXB BASEMAT REINFORCEMENT PLAN AT TOC EL. 24'-0"

Figure 3B-89: Cross Section of Reactor Building Basemat Showing Reinforcing Steel



Appendix 3C Methodology for Environmental Qualification of Electrical and Mechanical Equipment**3C.1 Purpose**

This appendix describes the Environmental Qualification (EQ) program methodology for qualifying electrical equipment and mechanical equipment in accordance with the applicable requirements. The environmental qualification and seismic and dynamic qualification of electrical and mechanical equipment is addressed in Sections 3.11 and 3.10, respectively.

This appendix defines the qualification methods employed to ensure the functionality of mechanical and electrical equipment (including instrumentation and controls) required to perform a design function related to safety during the full range of normal and accident loadings (including seismic), and under all normal environmental conditions, anticipated operational occurrences, and accident and post-accident environmental conditions.

3C.2 Scope

This appendix presents the methods and procedures for qualifying electrical and mechanical equipment to a range of environments to which the equipment could be exposed during normal and abnormal conditions or design basis events (DBE).

These methods and procedures are applicable to mechanical and electrical equipment associated with systems that are essential to emergency reactor shutdown, containment isolation, reactor core cooling, and containment and reactor heat removal or are otherwise essential in preventing significant release of radioactive material to the environment.

3C.3 Introduction

This appendix specifies the plant environmental conditions to which equipment that performs a design function related to safety, listed in Section 3.11, is designed and qualified. The environmental conditions are defined for plant conditions, including normal and abnormal operating conditions, and accident conditions including post-accident operations. The accident conditions considered are assumed events that are not reasonably expected to occur over the course of plant life and that could potentially result in creating adverse environmental conditions for qualified equipment that performs a design function related to safety. The accident conditions that are postulated are based on conservative assumptions.

Pressure, temperature, relative humidity, radiation, chemical conditions, spray/wetting, and submergence are the primary environmental parameters addressed in this appendix. In accordance with 10 CFR 50.49, the environmental conditions that equipment required to perform design functions related to safety are designed and qualified to are the result of the most limiting design basis accident (DBA). The design and qualification parameters for the equipment meet the EQ program acceptance criteria. The equipment qualification parameters do not include any margins that may be required to satisfy environmental qualification requirements in other applicable code and standards. The radiation parameters in this appendix provide a conservative basis for equipment qualification and are not applicable to personnel access requirements.

The following plant areas contain equipment that performs a design function related to safety for equipment qualification:

- Reactor Building (RXB)
- Control Building (CRB)

The CRB and the electrical equipment rooms on RXB elevations 75'-0" and 86'-0" are, by design, considered mild environments.

This section provides background for the EQ program and presents a summary of the program objectives, a program outline, and definitions for terms used in this document. Section 3C.4 identifies qualification criteria. Section 3C.5 presents design specifications. Section 3C.6 presents the equipment qualification methods, which includes: type-testing, analyses, operating experience, a combination of methods, and supplemental methods to aid qualification. Section 3C.7 and Section 3C.8 describe the documentation, including data packages, test reports, and maintenance records needed to support the equipment qualification program.

3C.4 Qualification Criteria

General Design Criteria (GDC) 1, 2, 4, and 23 of 10 CFR 50, Appendix A; Quality Assurance Criteria III, XI, and XVII of 10 CFR 50, Appendix B; and 10 CFR 50.49 establish the regulatory requirements for this program.

Electrical and active mechanical equipment required to perform design functions related to safety, including instrumentation, must be qualified to operate in environments associated with design basis conditions. GDC 4 requires that structures, systems, and components that perform design functions related to safety be designed to accommodate the environmental effects associated with normal operation, maintenance, testing, and postulated accidents, such as a loss-of-coolant accident (LOCA). The primary objective of environmental qualification is to demonstrate with reasonable assurance that equipment for which a qualified life or condition has been established can perform its design function related to safety without experiencing common-cause failures before, during, and after applicable design basis events. The environmental design requirements apply to equipment required to perform their design function related to safety, including both mild and harsh environments. The environmental qualification procedures described in this appendix define the conditions for which equipment required to perform a design function related to safety must be qualified. Electrical equipment required to perform a design function related to safety located in a harsh environment is qualified in accordance with the requirements of 10 CFR 50.49. Active mechanical equipment required to perform a design function related to safety located in a harsh environment is qualified to comply with the requirements of GDC 4 by incorporating the design-basis environmental conditions into the design process. Mechanical equipment that performs an active design function related to safety during or following exposure to harsh environmental conditions is qualified in accordance with ASME QME-1, Appendix QR-B (Reference 3C-4) with the following exceptions:

QR-B5200, Identification and Specification of Qualification Requirements, (g) material activation energy.

QR-B5300 Selection of Qualification Methods for determination and recording of shelf life of nonmetallics.

QR-B5500 Documentation, (h) shelf life preservation requirements.

These exceptions are addressed with the following alternatives:

QR-B5200, Identification and Specification of Qualification Requirements, (g) material's activation energy (in conjunction with one of the above identification methods only and that is based on the material's critical failure mechanism in the intended service).

Alternative:

In accordance with Appendix QR-B5200, nonmetallic material will be qualified to perform its intended functions. Although activation energy might not be used for material identification purposes per QR-B5200, the activation energy will be applied to the thermal energy equation for determining material degradation and qualification.

QR-B5300, Selection of Qualification Methods, last paragraph which states, "The shelf life of all nonmetallics, and any applicable storage limitations, should be determined and recorded in the qualification documentation."

Alternative:

Shelf life and preservation requirements are documented in accordance with the NQA-1 2008, Requirement 13 and Subpart 2.2, in lieu of ASME QME-1 2007, Appendix QR-B5300. These requirements are not included in the environmental qualification record file, but are documented separately.

QR-B5500, Documentation, (h) shelf life preservation requirements.

Alternative:

Shelf life preservation requirements are documented in accordance with the NQA-1 2008, Requirement 13 and Subpart 2.2 in lieu of ASME QME-1 2007, Appendix QR-B5500, item (h). These requirements are not included in the environmental qualification record file, but are documented separately.

Mechanical and electrical equipment required to perform a design function related to safety located in mild environments is qualified in accordance with the provisions of GDC 4. For each piece of equipment selected for environmental qualification, the environmental parameters and the qualification process is listed in the associated equipment qualification record file (EQRF).

3C.4.1 Environmental Conditions

The environmental conditions considered in the qualification process are pressure, temperature, humidity, radiation, flooding, chemistry effects, aging and synergistic effects. The appropriate margins to be included during qualification are addressed in the description of the qualification program. The applied margin considers the most

severe effects identified through industry operational experience or those identified by analysis. The plant environmental conditions are characterized as either harsh or mild.

Harsh Environment

The environmental conditions existing before, during and after a design basis event constitute a harsh environment. The consequences of a design basis event include severe or elevated effects of pressure, temperature, humidity, radiation, chemistry, and submergence. Equipment qualified to operate in a harsh environment must operate without a loss of capability to perform their design function related to safety. The equipment requiring qualification for a harsh environment, as identified in Section 3.11, includes the following:

- equipment within the containment and outside the containment under the bioshield
- equipment required to detect, mitigate, monitor the event or those related to achieving and maintaining safe shutdown
- equipment connected to, supporting, or in the vicinity of equipment in either of the two preceding categories
- equipment subject to the environmental effects of a rod ejection accident (environmental conditions are bounded by inadvertent opening of one reactor vent valve)
- equipment subject to environmental conditions that are more severe for other parameters (e.g., temperature, pressure, humidity, flood level, spray/wetting, radiation) such as those resulting from a fuel handling accident or moderate-energy line break

Instruments and devices requiring qualification include the associated sensors, and supporting loop components. The supporting components of a sensor, such as cables, connectors, terminals, junction boxes, preamplifiers, or other signal processing equipment, is qualified for the environmental conditions at the component's location. Electrical equipment in a harsh environment is qualified according to the requirements of IEEE Std. 323-1974 (Reference 3C-2).

Mechanical equipment located in harsh environmental zones is designed to perform under appropriate environmental conditions. The primary focus for mechanical equipment concerns materials that are sensitive to environmental effects (e.g., seals, gaskets, lubricants, fluids for hydraulic systems, and diaphragms).

The harsh environmental zones within the RXB are listed in Table 3C-1.

Mild Environment

A mild environment is never more severe than the normal plant environment, including during anticipated operational occurrences. To qualify equipment operating in a mild environment, the environmental conditions are described quantitatively in the equipment specification that is provided to the vendor or supplier. Certification from the vendor or supplier that the equipment will operate in the environment

described in the specification is sufficient to qualify the equipment. Additional analysis or testing may be required for seismic and aging qualification.

IEEE Std. 323-2003 (Reference 3C-1), as endorsed by Regulatory Guide 1.209, "Guidelines for Environmental Qualification of Safety-Related Computer-Based Instrumentation and Control Systems in Nuclear Power Plants," addresses qualification of computer-based I&C systems to mild environments that may affect their performance. Parameters that can affect computer-based I&C systems are ionizing doses in a mild environment and smoke. Qualification of computer-based I&C components for the mild environment that can exist during a DBE is necessary to assure that computer-based I&C systems can perform their design functions related to safety.

Other equipment located in a mild environment with no significant aging mechanisms does not require environmental qualification. For equipment requiring seismic qualification, pre-aging prior to the seismic testing is necessary only when there is a known correlation where aging adversely affects seismic performance. (Note that EPRI NP-3326 (Reference 3C-7) indicates for most equipment there is no aging seismic correlation).

3C.4.2 Aging

Equipment is qualified for aging by testing and analysis. The qualification process considers natural aging effects that are present during the installed service life of the equipment. The objective of the qualification program is to place the test specimen(s) in an end of life condition prior to exposure to simulated accident conditions. All significant types of degradation that can affect the ability of the equipment to perform its design function related to safety during or following exposure to harsh environmental conditions must be considered in the qualification process. Typical aging mechanisms that are addressed as part of a qualification test program includes:

- Thermal aging or thermal degradation
- Radiation aging
- Cyclic aging or wear related degradation

Periodic inspection, testing, and calibration can monitor equipment for aging effects which are otherwise difficult to quantify or are not able to be fully simulated by the accelerated aging applied during a qualification test program.

The concept of condition based qualification may be used to supplement the concept of qualified life. As the qualified life of the equipment approaches the end of its theoretical qualified life, periodic condition monitoring may be implemented to determine if actual aging is occurring at a slower rate such that further qualified service is possible based on the condition monitoring results. The use of condition monitoring is tied to the ability to monitor one or more condition indicators to determine whether equipment remains in a qualified condition. The trend of the condition indicator is determined during the performance of age conditioning of the test specimen during the qualification testing. The condition indicator must be measurable, linked to

functional degradation of the qualified equipment, and have a consistent trend from unaged through the limit of the qualified pre-accident condition.

Thermal Aging

As stated in NUREG-0588 (Reference 3C-16), the Arrhenius methodology is considered an acceptable method of addressing accelerated thermal aging. The development of the accelerated thermal aging parameters and activation energies shall consider or be based on the applicable guidance in IEEE Std. 1 (Reference 3C-9), IEEE Std. 98 (Reference 3C-10), IEEE Std. 99 (Reference 3C-11), IEEE Std. 101 (Reference 3C-12), and IEEE Std. 1205 (Reference 3C-13). The selection of activation energies shall be based on material properties that are representative of the design function related to safety of the item. Justification shall be provided for any use of Thermogravimetric Analysis to establish an activation energy that demonstrates that the resulting qualified life is conservative or representative of actual degradation under normal service conditions.

The minimum acceptable accelerated aging time shall be greater than 150 hours. Thermal aging of materials where diffusion limited oxidation effects have the potential to not fully simulate actual thermal aging degradation effects, the thermal acceleration rates are adjusted to minimize or otherwise account for these effects.

Radiation Aging

Radiation aging may be performed separately from the accident radiation exposure or the accident radiation exposure may be performed as part of the radiation aging. Radiation aging shall be performed using either a Cobalt-60 or Cesium-137 source. The maximum acceptable dose rate is 1.0 MRad/hr (10 k Gr/hr). For radiation aging of materials where diffusion limited oxidation effects have the potential to not fully simulate actual aging degradation effects from irradiation, the dose rates should be adjusted to minimize or otherwise account for these effects.

Cyclic Wear Aging

Cyclic wear aging is used to simulate electrical or mechanical degradation of the equipment due to normal operation of the equipment. This aging is intended to simulate wear related degradation as well as fatigue effects. The definition of the required number of cycles to be simulated during the qualification test program shall consider expected service conditions and be based on a conservative estimation of equipment cycles during power operation, module startup, module shutdown, outages, maintenance activities, surveillance activities, transients, anticipated operational occurrences, and accident conditions.

Qualified Life Objective

The qualified life objective shall be based on a specified set of harsh environment service conditions. Pre-service conditions shall be considered if significant aging occurs before equipment is placed into service. Qualified life can be demonstrated by age conditioning a test sample to simulate effects of significant aging mechanisms during a time equal to the qualified life objective. An adjunct to establishing a qualified life objective is to establish an end-condition objective of equipment condition indicators

that correlate to the ability of equipment to perform its design function related to safety. In this case, the end condition is the basis of qualification, and the time to reach that end condition in service may be more or less than the qualified life established by age conditioning. The fundamental objective of qualified life of equipment ensures that the equipment possesses the capability to perform its required design function(s) related to safety at the end of the qualified life with demonstrated margin to failure.

Design Life

Equipment in mild environment locations is expected to perform satisfactorily during the design life (Reference 3C-1) for the specified set of mild environmental service conditions. The design life of equipment is obtained from manufacturer's literature. Surveillance or trending programs also assist in verifying the design life or the need for re-evaluation.

Shelf Life

The equipment and material controlled storage program complies with the requirements of 10 CFR 50, Appendix B. This program verifies that equipment is handled and stored in accordance with the manufacturer's or vendor's recommendations, the engineering requirements, or general industry practices. In addition, the shelf life of non-metallic materials is considered and used in specifying the maximum allowable time a component or material can be stored. Materials are removed and replaced when they reach their established shelf life.

Qualified Life

Equipment in harsh environment locations is expected to perform satisfactorily during the qualified life (Reference 3C-16) for the specified set of harsh environmental service conditions for the required operating time with margin to failure. The margin included ensures that the accident function can be performed if the accident occurred just prior the item's replacement at the end of the qualified life.

3C.4.3 Synergistic Effects

Environmental qualification in accordance 10 CFR 50.49 requires that synergistic effects be considered. Regulatory Guide 1.89, Revision 1, Section C.5.a provides further guidance for addressing synergisms.

The synergistic relationship between multiple stresses usually cannot be deduced from physical principles; rather, an experimental approach must be employed. Synergistic stresses usually require extensive testing to reveal their magnitudes, since most interaction effects are minute by comparison to the primary effects, and thus require significantly more experimental evidence to identify. Current research, as referenced below, indicates that synergistic effects can typically be categorized under two main headings:

- Test sequence effects - The sequence in which radiation and thermal aging exposures occur is an important consideration. Radiation combined with elevated temperatures or radiation followed by elevated temperatures may produce more

material degradation than when thermal aging precedes radiation exposure (NUREG/CR-3629 (Reference 3C-14)).

- Radiation dose rate effects - For many materials, it has been observed that lower dose rates produce more degradation than a higher dose rate for the same total applied dose (NUREG/CR-2157 (Reference 3C-15)).

Test Sequence Effects

An important aging consideration is the possible existence of synergistic effects when multiple stress environments such as radiation and elevated temperatures, are applied simultaneously. Currently, sequential exposure is the only commercially available means of testing; no commercial facility offers simultaneous steam and radiation exposure. Although sequential and simultaneous tests can produce variances in degradation, the differences tend to be minor compared to total degradation. The possibility that significant synergistic effects may exist is addressed by the using the "worst-case" aging sequence, conservative accelerated aging parameters and conservative, DBE test levels to provide confidence that any synergistic effects are enveloped.

Radiation Dose Effects

The need for qualification due to radiation exposure is evaluated for each piece of equipment. The radiation environment is based on the type of radiation, the total dose expected during normal operation over the installed life of the equipment, and the radiation environment associated with the most severe design basis accident during or following which the equipment is required to remain functional.

3C.4.4 Operating Time

Equipment required to be environmentally qualified has one or more of the following design functions related to safety: reactivity control, decay heat removal, post-accident monitoring, containment isolation, maintenance of RCS pressure boundary integrity, control room habitability, event severity mitigation or system support functions. For each function, a period of operability is assigned that ranges from less than 1 hour to a maximum of 2400 hours. The assignment of these post accident operating times is separated into the five different time frames that are related to plant status or system functional requirements. These operating time designations and durations are summarized in Table 3C-4.

Equipment that performs its design function related to safety prior to significant changes in its environment may be qualified for shorter durations. In accordance with Regulatory Guide 1.89, justification for shorter duration includes:

- the consideration of a spectrum of pipe break sizes
- the potential need for the equipment later in an event or during recovery operations
- Subsequent failure of the equipment is shown to not be detrimental to plant safety or to mislead the operator

Post-accident operating times for equipment to be qualified shall be specified in the EQ Master List and as shown in Table 3.11-1.

3C.4.5 Performance Criterion

The qualification test program demonstrates the capability of the equipment to meet the design function related to safety performance requirements defined in the EQRF (Section 3C.8). As stated previously, the primary objective of qualification is to demonstrate that equipment, for which a qualified life or condition has been established, can perform its design functions related to safety without experiencing common-cause failures before, during, and after applicable DBEs. The continued capability for this equipment and its interfaces (Reference 3C-16) to meet or exceed its specification requirements is provided through an operational program that includes, but is not limited to, design control, quality control, qualification, installation, maintenance, periodic testing, and surveillance.

3C.4.6 Margin

The purpose of using margin in the qualification program is to account for commercial production variability, errors in establishing satisfactory performance, and errors in experimental measurements, thereby providing greater assurance that the equipment can perform under the specified service conditions. Table 3C-5 presents the margins for various environmental parameters. The margins shown in the table are those recommended in IEEE Std. 323 (Reference 3C-1).

3C.4.7 Treatment of Failures

Any failure to meet the acceptance criteria is analyzed to determine the cause. Equipment modifications, equipment retesting, or equipment use limitations are imposed as necessary to address the failure.

3C.5 Design Specifications

The equipment design specification identifies the applicable codes and standards, required operating times, performance requirements, design functions related to safety, operational service conditions, environmental service conditions, accepted methods of qualification, and acceptance criteria. The design specification also provides the basis for establishing the EQ of the specific equipment or the family of equipment.

Environmental Qualification of Electrical Equipment

The environmental conditions for which equipment is qualified are the most severe conditions resulting from the DBE for which the equipment is required to perform its design function related to safety. The equipment qualification life of electrical and mechanical equipment is established as a conservative 60 years unless otherwise noted on the equipment's specification. Periodic inspection and testing shall be used during the life of the equipment to verify its ongoing qualification.

The amount of time, after a design basis event, for which some equipment must remain functional, may be a few minutes or several hours depending on its design function related to safety.

Environmental Qualification of Mechanical Equipment

Both passive and active mechanical equipment (Reference 3C-3) is qualified according to the criteria and methodology described in this document. Non-metallic components like O-rings, seals, gaskets, and lubricants for mechanical equipment with a design function related to safety are also qualified in accordance with these criteria. Equipment that only has the design function related to safety of maintaining its structural integrity, for support or to protect the integrity of a pressure boundary, is qualified in accordance with the requirements specified in Section 3.11. The design specification will also identify if qualification to ASME QME-1 is required for active mechanical equipment.

3C.5.1 Normal Operating Conditions

Normal operating conditions are summarized in Table 3C-6. For qualification under normal operating conditions, the equipment is mounted, connected, interfaced, and operated in a manner that simulates its normal inservice conditions, and the equipment's design functions related to safety are demonstrated during exposure to normal service conditions. Data are recorded for later reference as required by Section 3C.8.

Normal Radiation Dose

The normal radiation integrated doses for equipment are based on the maximum normal reactor coolant system (RCS) radionuclide activities and system parameters to determine bounding normal cumulative doses both inside and outside of the containment, as shown in Table 3C-6. These values were determined based on 60 years (bounding environmental qualification life) of continuous operation and steady-state operating conditions, and take into account radiation exposure because of recirculatory fluid for equipment outside the containment.

The integrated doses shown in Table 3C-6 represent the direct dose to equipment and bound any additional airborne doses.

3C.5.2 Seismic

The methods, including applicable seismic loads, used for the seismic qualification of mechanical, electrical, and I&C equipment are addressed in Sections 3.7 and 3.10.

3C.5.3 Containment Test Environment

The design pressure of containment is 1050 psia, though it is hydrostatically tested at the manufacturing facility at a hydrostatic pressure of 1298 psig (1.25 times design pressure). Subsequent testing will be conducted as described in Section 6.2.6.

3C.5.4 Design Basis Event ConditionsDesign Basis Events (DBE)

Design basis events are defined as normal operation, including anticipated operational occurrences, and design basis accidents as analyzed within the scope of Section 3.6 and Chapter 15.

Design-Basis Accidents (DBAs)

The design basis accidents were reviewed and evaluated to determine which DBAs are addressed in FSAR Chapter 15. Based on this review, the following DBAs are evaluated to determine the mechanical and electrical equipment that requires environmental qualification.

FSAR Section 15.1.5 - steam system piping failure inside and outside of containment. This covers main steam line breaks (MSLB) inside and outside of containment. For the purpose of environmental qualification, main steam line breaks are considered inside the CNV even though the main steam piping is classified as leak before break (LBB).

FSAR Section 15.2.8 - feedwater system pipe break inside and outside of containment. This covers feedwater line breaks (FWLB) inside and outside of containment. For the purpose of environmental qualification, feedwater line breaks are considered inside the CNV even though the FW piping is classified as leak before break (LBB).

FSAR Section 15.4.8 - rod ejection accident (REA) reflects a potential break in the RCS pressure boundary. The equipment relied upon to mitigate this accident is the same as that used for the spectrum of small break loss of coolant accidents addressed by FSAR Section 15.6.5. The REA is analyzed as a reactivity event.

FSAR Section 15.6.5 - loss of coolant accidents (LOCA) from spectrum of postulated pipe breaks within the RCS pressure boundary inside and outside of containment. There are no large break LOCA events for the NuScale design. The small break LOCAs are the result of CVCS pipe rupture events that are postulated inside or outside of containment. The iodine spike design basis source term described in FSAR Section 15.0.3 is used in the EQ program as a bounding surrogate for the radiological consequences of DBEs that result in primary coolant entering the containment.

Note: The core damage event described in FSAR Section 15.10 is a special event that is outside of the scope of the EQ program.

FSAR Section 15.7.4 - radiological consequences of fuel handling accidents. This covers the FHAs within the RXB pool area.

Infrequent Events (IE)

FSAR Section 15.6.2 - radiological consequences of failure of small lines carrying primary coolant outside of containment. Similar to FSAR Section 15.6.5, this covers chemical and volume control systems (CVCS) pipe rupture events that are postulated inside or outside of containment.

Other Design Basis Events

FSAR Section 3.6 - high energy line breaks (HELB) outside containment. This covers HELB outside of containment that are not already addressed by FSAR Sections 15.1.5, 15.2.8, or 15.6.5, such as the postulated rupture of the module heatup system (MHS) piping in the gallery areas of the RXB.

FSAR Section 3.6 - moderate energy line breaks (MELB) outside containment.

Normal and Bounding Conditions

Containment vessel and reactor building pressure and humidity experienced during the indicated DBE are shown in Table 3C-7. Equipment that is required to perform a design function related to safety, and could potentially be subjected to the design basis environments, is qualified to these conditions for the required operating time.

RPV and containment vessel metal temperatures in the lower (liquid) space with corresponding liquid temperatures for the bounding DBAs are shown on Figure 3C-1. RPV and containment vessel metal temperatures in the upper (vapor) space with corresponding vapor temperatures for the bounding DBAs are shown on Figure 3C-2. The average vapor temperatures at the top of module for the bounding DBAs, and assuming a vented bioshield, are shown on Figure 3C-3. Refer to Section 3.7.3 for a description of the bioshield. The maximum vapor temperatures for elevation 145' in the RXB from the same bounding DBAs are shown on Figure 3C-4.

3C.5.5 Design Basis Event Radiation Doses

NuScale Topical Report, TR-0915-17565-P-A (Reference 3C-5) provides the methodology for determining the accident source terms for equipment following design basis events. The limiting event and associated source terms from the design basis accidents discussed above were used to determine total integrated doses for equipment qualification.

The accident conditions integrated doses within the reactor building were determined using the maximum normal core radionuclide inventory. The maximum normal core inventory bounds the equilibrium cycle burnup for the NuScale Power Module reactor and is representative of operating cycle characteristics for environmental qualification purposes. The required dose used for environmental qualification considers the total integrated dose consisting of the normal dose plus the accident dose corresponding to the required post-accident operating time. The normal dose considers gamma and neutron effects, while the accident dose considers the gamma and beta dose that is expected at the equipment location.

Based on the above, the integrated doses following a design basis event are shown in Table 3C-8.

For discussion on gamma and beta radiation effects, refer to Section 3.11.5.

3C.6 Qualification Methods

A qualification program plan defines tests, inspections, performance evaluation, acceptance criteria, and required analysis to demonstrate that, when called upon, the qualified equipment can perform its specified design function(s) related to safety for the required post-accident operating time with margin to failure.

This section describes the methodologies used to qualify equipment. Alternative approaches are available; however, the equipment vendor selects the methods best applied to the equipment. The result is an auditable record demonstrating that the equipment can perform its design function related to safety, under the specified service conditions, if an accident occurred at anytime during its Qualified Life.

IEEE Std. 323-2003 (as endorsed by RG 1.209 for computer-based digital I&C equipment in a mild environment) and IEEE Std. 323-1974 allow various qualification methods (e.g., testing, analysis, operating experience, or a combination of methods) as applicable to the equipment scope. Although type testing is the preferred method of qualification, a qualification program usually involves some combination of these methods. The qualification methods used depend on factors such as the:

- materials used in construction of the equipment
- applicable normal, abnormal, and DBE service conditions
- operational requirements during and after accidents
- nature of the required design function(s) related to safety
- size of the equipment
- dynamic characteristics of the expected failure modes (e.g., structural or functional)

In general, analysis may be used to supplement test data.

3C.6.1 Type Testing

The type test shall demonstrate that equipment performance meets or exceeds the design function related to safety requirements. Type test conditions shall meet or exceed specified service conditions. Appropriate margin shall be added to design basis event parameters if not otherwise included in the specified service conditions.

The type test program is designed to demonstrate that the equipment can perform its design functions related to safety within the accuracy and response time requirements applicable for normal, abnormal, and DBE service conditions. The type test consists of a demonstration of design functions related to safety under a planned sequence of environmental tests both before and after age conditioning (Reference 3C-1). Regulatory Guide 1.180 specifies electromagnetic compatibility design requirements for electromagnetic and radio-frequency interference and power surges for equipment and is independent of the EQ Program.

A test plan is prepared at the beginning of the test program, which includes the qualification methodology, its intent and purpose, and a description of the tests in

sufficient detail to demonstrate compatibility with specified requirements. As a minimum, the plan includes:

- applicable codes and standards
- equipment description
- number of test specimens
- acceptance criteria
- failure definition
- service conditions (environmental and operational)
- testing sequence
- aging technique with justification
- test levels that envelope or equal the service conditions
- parameters to be monitored
- test equipment to be used
- mounting and connection methods
- qualified life goal and design life
- documentation to be maintained

Similarity

Analysis may be employed to demonstrate that the test results obtained for one piece of equipment are applicable to a similar piece of equipment. Documentation of this analysis conforms with the guidelines in IEEE Std. 323-1974, IEEE Std. 323-2003 and IEEE Std. 627-1980 (Reference 3C-8).

3C.6.2 Analysis

Analytical techniques are used in qualification in a variety of ways, including evaluating aging effects, demonstrating qualification for particular DBE conditions, and evaluating differences between installed and tested equipment. Qualification by analysis requires a logical assessment or a valid mathematical model of the equipment to be qualified. When quantitative analysis is used for qualification, it needs to be supported by test data, operating experience, or physical laws of nature to demonstrate that the equipment can perform its design function(s) related to safety under specified conditions.

3C.6.3 Operating Experience

Operating experience can serve as a basis for determining or modifying the Qualified Life of equipment, including systems, elements, components, modules, and other constituent parts.

Auditable data are maintained for environmental qualification of equipment qualified on the basis of operating experience that addresses the following criteria:

- the equipment cited for operating experience is identical or justifiably similar to the equipment to be qualified
- the equipment cited for operating experience has operated under service conditions that equal, or exceed in severity, service conditions for which the equipment is to be qualified, and has performed its design function related to safety under these conditions
- the normal and abnormal service condition requirements were satisfied prior to the occurrence of the DBE conditions
- margin has been considered in determining the accident service conditions for the equipment to be qualified

Operating experience has been used to address the qualification of mechanical equipment principally because of the severe process conditions experienced by mechanical equipment during normal service applications.

Operating experience has been used on an infrequent basis to qualify electrical equipment to harsh environments, principally because LOCA-type pipe break accidents rarely occur. Therefore, qualification of electrical components can be qualified using operating experience as a basis when used with a combination of other methods per Section 3C.6.4.

When the above criteria are met the equipment may be qualified.

3C.6.4 Combination of Methods

Equipment may be qualified by test, analysis, previous operating experience, or any combination of these three methods. Using a combination of methods may be appropriate under a variety of circumstances, such as:

- equipment is too complex for analysis alone or too large for testing alone
- test data are available on samples of similar design and materials that are of different sizes, so extrapolation may be possible
- verification of a mathematical model using partial type test to determine mode shapes and resonant frequencies
- operating experience provides the basis for developing simulated aging techniques
- analysis of an assembly to determine the environment to which components are to be tested
- two subassemblies that have been tested and qualified separately are combined into a complete assembly, and analysis of certain parameters (e.g., individual subassemblies' error rates and response times) demonstrates that the combination is also qualified

The combined qualification demonstrates that the equipment can perform its design function related to safety under normal, abnormal, and DBE service conditions throughout its Qualified Life. Combined qualification provides auditable data by which the various primary qualification methods may be brought together to satisfy the qualification program requirements.

3C.7 Equipment Qualification Maintenance Requirements

The equipment qualification maintenance requirements consider condition monitoring and preventive maintenance activities to ensure effective aging management.

These maintenance requirements documents typically consist of the following sections:

1) Equipment Description

Tag numbers, equipment numbers, description of function, location, manufacturer, and model number; general information for completing maintenance orders.

2) Technical References

Reference information useful for preparing for or conducting maintenance.

3) Installation and Maintenance Requirements

a) Installation Requirements

Tasks essential to achieving installations that conform to EQ requirements; derived from vendor technical manuals and equipment EQ test reports.

b) Electrical Connection Interface and Data Requirements

The requirements for environmentally qualified connections; the information represents the current physical configuration.

c) Maintenance Requirements

Tasks and their frequencies necessary to maintaining the equipment's EQ; derived from vendor technical manuals and equipment EQ test reports; to be incorporated into the plant surveillance test procedures or preventive maintenance program, as applicable.

d) Post-Maintenance Test Requirements

Testing to be performed after EQ maintenance is completed.

e) Condition Monitoring Requirements

Monitoring required to detect and assess degradation of materials or performance; derived from review of qualification documentation, evaluation of degrading mechanisms, and engineering judgment.

4) Replacement Parts

The description, manufacturer, and model number of parts needed to maintain EQ equipment; includes items routinely used in the maintenance activity.

3C.7.1 On-going Qualification

The equipment qualification program may employ on-going qualification, though this method is not acceptable as a sole means for qualifying equipment for DBE conditions. Its use is generally limited to areas subjected to mild environment conditions or as a method in which to modify the Qualified Life that was established using another qualification method. Supplemental test, analysis, or experience data to address equipment qualification and performance during and after a seismic DBE is also required.

3C.8 Documentation

The equipment qualification program documentation consists of equipment qualification data packages, equipment qualification test reports, and qualification maintenance requirements.

Equipment Qualification Record File

The EQRF for each equipment item contains the documentation that demonstrates that the equipment or system is environmentally qualified for its application, and can accomplish its specified design functions related to safety. An equipment item refers to equipment categorized by manufacturer and model, which is representative of identical or similar equipment in plant areas potentially exposed to the same bounding environmental conditions during and after a design basis event. Documentation that supports EQ for the equipment is compiled in the EQRF or referenced therein. The elements of the EQRF include: equipment identification, interfaces, qualified life, design functions related to safety, service conditions (e.g., normal, abnormal, DBE), qualification program plan, and qualification program implementation following the guidance of IEEE Std. 323-1974 (Reference 3C-2) for harsh environment applications and IEEE Std. 323-2003 (Reference 3C-1) for mild environment applications.

Equipment Qualification Test Reports

The equipment qualification test report is prepared by the equipment vendor or an independent testing laboratory. This report documents the tests that demonstrate the capability to meet specified functional requirements under specified environmental conditions and operational parameters. These tests subject one or more equipment samples to conditions designed to simulate normal, abnormal, containment test, DBE, and post-DBE conditions, as applicable.

3C.9 References

- 3C-1 Institute of Electrical and Electronics Engineers, "Qualifying Class 1E Equipment for Nuclear Generating Stations," IEEE Standard 323-2003, Piscataway, NJ.

- 3C-2 Institute of Electrical and Electronics Engineers, "IEEE Standard for Qualifying Class IE Equipment for Nuclear Power Generating Stations," IEEE Standard 323-1974, Piscataway, NJ.
- 3C-3 Institute of Electrical and Electronics Engineers, "IEEE Recommended Practice for Seismic Qualification of Class 1E Equipment for Nuclear Power Generating Stations," IEEE Standard 344-2004, Piscataway, NJ.
- 3C-4 American Society of Mechanical Engineers, "Qualification of Active Mechanical Equipment Used in Nuclear Power Plants," ASME QME-1-2007, New York, NY.
- 3C-5 NuScale Power, LLC, "Accident Source Term Methodology," TR-0915-17565-P-A, Revision 4.
- 3C-6 Institute of Electrical and Electronics Engineers, "IEEE Standard Criteria for Accident Monitoring Instrumentation for Nuclear Generating Stations," IEEE Standard 497-2002, Piscataway, NJ.
- 3C-7 Electric Power Research Institute, "Correlation Between Aging and Seismic Qualification for Nuclear Plant Electrical Components," EPRI NP-3326, EPRI, Palo Alto, CA, 1983.
- 3C-8 Institute of Electrical and Electronics Engineers, "IEEE Standard for Design Qualification of Safety Systems Equipment Used in Nuclear Power Generating Stations," IEEE Standard 627-1980, Piscataway, NJ.
- 3C-9 Institute of Electrical and Electronics Engineers, "General Principles for Temperature Limits in the Rating of Electrical Equipment and for the Evaluation of Electrical Insulation," IEEE Standard 1-2000, Reaffirmed 2005, Piscataway, NJ.
- 3C-10 Institute of Electrical and Electronics Engineers, "The Preparation of Test Procedures for the Thermal Evaluation of Solid Electric Insulating Materials," IEEE Standard 98-2016, Piscataway, NJ.
- 3C-11 Institute of Electrical and Electronics Engineers, "Recommended Practice for the Preparation of Test Procedures for the Thermal Evaluation of Insulation Systems for Electric Equipment," IEEE Standard 99-2007, Piscataway, NJ.
- 3C-12 Institute of Electrical and Electronics Engineers, "IEEE Guide for the Statistical Analysis of Thermal Life Test Data," IEEE Standard 101-2004, Reaffirmed 2010, Piscataway, NJ.
- 3C-13 Institute of Electrical and Electronics Engineers, "Guide for Assessing, Monitoring, and Mitigating Aging Effects on Class 1E Equipment Used in Nuclear Power Generating Stations and Other Nuclear Facilities," IEEE Standard 1205-2014, Piscataway, NJ.
- 3C-14 U.S. Nuclear Regulatory Commission, "The Effect of Thermal and Irradiation Aging Simulation Procedures on Polymer Properties," NUREG/CR-3629, April 1984.

- 3C-15 U.S. Nuclear Regulatory Commission, "Occurrence and Implications of Radiation Dose-Rate Effects for Material Aging Studies," NUREG/CR-2157, Sandia National Laboratories, June 1981.
- 3C-16 U.S. Nuclear Regulatory Commission, "Interim Staff Position on Environmental Qualification of Safety Related Electrical Equipment," NUREG-0588, Revision 1, July 1981.

Table 3C-1: Environmental Qualification Zones - Reactor Building

EQ Zone⁽¹⁾	Description	Environment
A	Room 010-022, Containment Vessel - bottom of containment (6") to bottom of upper core plate (142")	Harsh
B	Room 010-022, Containment Vessel - bottom of upper core plate (142") to bottom of riser transition (236")	Harsh
C	Room 010-022, Containment Vessel - bottom of riser transition (236") to bottom of baffle plate (587")	Harsh
D	Room 010-022, Containment Vessel - bottom of baffle plate (587") to top of pressurizer (697")	Harsh
E	Room 010-022, Containment Vessel - top of pressurizer (697") to bottom of torispherical head (841")	Harsh
F	Room 010-022, Containment Vessel - bottom of torispherical head (841") to top of containment (904")	Harsh
G	Room 010-022, Module pool bay vapor space - outside containment and under the BioShield (Top of Module) (Figure 1.2-19: Reactor Building East and West Section View)	Harsh
H	Rooms 010-022, 010-422, and 010-423 above pool level to ceiling (RXB Pool Room Vapor Space) (Figure 1.2-16: Reactor Building 100'-0" Elevation thru Figure 1.2-18: Reactor Building 145'-6" Elevation)	Harsh
I	Room 010-022, 010-023 and 010-024 up to top of pool level (RXB Pool Room liquid space) (Figure 1.2-10: Reactor Building 24'-0" Elevation)	Harsh
J	Rooms 010-101, 010-102, 010-103, 010-104, 010-005, 010-106, 010-107, 010-112, 010-114, 010-115, 010-116, 010-117, 010-118, 010-119, 010-120, 010-121, 010-122, 010-123, 010-125, 010-126, 010-127, 010-128, 010-129, 010-130, 010-131, 010-133, 010-134 (Figure 1.2-12: Reactor Building 50'-0" Elevation)	Harsh
K	Rooms 010-201, 010-202, 010-203, 010-204, 010-005, 010-206, 010-207, 010-208, 010-242, 010-275 (Figure 1.2-14: Reactor Building 75'-0" Elevation)	Harsh
L	Rooms 010-201, 010-202, 010-203, 010-204, 010-005 (Figure 1.2-15: Reactor Building 86'-0" Elevation)	Harsh
M	Rooms 010-005, 010-401, 010-402, 010-403, 010-404, 010-405, 010-406, 010-407, 010-408, 010-409, 010-410, 010-411, 010-412, 010-414, 010-415, 010-416, 010-417, 010-418, 010-419, 010-420 (Figure 1.2-16: Reactor Building 100'-0" Elevation)	Harsh
N	Rooms 010-005, 010-501, 010-502, 010-503, 010-504, 010-506, 010-507, 010-508, 010-509, 010-510 (Figure 1.2-17: Reactor Building 126'-0" Elevation)	Harsh

Note:

- 1) EQ Zones listed are those areas within the Reactor Building that are harsh environments and contain equipment that requires environmental qualification.

Table 3C-2: Designated Harsh Environment Areas

Area	Basis	Comment/Remarks
EQ Zones A, B, C, D, E and F	Harsh environment as a result of primary and secondary HELBs potential to occur in this area Total integrated dose (60 yrs + accident) > 1.0E4 Rads	Inaccessible post-accident and during normal operation.
EQ Zone G	Harsh environment as a result of primary and secondary HELBs potential to occur in this area Total integrated dose (60 yrs + accident) > 1.0E4 Rads	Inaccessible post-accident
EQ Zone H	Harsh environment as a result of primary and secondary HELBs potential to occur in the Top of Module (TOM) $\geq 120^{\circ}\text{F}$ and $> 18^{\circ}\text{F}$ increase above normal operating conditions with RH $\geq 85\%$	Harsh due to HELBs potential to occur under the bioshield
EQ Zone I	Harsh environment as a result of primary and secondary HELBs potential to occur in the TOM Total integrated dose (60 yrs + accident) > 1.0E4 Rads	
EQ Zones J, K, L, M, and N	These areas will contain high and moderate energy piping. Total integrated dose exceed > 1.0E3 Rads (60 year normal + 30 day accident dose) for equipment with solid state circuitry and > 1.0E4 Rads (60 year normal + 30 day accident dose) for electrical or mechanical equipment.	Harsh by preliminary design for HELBs. Zone J is harsh due to post-accident radiological equipment qualification requirements exceeding source term doses of > 1.0E4 Rads (60 year normal + 30 day accident dose) for electrical or mechanical equipment. Zone M is harsh due to post-accident radiological equipment qualification requirements exceeding source term doses of > 1.0E3 Rads (60 year normal + 30 day accident dose) for equipment with solid state circuitry.

Table 3C-3: Designated Mild Environment Areas

Area	Basis	Comments/Remarks
CRB	<p>No harsh environment DBA or IE are postulated to occur in the control building.</p> <p>Total integrated dose (60 years + accident $\leq 1.0E3$ Rads)</p> <p>Control building does not contain any high energy piping systems ($>200F$ or > 275 psig) and flooding analysis demonstrates that no equipment designed to perform a function related to safety is submerged.</p> <p>Max temp is $< 120F$ with humidity $< 85\%$</p>	Satisfies MILD environment criteria
<p>EDS equipment rooms on RXB elev. 75' Gallery areas, specifically:</p> <p>EDSS battery rooms</p> <p>MPS rooms</p> <p>EDSS SWGR rooms</p>	<p>No harsh environment DBA or IE are postulated to occur in these rooms.</p> <p>Total integrated dose (60 years + accident $\leq 1.0E3$ Rads)</p> <p>Max temp is $< 120F$ with humidity $< 85\%$</p>	Satisfies MILD environment criteria
Diesel Generator Building	<p>No harsh environment DBA or IE occur in this building.</p> <p>Total integrated dose (60 years + accident $\leq 1.0E3$ Rads)</p> <p>Diesel Generator Building Ventilation maintains DGB temperatures within design specification for backup diesel generator (BDG).</p>	<p>Satisfies MILD environment criteria</p> <p>Supports PAM function beyond 72 hours</p>

Table 3C-4: Equipment Post-Accident Operating Times

Description	Time Frame (hours)	Actions Accomplished	Basis
Short Term (ST)	≤ 1	<ul style="list-style-type: none"> • Event Detection • Initiation of Trip and ESF actuation • Achievement of Hot Shutdown 	Note 1
Intermediate Term (IT)	$ST \leq IT \leq 36$	<ul style="list-style-type: none"> • Achievement of Safe Shutdown • RCS Depressurization and Cooldown • Maintain Fission Product Barrier Integrity 	Note 2
Long Term (LT)	$IT \leq LT \leq 72$	<ul style="list-style-type: none"> • Maintaining Safe Shutdown • Maintain Fission Product Barrier Integrity 	Note 3
Extended	$LT \leq \text{Extended} \leq 720$	<ul style="list-style-type: none"> • Maintaining Safe Shutdown • Maintain Fission Product Barrier Integrity 	Note 4
Extended PAM	$LT \leq \text{Extended} \leq 2400$	<ul style="list-style-type: none"> • Monitoring of Fission Product Barrier Integrity 	Note 5

Notes:

1. The Short Term post-accident operating time (PAOT) is assigned to components associated with event detection, reactor trip initiation, or Engineered Safety Features (ESF) actuation that occur very early in the accident sequence. This includes the Module Protection System (MPS) initiation of:
 - Reactor Trip,
 - Containment Isolation,
 - Decay Heat Removal System (DHRS) actuation,
 - Emergency Core Cooling System (ECCS) actuation,
 - De-energizing the Pressurizer Heaters, and
 - Isolation of demineralized water
 Short Term actions are also associated with the achievement of Hot Shutdown.
2. Intermediate Term actions are associated with the achievement of Safe Shutdown using DHRS. The Intermediate Term time frame extends to 36 hours and is used to qualify equipment that is relied upon to support the ECCS hold for up to 24 hours. Examples of equipment assigned an Intermediate Term PAOT includes:
 - Reactor Vent Valves
 - Reactor Recirculation Valves
3. The Long Term time frame extends to 72 hours. This category is considered the maximum post-accident operating time for HELB and MELB events outside containment in areas that are readily accessible after break termination or isolation. Examples of equipment assigned to this category includes the following:
 - Equipment that is relied upon to mitigate a HELB or MELB outside containment, that are located outside of the top of module area (outside containment and under BioShield).
 - Highly Reliable DC Power System (EDS) Batteries for separation groups B and C which are sized to support an extended loss of AC power for up to 72 hours.
4. The Extended time frame of 720 hours represents the maximum post-accident operating time used to qualify equipment that is relied upon to maintain a safe shutdown condition. Equipment assigned to this post-accident operating time category are typically located inside the CNV or in an inaccessible area outside of containment, such as under the BioShield.

Table 3C-4: Equipment Post-Accident Operating Times (Continued)

This duration is selected to align with 10 CFR 50 Appendix J, 10 CFR 50 Appendix K, as well as control room habitability analysis timeframes. This duration is considered appropriate for an advanced light water reactor design that employs passive means to maintain a safe shutdown condition.

This duration is also applicable to equipment assigned to support the following, including equipment located in the top of module area (outside containment and under BioShield) or in the Reactor Pool / Pool Bays:

- Containment Integrity
- RCS pressure boundary integrity
- Decay Heat Removal/Emergency Core Cooling (DHRS/ECCS)
- Mitigation of Fuel Handling Accidents
- Supporting Control Room Habitability
- PAM Type B and D variables

5. Extended PAM category specifically applies to RG 1.97 Type C variables and is consistent with Reference 3C-6.

Table 3C-5: EQ Program Margin Requirements

Parameter	Required Margin ⁽¹⁾	Notes
Peak Temperature	+15°F	For accident profile.
Peak Pressure	+ 10% of gauge, but not more than 10 psig	
Radiation	+10%	On accident dose only.
Power Supply Voltage	±10%	Of rated value, not to exceed equipment design limits.
Equipment Operating Time	+10%	For the period of time the equipment is required to operate following the start of a DBE. See also Section 3C.4.5 and Table 3C-4.
Seismic Vibration	+10%	Margin added to acceleration requirements at the mounting point of equipment.
Line Frequency	N/A	Line frequency margin is N/A because the relied upon electrical power is from EDSS (DC power).
Time	+10%	In addition to the period of time the equipment is required to be operational following the DBE.
Environmental Transients	2 or more	The initial transient and the dwell at peak temperature shall be applied at least twice

Notes:

1. The margins apply unless it can be shown that the derivation of environmental conditions contain conservatisms that can be quantified to show that appropriate margin exists.

Table 3C-6: Normal Operating Environmental Conditions

Zone	Temperature (°F)	Pressure (psig) (Nominal)	Maximum Relative Humidity (%) ⁽¹⁾	60 Years Integrated N Dose (Rads)		60 Years Integrated γ Dose (Rads) (Includes fission γ , N- γ , coolant)		Water Level (ft. above RXB pool floor)
A	487 (lower RPV wall)	<(-14.6) ⁽²⁾	0	2.41E8		6.21E10		47' (inside CNV for refueling)
B	491 (RPV wall) 295 (CNV wall)	<(-14.6) ⁽²⁾	0	5.93E8		3.11E10		47' (inside CNV for refueling)
C	551 (RPV wall)	<(-14.6) ⁽²⁾	0	9.44E8		2.69E7		47' (inside CNV for refueling)
D	618 (outside top of PZR) 295 (CNV wall)	<(-14.6) ⁽²⁾	0	4.92E7		2.49E6		47' (inside CNV for refueling)
E	581 (surface of MS piping)	<(-14.6) ⁽²⁾	0	3.70E7		2.00E6		47' (inside CNV for refueling)
F	295 (upper CNV volume)	<(-14.6) ⁽²⁾	0	2.47E7		1.51E6		-
G	140	0	<100	5.45E5		1.81E4		-
H	105	0	<100	above bioshield EL 145	4.50E2 2.30E3	above bioshield EL 145	4.13E3 3.06E3	-
I	140	0 plus submergence head	N/A	pool center	0	pool center (coolant only)	4.93E3	69' (normal operating level outside CNV)
				next to operating module	9.09E7	next to operating module	1.77E10	
J	105	0	<100	0		5.56E4		-
K	85	0	<100	0		5.00E1		-
L	85	0	<100	0		5.00E1		-
M	105	0	<100	0		4.30E1		-
N	105	0	<100	0		-		-

Notes:

1. Normal service relative humidity outside of the containment vessel is shown as <100%; the relative humidity inside the containment vessel is 0% because the environment is normally maintained in a vacuum.
2. The pressure inside the CNV is maintained less than the saturation pressure corresponding to the reactor pool pressure; this results in a vacuum.
3. The boron concentration in the pool areas will be nominally 1800 ppm. EPRI primary water chemistry guidelines show the pH of a pool with 1800 ppm boron concentration to be 4.75.

Table 3C-7: Design Basis Event Environmental Conditions

Zone ⁽³⁾	DBE	Temperature (°F)	DBE	Pressure (psig) ⁽²⁾	DBE	Relative Humidity (%)	Water Level (ft. above RXB pool floor)	Water Spray (pipe rupture)
A	HELB	See Figure 3C-1	HELB	979.3	All Events	100	24 (inside CNV to support ECCS operation)	-
B	HELB	See Figure 3C-1	HELB	979.3	All Events	100	24 (inside CNV to support ECCS operation)	-
C	HELB	See Figure 3C-2	HELB	979.3	All Events	100	-	Yes
D	HELB	See Figure 3C-2	HELB	979.3	All Events	100	-	Yes
E	HELB	See Figure 3C-2	HELB	979.3	All Events	100	-	Yes
F	HELB	See Figure 3C-2	HELB	979.3	All Events	100	-	Yes
G	HELB	See Figure 3C-3	HELB	1.6	All Events	100	-	Yes
H	Conditions resulting from HELB and fuel handling accident (FHA) in the pool area/top of module (TOM)	See Figure 3C-4	Conditions resulting from HELB and FHA in the pool area/TOM	1.9	Conditions resulting from HELB and FHA in the pool area/TOM	100	-	-

Table 3C-7: Design Basis Event Environmental Conditions (Continued)

Zone⁽³⁾	DBE	Temperature (°F)	DBE	Pressure (psig)⁽²⁾	DBE	Relative Humidity (%)	Water Level (ft. above RXB pool floor)	Water Spray (pipe rupture)
I	Conditions resulting from HELB and FHA in the pool area/TOM	212 ⁽¹⁾	Conditions resulting from HELB and FHA in the pool area/TOM	1.9 (Equipment located below water level will be affected by hydrostatic pressure plus atmospheric overpressure)	Conditions resulting from HELB and FHA in the pool area/TOM	N/A	75 (top of pool, not DBA condition)	-

Notes:

1. The long term pool temperature will remain at 212 degrees F due to all modules being on DHRS from a loss of power. Equipment exposed to this environment will need to be qualified at 212 degrees F for as long as the equipment is required as specified in Table 3.11-1.
2. Note 2 applies to Zones A through F only. Refer to TR-0516-49084 for the CNV pressure for the spectrum analyses of primary and secondary mass and energy releases. NRELAP5 was used for development of the pressure and temperature envelop for qualification of equipment within containment and has been shown to be equivalent to COMTEMPT-LT for this purpose.
3. DCA EQ Zones J, K, L, M, and N are preliminarily designated as harsh environments in the RXB because these areas contain high or moderate energy piping. Additionally, Zone J is harsh due to post-accident radiological equipment qualification exceeding source term doses > 1.0E4 Rads (60 year normal + 30 day accident dose) for electrical or mechanical equipment. Zone M is harsh due to post-accident radiological equipment qualification requirements exceeding source term doses of > 1.0E3 Rads (60 year normal + 30 day accident dose) for equipment with solid state circuitry.
4. The CNV post-accident pH for any postulated accident that results in core damage is 6.9 at 1000 ppm boron concentration and 8.3 at 200 ppm boron concentration. These values remain essentially unchanged between 25C and 200C.

Table 3C-8: Limiting Design Basis Accident EQ Radiation Dose

Zone	Dose	Accident Integrated Dose (rads)				
		1 hour	36 hours	72 hours	720 hours	2400 hours
A	Integrated β	6.40E02	8.89E03	1.23E04	2.59E04	2.82E04
	Integrated γ	2.09E03	2.10E04	2.78E04	6.55E04	8.84E04
B	Integrated β	6.40E02	8.89E03	1.23E04	2.59E04	2.82E04
	Integrated γ	2.09E03	2.10E04	2.78E04	6.55E04	8.84E04
C	Integrated β	2.91E05	4.38E06	6.38E06	2.00E07	3.94E07
	Integrated γ	8.96E05	9.07E06	1.20E07	2.85E07	3.84E07
D	Integrated β	2.91E05	4.38E06	6.38E06	2.00E07	3.94E07
	Integrated γ	8.96E05	9.07E06	1.20E07	2.85E07	3.84E07
E	Integrated β	2.91E05	4.38E06	6.38E06	2.00E07	3.94E07
	Integrated γ	8.96E05	9.07E06	1.20E07	2.85E07	3.84E07
F	Integrated β	2.91E05	4.38E06	6.38E06	2.00E07	3.94E07
	Integrated γ	8.96E05	9.07E06	1.20E07	2.85E07	3.84E07
G	Integrated β	7.58E01	3.13E03	6.28E03	9.58E04	6.33E05
	Integrated γ	7.27E03	7.71E04	1.05E05	3.34E05	6.66E05
H	Integrated β	5.50E01	1.69E03	2.99E03	1.56E04	2.48E04
	Integrated γ	7.65E01	2.32E03	4.08E03	2.22E04	3.95E04
I	Integrated β	6.40E00	1.60E02	2.69E02	1.80E03	4.75E03
	Integrated γ	1.94E01	5.78E02	1.02E03	7.89E03	2.25E04
J	Integrated β	-	-	-	-	-
	Integrated γ	6.17E02	1.24E04	1.71E04	3.95E04	5.39E04
K	Integrated β	-	-	-	-	-
	Integrated γ	1.56E-02	3.00E-01	3.73E-01	4.74E-01	4.76E-01
L	Integrated β	-	-	-	-	-
	Integrated γ	1.56E-02	3.00E-01	3.73E-01	4.74E-01	4.76E-01
M	Integrated β	-	-	-	-	-
	Integrated γ	3.60E01	6.81E02	8.94E02	1.85E03	2.63E03
N	Integrated β	-	-	-	-	-
	Integrated γ	2.78E-04	5.70E-03	7.00E-03	7.00E-03	7.00E-03

Figure 3C-1: Containment Liquid Space Metal and Liquid Temperatures with Bounding Curve (Zones A and B)




Figure 3C-2: Containment Vapor Space Metal and Gas Temperatures with Bounding Curve (Zones C, D, E, and F)




Figure 3C-3: Bounding Envelope for Average Vapor Temperature at Top of Module (Zone G)




Figure 3C-4: Bounding Envelope for Maximum Vapor Temperatures at Reactor Building EI 145'-0 (Zone H)

