TRANSMITTAL OF MEETING HANDOUT MATERIALS FOR IMMEDIATE PLACEMENT IN THE PUBLIC DOMAIN

This form is to be filled out (typed or hand-printed) by the person who announced the meeting (i.e., the person who issued the meeting notice). The completed form, and the attached copy of meeting handout materials, will be sent to the Document Control Desk on the same day of the meeting; under no circumstances will this be done later than the working day after the meeting.

Do not include proprietary materials.			
12/16/2002	The attached document(s), which was/were handed out in this meeting, is/are to be placed in the public domain as soon as possible. The minutes of the meeting will be issued in the near future. Following are administrative details regarding this meeting:		
	Docket Number(s)	Proj 689	
	Plant/Facility Name	_	
	TAC Number(s) (if available)		
	Reference Meeting Notice	12/9/02	
	Purpose of Meeting (copy from meeting notice)	Westinghouse will provide an overview of the	
		construction scheduling techniques that they intend	
		to u	se for new reactor construction to NRR management
NAME OF PERSON WHO ISSUED MEETING NOTICE			TITLE
Joseph Sebrosky			Senior Project Manager
OFFICE			
NRR			
DIVISION			
NRLPO			
BRANCH			
Distribution of this form and attachments: Docket File/Central File PUBLIC Docket File/Central File			

CONSTRUCTION SCHEDULING SOFTWARE AND TECHNIQUES



Slide 1



Westinghouse Presenters

Presenters

- Ed Cummins
 - Director, AP600 & AP1000 Projects
 - 412-374-6211 cumminwe@westinghouse.com
- Jim Winters
 - Manager, Passive Plant Projects
 412-374-5290 winterjw@westinghouse.com

Drivers

- Jill Clelland
 - AP1000 Computer Systems
 - 412-374-4142 clellaja@westinghouse.com
- Jean-Luc Foret
 - EdF Representative for AP1000
 - 412-374-4931 foretjl@venus.pgh.wec.com





Meeting Objectives

Demontrate:

- A technique for visualizing the construction of a nuclear power plant (4D)
- A technique for more rapid construction of a nuclear power plant (modularization)

Answer:

- Your questions on the techniques



Slide 3



Background

- 3D plant model is AP1000, based on AP600
- Schedule is for AP1000, based on AP600
- Demonstration of 4D is live
- Development of the 4D technique was supported by EPRI, Intergraph and BNFL

BNFL



AP1000 Primavera Standard Construction Schedule

- Prepared in Primavera
- Prepared by MK Ferguson, now Washington Group
- Prepared in parallel with AP600 design
- Includes activities from site selection through plant turn over
- Currently on Primavera P3, version 3.1
- One Standard Schedule with custom variants



slide 5



AP1000 Primavera Standard Construction Schedule

- Logic Based
- Durations established by constructors
- 5 10 hour days per week
- Inspections and setup on back shifts
- Modular construction approach
- Nth plant 5 year overall, 18-36-6
- 5700+ activities
- About "Level 3"



lide 6



AP1000 Primavera Standard Construction Schedule Construction Activities

- Smallest time increment = 1 day
- Smallest work group = 1 crew
- Standard US (Westinghouse) calendar
- Real time activities (concrete curing, for example) modified to reflect work calendar
- Most activity codes used
- Subschedules integrated by logic



Slide 7




AP1000 Primavera Standard Construction Schedule Current Subschedules


- Licensing
- Procurement
- Engineering
- Yard and Site Preparation
- Nuclear Island Areas
- Nuclear Island Containment
- Nuclear Island Auxiliary Building
- Annex Building
- Turbine Building
- Diesel Building
- Radwaste Building
- Test and Startup























AP1000 Plant Design in 3D


- Intergraph PDS
- Intergraph Smart Plant Review
- Entire AP600 in 3D
- AP1000 is the same (almost) as AP1000
- Entire AP1000 is in 3D
- Nuclear island is used for 4D Critical Path

BNFL

de 16



AP1000 - 3D Model



BNFL

lide 17



AP1000 Virtual Construction

- Intergraph Smart Plant Review
- Schedule Accessory
- PDS or MicroStation models are attached to selected activities from the Primavera schedule

BNFL



Schedule & Model Integration

Intergraph Smart Plant Review product Primavera Project Planner Continuing interactions with software vendor PDS model boundaries modified to match schedule activities Link 3D model to schedule activity Activity construction durations maintained Schedule improvements by logic changes only Visualization capability for changing activity sequences












Slide 19



Model Linked to Schedule BNFL Westinghouse







Other Benefits for the Designer/Constructor

- In addition to sequence review we can review:
 - activity environment
 - lifting and handing constraints
 - crane assignments
 - physical interactions between activities
 - general worker flow



Regulatory Interface

- Modularization changes the interface and schedule of activities between NRC and the applicant/constructor
- 4D changes our perception of the interface
- The new interface must be discussed:
 - provide efficient review
 - protect detailed vendor information
 - enhance common understanding of goals and limits
 - minimize duplication of information and software
- For AP1000 3D model is a design tool not a design deliverable



lide 25



